

SCHEDULE OF QUANTITIES

F.A.R. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
30L	2LT-1	STEPHENSON	64	11
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

50100300 REMOVAL OF EXISTING STRUCTURE NO.1

EACH	LOCATION	OFFSET
1	374+84.6	
1	TOTAL	

REMARKS
12' X 7' Box Culvert

50100400 REMOVAL OF EXISTING STRUCTURE NO.2

EACH	LOCATION	OFFSET
1	385+50	
1	TOTAL	

REMARKS
3' X 2' Box Culvert

50200400 ROCK EXCAVATION FOR STRUCTURES

CY	LOCATION	OFFSET
50	374+85	
50	TOTAL	

REMARKS
USE IF APPLICABLE

54205470 PIPE CULVERTS, CLASS D, TYPE I, EQUIVALENT ROUND-SIZE 15"

FOOT	LOCATION	TO	OFFSET
60	370+58	371+18	LT
60	TOTAL		

REMARKS
FE

54214290 END SECTIONS, EQUIVALENT ROUND-SIZE 15"

EACH	LOCATION	OFFSET
1	370+58	LT
1	371+18	LT
2	TOTAL	

REMARKS
FE

61100500 EXPLORATION TRENCH 52" DEPTH

FOOT	LOCATION	TO	OFFSET
100	374+35	375+35	LT
100	374+35	375+35	RT
50	385+25	385+75	LT
50	385+25	385+75	RT
300	TOTAL		

REMARKS

63200310 GUARDRAIL REMOVAL

FOOT	LOCATION	TO	OFFSET
85	374+40	375+25	RT
250	374+40	376+80	LT
65	385+08	385+73	RT
65	385+25	385+90	LT
465	TOTAL		

REMARKS
Inside curve
Outside Curve

63500105 DELINEATORS

EACH	LOCATION	OFFSET
2	374+84.6	LT & RT
2	TOTAL	

REMARKS

66600105 FURNISHING AND ERECTING RIGHT OF WAY MARKERS

EACH	LOCATION	OFFSET
1	372+00	33' LT
1	372+00	33' RT
1	374+00	65' RT
1	374+34	105.41' LT
1	377+00	60' RT
1	378+00	60' RT
1	389+00	60' RT
1	390+00	33' RT
8	TOTAL	

REMARKS

66700305 PERMANENT SURVEY MARKERS, TYPE II

EACH	LOCATION	OFFSET
2	ENTIRE JOB	
2	TOTAL	

REMARKS

70106700 TEMPORARY RUMBLE STRIP

EACH	LOCATION	OFFSET
1	339+60.9	
1	344+60.9	
1	349+60.9	
1	354+60.9	
1	359+60.9	
1	364+60.9	
1	385+08.3	
1	390+08.3	
1	395+08.3	
1	400+08.3	
1	405+08.3	
1	410+08.3	
12	TOTAL	

REMARKS

70106800 CHANGEABLE MESSAGE SIGN

CAL. MO.	LOCATION	OFFSET
1	BEGINNING OF PROJECT	
1	END OF PROJECT	
2	TOTAL	

REMARKS

70300100 SHORT-TERM PAVEMENT MARKING

FOOT	LOCATION	TO	OFFSET
57	371+73.5	377+45.2	CL
330	373+00.0	389+50.0	RT & LT
387	TOTAL		

70300520 PAVEMENT MARKING TAPE, TYPE III 4"

FOOT	LOCATION	TO	OFFSET
627.3	371+70.9	377+98.2	RT
350.0	373+00.0	376+50.0	LT
626.9	371+71.2	377+98.1	LT
400.0	373+00.0	377+00.0	RT
2004.2	TOTAL		

REMARKS
STAGE I (WHITE)
STAGE I (WHITE)
STAGE II (WHITE)
STAGE II (WHITE)

70300570 PAVEMENT MARKING TAPE, TYPE III 24"

FOOT	LOCATION	TO	OFFSET
12	371+61.2		RT
12	378+08.0		LT
24	TOTAL		

REMARKS

70301000 WORK ZONE PAVEMENT MARKING REMOVAL

SO FT	LOCATION	OFFSET
431.6	Stage I	
342.3	Stage II	
48.0	Stop Bars	
821.9	TOTAL	

REMARKS

70400100 TEMPORARY CONCRETE BARRIER

FOOT	LOCATION	TO	OFFSET
275	373+47	376+22	
275	TOTAL		

REMARKS
STAGE I

70400200 RELOCATE TEMPORARY CONCRETE BARRIER

FOOT	LOCATION	TO	OFFSET
275	373+48	376+22	
275	TOTAL		

REMARKS
STAGE II

78001110 PAINT PAVEMENT MARKING - LINE 4"

FOOT	LOCATION	TO	OFFSET
7600	370+50	389+50	RT & LT
2520	370+50	376+80	CL
636	376+80	389+50	CL
10756	TOTAL		

REMARKS
white edge lines (2 applications)
Double Yellow (2 applications)
yellow skip dash (2 applications)

78100100 RAISED REFLECTIVE PAVEMENT MARKER

EACH	LOCATION	OFFSET
1	374+85	
1	385+50	
2	TOTAL	

REMARKS

78300100 PAVEMENT MARKING REMOVAL

SO FT	LOCATION	TO	OFFSET
431.6	371+60.9	378+08.3	CL
116.7	373+00.0	376+50.0	LT
133.3	37+00.0	377+00.0	RT
681.6	TOTAL		

REMARKS
STAGE I - Double Yellow
STAGE I - white edge line
STAGE II - white edge line

78300200 RAISED REFLECTIVE PAVEMENT MARKER REMOVAL

EACH	LOCATION	OFFSET
1	374+84.6	
1	385+50	
2	TOTAL	

REMARKS

Z0005400 BREAKER-RUN CRUSHED STONE

TON	LOCATION	OFFSET
108.4	374+84.6	
108.4	TOTAL	

REMARKS
(12") 17'x 84' UNDER CULVERT & END SECTIONS

PLOT DATE : Tue Jan 16 10:58:12 2007
 FILE NAME : c:\projects\1105\1105.dgn
 REFERENCE : REF1