

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*754	101M&TS	BOONE	95	7
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS FED. AID PROJECT		

*(IL 76)

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	1000-1A	Y031-1F
				90% FED / 10% STATE	90% FED / 5% STATE / 5% TOWNSHIP
70106800	CHANGEABLE MESSAGE SIGN	CAL MD	4	4	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1,463	1,463	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	248	248	
* 72000100	SIGN PANEL - TYPE 1	SQ FT	12		12
* 72000200	SIGN PANEL - TYPE 2	SQ FT	32.5		32.5
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	281	281	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	19,704	19,704	
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	1,893	1,893	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	619	619	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	132	132	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	216	216	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	35	35	
* 80501000	SERVICE INSTALLATION (SPECIAL)	EACH	1		1
81400700	HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	3		3
81400720	DOUBLE HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	1		1
81702110	ELECTRIC CABLE IN CONDUIT, 600V OLP-TYPE USE1 1/C NO. 10	FOOT	1,358		1,358
82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	4		4
* 82500605	LIGHTING CONTROLLER PHOTOCELL RELAY	EACH	1		1
* 85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1		1
* 86200200	UNINTERRUPTABLE POWER SUPPLY, STANDARD	EACH	1		1
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	377		377
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	1,013		1,013
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	2,190		2,190
87301815	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 3C	FOOT	21		21
87502470	TRAFFIC SIGNAL POST, GALVANIZED STEEL 13 FT.	EACH	1		1
87702920	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 38 FT.	EACH	1		1
87702930	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 40 FT.	EACH	1		1
87702940	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 42 FT.	EACH	1		1
87703000	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 55 FT.	EACH	1		1
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	6		6
87800150	CONCRETE FOUNDATION, TYPE C	FOOT	3		3
87800400	CONCRETE FOUNDATION, TYPE E - 30-INCH DIAMETER	FOOT	15.5		15.5
87800415	CONCRETE FOUNDATION, TYPE E - 36-INCH DIAMETER	FOOT	46.75		46.75
88040090	SIGNAL HEAD POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	6		6

* SPECIALTY ITEM

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		<p>FAP ROUTE 754 (IL 76) SECTION 101M&TS BOONE COUNTY</p>
SCALE: VERT.	DRAWN BY	CHECKED BY
HORIZ.	DATE	

SUMMARY OF QUANTITIES

PLOT DATE = Fri, Dec 08 09:43:28 2006
 FILE NAME = c:\p\project\2006\06\08106\summary.dgn
 USER NAME = polstray