

SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
754	101M&TS	BOONE	95	13
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

*(IL 76)

20101000 TEMPORARY FENCE

FOOT	LOCATION	REMARKS
IL 76		
18.8	LT Sta 62+ 70	47.7' LT o/s
18.8	LT Sta 63+ 77	47.2' LT o/s
Squaw Prairie Road		
31.4	LT Sta 234+ 96.5	44.8' LT o/s
31.4	LT Sta 237+ 27.5	61.7' LT o/s
100	TOTAL	

25000400 NITROGEN FERTILIZER NUTRIENT

POUND	LOCATION	REMARKS
IL 76/Squaw Prairie Road		
83.7	RT Sta 63+ 58 - 247+ 00	LT NE Quad - Perm Seeding
112.8	RT Sta 229+ 89 - 44+ 30	LT SW Quad - Perm Seeding
111.7	RT Sta 44+ 30 - 247+ 00	RT SE Quad - Perm Seeding
71.8	LT Sta 229+ 89.48 - 63+ 58	LT NW Quad - Sodding
380	TOTAL	

25000600 POTASSIUM FERTILIZER NUTRIENT

POUND	LOCATION	REMARKS
IL 76/Squaw Prairie Road		
83.7	RT Sta 63+ 58 - 247+ 00	LT NE Quad - Perm Seeding
112.8	RT Sta 229+ 89 - 44+ 30	LT SW Quad - Perm Seeding
111.7	RT Sta 44+ 30 - 247+ 00	RT SE Quad - Perm Seeding
71.8	LT Sta 229+ 89.48 - 63+ 58	LT NW Quad - Sodding
380	TOTAL	

20101700 SUPPLEMENTAL WATERING

UNIT	LOCATION	REMARKS
IL 76/Squaw Prairie Road		
34.8	LT Sta 229+ 89.48 - 63+ 58	LT NW Quadrant
34.8	TOTAL	

25000500 PHOSPHORUS FERTILIZER NUTRIENT

POUND	LOCATION	REMARKS
IL 76/Squaw Prairie Road		
83.7	RT Sta 63+ 58 - 247+ 00	LT NE Quad - Perm Seeding
112.8	RT Sta 229+ 89 - 44+ 30	LT SW Quad - Perm Seeding
111.7	RT Sta 44+ 30 - 247+ 00	RT SE Quad - Perm Seeding
71.8	LT Sta 229+ 89.48 - 63+ 58	LT NW Quad - Sodding
380	TOTAL	

25000750 MOWING

ACRE	LOCATION	REMARKS
IL 76/Squaw Prairie Road		
0.93	RT Sta 63+ 58 - 247+ 00	LT NE Quadrant
1.25	RT Sta 229+ 89 - 44+ 30	LT SW Quadrant
1.24	RT Sta 44+ 30 - 247+ 00	RT SE Quadrant
3.50	TOTAL	

20800150 TRENCH BACKFILL

CU YD	LOCATION	REMARKS
Squaw Prairie Road		
165	LT Sta 230+ 65 - 236+ 35	
165	TOTAL	

25100115 MULCH METHOD 2

ACRE	LOCATION	REMARKS
IL 76/Squaw Prairie Road		
0.93	RT Sta 63+ 58 - 247+ 00	LT NE Quad - Perm Seeding
1.25	RT Sta 229+ 89 - 44+ 30	LT SW Quad - Perm Seeding
1.24	RT Sta 44+ 30 - 247+ 00	RT SE Quad - Perm Seeding
3.42	TOTAL	

25000100 SEEDING CLASS 1

ACRE	LOCATION	REMARKS
IL 76/Squaw Prairie Road		
0.93	RT Sta 63+ 58 - 247+ 00	LT NE Quadrant
1.00	TOTAL	

25100630 EROSION CONTROL BLANKET

SQ YD	LOCATION	REMARKS
IL 76/Squaw Prairie Road		
4498.9	RT Sta 63+ 58 - 247+ 00	LT NE Quad - Perm Seeding
6064.3	RT Sta 229+ 89 - 44+ 30	LT SW Quad - Perm Seeding
6008.3	RT Sta 44+ 30 - 247+ 00	RT SE Quad - Perm Seeding
16,572	TOTAL	

25000210 SEEDING CLASS 2A

ACRE	LOCATION	REMARKS
IL 76/Squaw Prairie Road		
1.25	RT Sta 229+ 89 - 44+ 30	LT SW Quadrant
1.24	RT Sta 44+ 30 - 247+ 00	RT SE Quadrant
2.50	TOTAL	

25200100 SODDING

SQ YD	LOCATION	REMARKS
IL 76/Squaw Prairie Road		
3862.8	LT Sta 229+ 89.48 - 63+ 58	LT NW Quadrant
3863	TOTAL	

PLOT DATE = Thu Dec 07 14:23:33 2006
 FILE NAME = c:\nrc\psets\2280108\2280108.dgn
 PLOT SCALE = 50.0000 / IN.
 USER NAME = palzmej

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

FAP ROUTE 754 (IL 76)
SECTION 101M&TS
BOONE COUNTY

SCALE: VERT. DATE HORIZ. DRAWN BY CHECKED BY

SCHEDULE OF QUANTITIES