

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*754	101M&TS	BOONE	95	16
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS FED. AID PROJECT		

*(IL 76)

SCHEDULE OF QUANTITIES

54213675 PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"

EACH	LOCATION	REMARKS
Squaw Prairie Road		
1	LT Sta 230 + 65	360' LT. OS
1	LT Sta 236 + 35	360' LT. OS
2	TOTAL	

54214311 END SECTIONS, EQUIVALENT ROUND-SIZE 36"

EACH	LOCATION	REMARKS
IL RTE 76		
2	LT Sta 49 + 76.3	
2	LT Sta 58 + 74	
4	TOTAL	

54214521 PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 36"

EACH	LOCATION	REMARKS
Squaw Prairie Road		
2	Sta 238 + 00.8	
2	TOTAL	

54248510 CONCRETE COLLAR

CU YD	LOCATION	REMARKS
Squaw Prairie Road-West Leg		
1.15	LT Sta 238 + 00.8	AROUND EQUIV ROUND-SIZE 36" PIPE CULVERT
1.15	RT Sta 238 + 00.8	AROUND EQUIV ROUND-SIZE 36" PIPE CULVERT
2.3	TOTAL	

550A0140 STORM SEWERS, CLASS A, TYPE I 30"

FOOT	LOCATION	REMARKS
Squaw Prairie Road		
198	LT Sta 230 + 65 - 232 + 65	
166	LT Sta 232 + 65 - 234 + 35	
198	LT Sta 234 + 35 - 236 + 35	
562	TOTAL	

60242700 INLETS, SPECIAL NO. 3

EACH	LOCATION	REMARKS
Squaw Prairie Road		
1	LT Sta 232 + 65	
1	LT Sta 234 + 35	
2	TOTAL	

60600095 CLASS SI CONCRETE (OUTLET)

CU YD	LOCATION	REMARKS
Squaw Prairie Road		
1.2	LT Sta 230 + 88 - 231 + 00	
3.2	LT Sta 236 + 00 - 236 + 35	
4.4	TOTAL	

60605000 COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24

FOOT	LOCATION	REMARKS
Squaw Prairie Road		
500	LT Sta 231 + 00 - 236 + 00	
500	TOTAL	

63500105 DELINEATORS

EACH	LOCATION	REMARKS
IL RTE 76		
2	LT Sta 49 + 76.3	EO SECTION, EQUIV ROUND-SIZE 36"
2	LT Sta 58 + 74	EO SECTION, EQUIV ROUND-SIZE 36"
2	RT Sta 62 + 88.4	EO SECTION 8'
Squaw Prairie Road		
1	LT Sta 230 + 65	FFC FLARED EO SECTION 30"
1	LT Sta 236 + 35	FFC FLARED EO SECTION 30"
1	LT Sta 238 + 00.8	FFC EO SECTION, EQUIV. ROUND-SIZE 36"
1	RT Sta 238 + 00.8	FFC EO SECTION, EQUIV. ROUND-SIZE 36"
1	LT Sta 240 + 27.82	FFC FLARED EO SECTION 24"
1	RT Sta 240 + 27.82	FFC FLARED EO SECTION 24"
2	RT Sta 241 + 68.6	EO SECTION 24"
2	LT Sta 241 + 86.9	EO SECTION 24"
2	LT Sta 244 + 26.8	EO SECTION 24"
18	TOTAL	

PLT DATE = Thu Dec 07 14:13:24 2006
 USER NAME = polzinej
 PLT SCALE = 5000000 / IN
 USER NAME = polzinej

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
FAP ROUTE 754 (IL 76)
SECTION 101M&TS
BOONE COUNTY

SCALE: VERT. _____
 HORIZ. _____
 DATE _____ DRAWN BY _____
 CHECKED BY _____