

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*754	101M&TS	BOONE	95	17
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS	FED. AID PROJECT	

SCHEDULE OF QUANTITIES

66600105 FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS

EACH	LOCATION	OFFSET (FEET)
IL RTE 76		
1	LT Sta 44+ 00	50.4
1	RT Sta 44+ 00	499
1	LT Sta 45+ 00	700
1	RT Sta 45+ 00	700
1	LT Sta 48+ 00	750
1	RT Sta 49+ 00	800
1	RT Sta 50+ 00	850
1	LT Sta 51+ 00	850
1	RT Sta 52+ 00	850
1	LT Sta 52+ 62.43	850
1	RT Sta 54+ 25	850
1	LT Sta 54+ 50	700
1	LT Sta 55+ 00	602
1	RT Sta 55+ 00	800
1	RT Sta 63+ 00	800
1	RT Sta 64+ 00	454
Squaw Prairie Road		
1	RT Sta 229+ 00	2783
1	RT Sta 231+ 00	400
1	LT Sta 231+ 00	2892
1	RT Sta 233+ 00	5000
1	LT Sta 233+ 50	3500
1	LT Sta 235+ 00	3500
1	LT Sta 236+ 50	6000
1	RT Sta 236+ 99.76	499
1	LT Sta 238+ 00	6500
1	LT Sta 240+ 00	7500
1	RT Sta 240+ 50	7000
1	RT Sta 242+ 50	7000
1	RT Sta 246+ 00	5000
1	LT Sta 246+ 00	5000
1	RT Sta 247+ 00	2692
1	LT Sta 247+ 00	2703
32	TOTAL	

78000100 THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS

SO. FT.	LOCATION	REMARKS
IL RTE 76		
93.6	Sta 50+ 07.51 - 52+ 71.10	"Right & Left Turn Arrows"
93.6	Sta 54+ 16.44 - 56+ 79.75	"Right & Left Turn Arrows"
Squaw Prairie Road		
46.8	Sta 235+ 63.69 - 238+ 18.72	"Left Turn Arrows"
46.8	Sta 239+ 83.57 - 241+ 28.65	"Left Turn Arrows"
281	TOTAL	

78000200 THERMOPLASTIC PAVEMENT MARKING - LINE 4"

FOOT	LOCATION	REMARKS
IL RTE 76		
500.0	RT Sta 40+ 07.51 - 45+ 07.51	Yellow No Pass
3138.4	Sta 45+ 07.51 - 52+ 91.10	Median - Double Yellow No Pass
3478.2	Sta 53+ 96.21 - 62+ 64.75	Median - Double Yellow No Pass
908.7	LT Sta 44+ 23.86 - 53+ 32.55	EOP - White
872.1	RT Sta 44+ 23.86 - 52+ 95.96	EOP - White
966.3	LT Sta 53+ 91.22 - 63+ 57.56	EOP - White
1002.8	RT Sta 53+ 54.76 - 63+ 57.56	EOP - White
Squaw Prairie Road		
3064.0	Sta 230+ 73.69 - 238+ 38.69	Median - Double Yellow No Pass
2624.0	Sta 239+ 63.65 - 246+ 18.65	Median - Double Yellow No Pass
849.2	LT Sta 229+ 89.47 - 238+ 38.69	EOP - White
849.2	RT Sta 229+ 89.47 - 238+ 38.69	EOP - White
725.3	LT Sta 239+ 63.65 - 246+ 89	EOP - White
725.3	RT Sta 239+ 63.65 - 246+ 89	EOP - White
19704	TOTAL	

78000500 THERMOPLASTIC PAVEMENT MARKING - LINE 8"

FOOT	LOCATION	REMARKS
IL RTE 76		
311.6	RT Sta 49+ 87.51 - 52+ 99.10	White Edge Line For Left/Thru Lanes
326.3	RT Sta 49+ 87.51 - 53+ 13.86	White Edge Line For Right/Thru Lanes
70.7	RT Sta 52+ 81.87 - 53+ 13.86	Island - White
326.3	LT Sta 53+ 73.49 - 56+ 99.75	White Edge Line For Right/Thru Lanes
311.5	LT Sta 53+ 88.21 - 56+ 99.75	White Edge Line For Left/Thru Lanes
70.5	LT Sta 53+ 73.49 - 54+ 05.39	Island - White
Squaw Prairie Road		
293.0	RT Sta 235+ 43.69 - 238+ 36.69	White Edge Line For Left/Thru Lanes
183.0	LT Sta 239+ 65.65 - 241+ 48.65	White Edge Line For Left/Thru Lanes
1893	TOTAL	

78000600 THERMOPLASTIC PAVEMENT MARKING - LINE 12"

FOOT	LOCATION	REMARKS
IL RTE 76		
128.7	Sta 45+ 12 - 49+ 56	Median - Yellow Diagonals
47.5	RT Sta 52+ 81.87 - 53+ 13.86	Island - White Diagonals
47.8	LT Sta 53+ 73.49 - 54+ 05.39	Island - White Diagonals
148.3	Sta 57+ 31 - 62+ 35	Median - Yellow Diagonals
Squaw Prairie Road		
124.4	Sta 231+ 03 - 235+ 17	Median - Yellow Diagonals
121.8	Sta 241+ 75 - 245+ 90	Median - Yellow Diagonals
619	TOTAL	

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

FAP ROUTE 754 (IL 76)

SECTION 101M&TS

BOONE COUNTY

SCALE: VERT. _____
 HORIZ. _____

DATE _____ DRAWN BY _____
 CHECKED BY _____

PLOT DATE = Thu, Dec 07 14:37:45 2006
 FILE NAME = c:\projects\2200100\06\060106.dgn
 PLOT SCALE = 5/8"=1'-0"
 USER NAME = palzmej