

TRAFFIC SIGNAL PLANS

CONTRACT NO. 64881

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*754	101M&TS	BOONE	95	42
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS FED. AID PROJECT		

*(IL 76)

PAY CODE	ITEM	UNIT	TOTAL
* #2001379	CONDUIT INSTALLED, 1 1/2" DIA., NON-METALLIC	FOOT	11
72000100	SIGN PANEL TYPE I	SQ FT	12
72000200	SIGN PANEL TYPE II	SQ FT	32.5
* 80501000	SERVICE INSTALLATION, (SPECIAL)	EACH	1
81400400	CONCRETE HANDHOLE	EACH	3
81400600	CONCRETE DOUBLE HANDHOLE	EACH	1
81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP TYPE USE) 1/C NO. 10	FOOT	1358
82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	4
* 82500605	LIGHTING CONTROLLER PHOTOCELL RELAY	EACH	1
* 85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1
* 86200200	UNINTERRUPTABLE POWER SUPPLY, STANDARD	EACH	1
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 2C	FOOT	377
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 5C	FOOT	1013
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 7C	FOOT	2190
87301815	ELECTRIC CABLE IN CONDUIT, SERVICE, NO 6 3C	FOOT	21
87502470	TRAFFIC SIGNAL POST, GALVANIZED STEEL, 13 FT	EACH	1
87702920	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 38 FT	EACH	1
87702930	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 40 FT	EACH	1
87702940	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 42 FT	EACH	1
87703000	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 55 FT	EACH	1
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	6
87800150	CONCRETE FOUNDATION, TYPE C	FOOT	3
87800400	CONCRETE FOUNDATION, TYPE E, 30-INCH DIAMETER	FOOT	15.5
87800415	CONCRETE FOUNDATION, TYPE E, 36-INCH DIAMETER	FOOT	46.75
88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	6
88040150	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	8
88040160	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	6
88200400	TRAFFIC SIGNAL BACKPLATE, FORMED PLASTIC	EACH	12
* X0322674	STROBE LIGHT	EACH	2
* X0323153	ELECTRIC CABLE IN CONDUIT, GROUND, NO. 6 1C (GREEN)	FOOT	421
* X0324887	CONDUIT INSTALLED, 2 1/2" DIA., NON-METALLIC	FOOT	54
* X0324888	CONDUIT INSTALLED, 4" DIA., NON-METALLIC	FOOT	315
* X0962500	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	L SUM	1
* XX003165	VIDEO CAMERA DETECTOR SYSTEM	EACH	1

PLOT DATE * Fri Dec 08 11:45:14 2006
 FILE NAME * c:\projects\2006\101M&TS\081006\ts-01.dgn
 USER NAME * pstlmj

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

F.A.P. ROUTE 754 (IL 76)

SECTION 101M&TS

BOONE COUNTY

SCALE: VERT. _____ HORIZ. _____
 DATE _____ DRAWN BY _____ CHECKED BY _____

TRAFFIC SIGNAL PLANS