

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
545	114T-1	*	118	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
* CARROLL & OGLE				

CODE	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE					
				80% FEDERAL 20% STATE ROADWAY 1000	CARROLL COUNTY 80% FEDERAL 20% STATE BOX CULVERT Y007	80% FEDERAL 20% STATE BOX CULVERT X028-2A S. N. 008-1090	80% FEDERAL 20% STATE ROADWAY 1000	OGLE COUNTY 80% FEDERAL 20% STATE BOX CULVERT Y007	80% FEDERAL 20% STATE BOX CULVERT X028-2A S. N. 071-1151
54200220	PIPE CULVERTS, CLASS D, TYPE I 15"	FOOT	50		50				
54200223	PIPE CULVERTS, CLASS D, TYPE I 18"	FOOT	111	5				106	
54200229	PIPE CULVERTS, CLASS D, TYPE I 24"	FOOT	52		52				
54205905	PIPE CULVERTS, TYPE I, CORRUGATED STEEL, EQUIVALENT ROUND-SIZE 30"	FOOT	106					106	
54207159	PIPE CULVERTS, TYPE I, REINFORCED CONCRETE-ELLIPTICAL, EQUIVALENT ROUND-SIZE 24"	FOOT	7	7					
54213453	END SECTIONS 18"	EACH	1	1					
54214719	PRECAST REINFORCED CONCRETE FLARED END SECTIONS-ELLIPTICAL EQUIVALENT ROUND-SIZE 24"	EACH	2	2					
54215550	METAL END SECTIONS 15"	EACH	2		2				
54215553	METAL END SECTIONS 18"	EACH	4					4	
54215559	METAL END SECTIONS 24"	EACH	2		2				
54248510	CONCRETE COLLAR	CU YD	1.1	1.1					
60100925	PIPE DRAINS 8"	FOOT	40		20			20	
60100935	PIPE DRAINS 10"	FOOT	20		10			10	
61100500	EXPLORATION TRENCH 52" DEPTH	FOOT	230		125			105	
61100605	MISCELLANEOUS CONCRETE	CU YD	6		3			3	
61133100	FIELD TILE JUNCTION VAULTS, 2' DIA.	EACH	6		3			3	
63200310	GUARDRAIL REMOVAL	FOOT	1227		580			647	
63500105	DELINEATORS	EACH	24		12			12	
66500105	WOVEN WIRE FENCE 4'	FOOT	100	100					
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	84		40			44	
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	6		3			3	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4		2			2	
67100100	MOBILIZATION	L SUM	1		0.5			0.5	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	0.5			0.5		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10	10					
78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	7178	3125	1080		2033	940	
78001150	PAINT PAVEMENT MARKING - LINE 12"	FOOT	62	62					
78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	30	30					
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	6		3			3	
78300500	PAINT PAVEMENT MARKING REMOVAL	SO FT	267	267					
X7013015	TRAFFIC CONTROL FOR ROAD CLOSURE	L SUM	1		0.5			0.5	
Z0005400	BREAKER-RUN CRUSHED STONE	TON	957			171		376	410
Z0013798	CONSTRUCTION LAYOUT	L SUM	1		0.5			0.5	
Z0049800	RELOCATE EXISTING SURVEY MARKERS	EACH	1		1				
Z0076800	TURF REINFORCEMENT MAT	SO YD	60	60					
X0325666	CORRUGATED STEEL PIPE MULTIPLE END SECTIONS (DOUBLE) EQUIVALENT ROUND-SIZE 30"	EACH	2					2	

* SPECIALTY ITEM

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		IL RTE 72 BOX CULVERT REPLACEMENTS SUMMARY OF QUANTITIES
SCALE:	VERT. HORIZ.	DRAWN BY
DATE		CHECKED BY

PLOT DATE = Fri Jan 05 13:53:45 2007
 FILE NAME = C:\Documents and Settings\kds\My Documents\12873865\MD.dgn
 PLOT SCALE = 28.0000 / IN.
 User Name = kds