

SCHEDULE OF EARTHWORK

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
545	114T-1		118	9
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
* CARROLL & OGLE				

Sta	EARTH EXCAVATION CU YD	EMBANKMENT CU YD	Excavation used in Embankment (Adj for Shrinkage) CU YD	Earthwork Balance Waste (+) or Shortage (-) CU YD
IL RTE 72				
CARROLL CO.				
24100	3	16	2	-14
24150	22	33	17	-16
24200	53	35	40	5
24250	51	40	39	-1
24300	71	61	54	-8
24350	135	103	102	-1
24400	145	123	105	-15
24450	111	91	83	-8
24500	71	39	54	15
24550	30	8	22	14
24600	6	1	5	4
24650	0	0	0	0
31000	5	2	4	2
31050	16	7	12	5
31100	29	12	22	11
31150	46	19	35	16
31200	49	20	36	16
31250	64	21	48	27
31300	149	54	112	58
31350	174	85	131	46
31400	128	67	96	29
31450	102	45	67	22
31500	68	31	51	21
31550	53	9	40	31
31600	27	0	20	20
31650	0	0	0	0
32000	12	3	9	3
32050	30	13	22	9
32100	96	41	72	30
32150	238	100	179	79
32200	281	147	211	64
32250	219	107	164	57
32300	167	45	125	81
32350	116	32	87	55
32400	78	31	59	28
32450	43	23	32	9
32500	13	8	10	2
32550	0	0	0	0
Co. Total =	2903	1469	2178	709
OGLE CO.				
3550	6	3	4	2
3600	19	12	14	2
3650	35	29	27	-2
3700	35	41	26	-14
3750	25	61	19	-42
3800	22	100	16	-84
3850	26	120	19	-100
3900	28	94	21	-73
3950	24	54	18	-36
4000	23	28	17	-10
4050	24	19	18	-1
4100	13	10	10	0
4150	0	0	0	0
11850	11	3	8	5
11900	29	10	22	11
11950	23	40	17	-23
12000	41	52	31	-21
12050	109	33	82	49
12100	184	22	138	116
12150	148	41	111	69
12200	83	64	62	-2
12250	64	62	48	-15
12300	30	61	23	-39
12350	23	40	17	-23
12400	10	10	8	-3
12450	0	0	0	0
14250	2	0	2	2
14300	13	12	10	-3
14350	17	21	12	-9
14400	24	20	18	-2
14450	165	36	123	87
14500	177	97	133	36
14550	56	98	42	-55
14600	76	36	57	21
14650	92	12	69	57
14700	94	4	70	67
14750	80	4	60	57
14800	32	3	24	21
14850	4	1	3	2
14900	0	0	0	0
Co. Total =	1867	1354	1400	46
IL 64	51.1	9.8	38.3	28.5
SHANNON RD @ IL 64	84.9	26.3	63.7	37.4
IL 72	17.5	2	13.1	11.1
SHANNON RD @ IL 72	19.9	1.8	14.9	13.1
TOTAL =	4943.4	2862.9	3708	845.1

Shrinkage Factor = 25%

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		ILL. RTE 72 BOX CULVERT REPLACEMENTS SCHEDULE OF QUANTITIES
SCALE:	VERT. HORIZ.	DRAWN BY
DATE		CHECKED BY