CONTRACT NO. 64C83

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
39	141/201	*	46	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* OGLE/ WINNEBAGO

SUMMARY OF QUANTITIES

	PAY CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	100% STATE Y032-1F OGLE COUNTY	WINNEBAGO COUNTY
	20800150	TRENCH BACKFILL	CU YD	31	31	0
*	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	29,110	20,517	8,593
*	25000210	SEEDING, CLASS 2A	ACRE	6	4	2
*	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	540	380	160
*	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	540	380	160
*	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	540	380	160
	28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	4,213	2,665	1,548
	50200400	ROCK EXCAVATION FOR STRUCTURES	CU YD	1,259.1	514.7	744.4
	60100915	PIPE DRAINS, 6"	FOOT	12	12	0
	60100925	PIPE DRAINS, 8"	FOOT	4	4	0
	61100500	EXPLORATION TRENCH 52" DEPTH	FOOT	16	16	0
	67100100	MOBILIZATION	L SUM	1	.67	.33
	67000400	ENGINEERS FIELD OFFICE, TYPE A	CAL MO	8	5	3
	70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	.67	.33
	81017515	CONDUIT IN TRENCH, 1 1/4" DIA., COILABLE NON-METALLIC CONDUIT	FOOT	50,970	20,820	30,150
	81028040	CONDUIT, BORED AND PULLED, COILABLE NON-METALLIC CONDUIT, 1 1/4"	FOOT	37,820	29,420	8,400
	XX005765	FIBER OPTIC HANDHOLE	EACH	80	51	29
	81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	16,990	6,940	10,050
	Z0020900	ESTABLISHING AND REFERENCING LAND SECTION MARKERS	EACH	97	60	37
	Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	.37	.63
	X0325690	ARMORED LOOSE TUBE ENHANCED SINGLE-MODE FIBER OPTIC CABLE-DOUBLE JACKET/SINGLE ARMOR, 96 STRAND	FOOT	442,530	294,960	147,570
	X0325700	CONDUIT ATTACHED TO BRIDGE STRUCTURE, 4", FIBERGLASS REINFORCED EPOXY, SPECIAL	FOOT	3,085	1,140	1,945

* Specialty Item

NOTE:

1. THE COILABLE NON-METALLIC CONDUIT (1-1/4") IS COMPRISED OF A HIGH DENSITY POLYETHYLENE (HDPE) AS DEFINED IN ARTICLE 1088.03(c) OF THE STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION, ADOPTED JANUARY 1, 2007.

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. HORIZ.

DATE

DRAWN BY

CHECKED BY

PLOT DATE = Mon Dec 18 16:15:52 2006
FILE NAME = P:\dpa-f\GRI\083_Quantities.dgn
PLOT SCALE = 1.000 ' / IN.
USER NAME = adcallahan