

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
623	*	LASALLE	126	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
* (34)R,DM&(X-1)RS&BR				

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE TYPE:							
				I000-2A	X171-5B	X071-2A	Y007	SFTY-1A	SFTY-1B	SFTY-1B	
				ROADWAY	SN 050-0095	SN 050-0094	STORM SEWER UPSIZE	SIDEWALK REMOVAL	DETECTABLE WARNINGS	SIDEWALK	
				80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	100% CITY	100% CITY	50% STATE 50% CITY	50% STATE 50% CITY	
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	2360	2360							
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	1784	1784							
20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	1	1							
20200100	EARTH EXCAVATION	CU YD	7433	7433							
20400800	FURNISHED EXCAVATION	CU YD	536	536							
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	173			173					
20800150	TRENCH BACKFILL	CU YD	812	812							
* 25000200	SEEDING, CLASS 2	ACRE	0.5	0.5							
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	90	90							
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	90	90							
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	90	90							
* 25100630	EROSION CONTROL BLANKET	SQ YD	2476	2476							
* 25200100	SODDING	SQ YD	3600	3600							
25200200	SUPPLEMENTAL WATERING	UNIT	11	11							
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	117	117							
28000400	PERIMETER EROSION BARRIER	FOOT	1979	1979							
28000500	INLET AND PIPE PROTECTION	EACH	10	10							
28100205	STONE RIPRAP, CLASS A3	TON	4	4							
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	703	703							
31101810	SUB-BASE GRANULAR MATERIAL, TYPE B 12"	SQ YD	4032	4032							
35101400	AGGREGATE BASE COURSE, TYPE B	TON	450	450							
35400400	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 9"	SQ YD	198	198							
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	75	75							
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1904	1904							
40600300	AGGREGATE (PRIME COAT)	TON	7	7							
40600535	LEVELING BINDER (HAND METHOD), N70	TON	2	2							
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	162	162							
40600895	CONSTRUCTING TEST STRIP	EACH	2	2							
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	167	167							
40600990	TEMPORARY RAMP	SQ YD	118	118							
40603080	HOT-MIX ASPHALT BINDER COURSE, IL 19.0, N50	TON	229	229							
40603235	HOT-MIX ASPHALT BINDER COURSE, IL 19.0, N70 POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL 19.0, N70	TON	1862	1862							
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	215	215							
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	539	539							
42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ YD	266	266							
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	966	966							
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	10507	10180							327
42400440	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH SPECIAL	SQ FT	210	210							

50% STATE
50% CITY

△ REVISED 2/15/07
*SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
SCALE: VERT. DRAWN BY
 HORIZ. CHECKED BY
DATE

12/18/2006 10:53:27 AM
c:\p\d\pccs\ep010\dep0118.dgn