CONTRACT NO. 66617

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
623	*	LASALLE	126	3
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* (34)R,DM&(X-1)RS&BR

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	1000-2A ROADWAY 80% FED 20% STATE	X171-5B SN 050-0095 80% FED 20% STATE	X071-2A SN 050-0094 80% FED 20% STATE	Y007 STORM SEWER UPSIZE 100% CITY	SFTY-1A SIDEWALK REMOVAL 100% CITY	SFTY-1B DETECTABLE WARNINGS 100% CITY	SFTY-1B SIDEWALK 50% STATE 50% CITY
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	2360	2360						
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	1784	1784						
20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	1	1						
20200100	EARTH EXCAVATION	CU YD	7433	7433						
20400800	FURNISHED EXCAVATION	CU YD	536	536						
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	173			173				
20800150	TRENCH BACKFILL	CU YD	812	812						
* 25000200	SEEDING, CLASS 2	ACRE	0.5	0.5						
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	90	90						
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	90	90						
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	90	90						
* 25100630	EROSION CONTROL BLANKET	SQ YD	2476	2476						
* 25200100	SODDING	SQ YD	3600	3600						
25200200	SUPPLEMENTAL WATERING	UNIT	11	11						
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	117	117						
28000400	PERIMETER EROSION BARRIER	FOOT	1979	1979						
28000500	INLET AND PIPE PROTECTION	EACH	10	10						
28100205	STONE RIPRAP, CLASS A3	TON	4	4						
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	703	703						
31101810	SUB-BASE GRANULAR MATERIAL, TYPE B 12"	SQ YD	4032	4032						
35101400	AGGREGATE BASE COURSE, TYPE B	TON	450	450						
35400400	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 9"	SQ YD	198	198						
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	75	75						
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1904	1904						
40600300	AGGREGATE (PRIME COAT)	TON	7	7						
40600535	LEVELING BINDER (HAND METHOD), N70	TON	2	2						
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	162	162						
40600895	CONSTRUCTING TEST STRIP	EACH	2	2						
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	167	167						
40600990	TEMPORARY RAMP	SQ YD	118	118						
40603080	HOT-MIX ASPHALT BINDER COURSE, IL 19.0, N50	TON	229	229						
40603235	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL 19.0, N70	TON	1862	1862						
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	215	215						
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	539	539						
42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ YD	266	266						
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	966	966						
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	10507	10180						327
42400440	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH SPECIAL	SQ FT	210	210						

*SPECIALTY ITEMS

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. HORIZ.

DATE

DRAWN BY

CHECKED BY

12/18/2006 10:53:27 AM
c:\pro/aers\60170\defaults.dgn