CONTRACT NO. 66617

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
623	*	LASALLE	126	4
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* (34)R,DM&(X-1)RS&BR

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	SN 050-0095	SN 050-0094	STORM SEWER UPSIZE	SIDEWALK REMOVAL	DETECTABLE WARNINGS	SIDEWALK
	CONSTRUCTION CODE TYPE:			1000-2A	X171-5B	X071-2A	Y007	SFTY-1A	SFTY-1B	SFTY-1B
				80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	100% CITY	100% CITY	100% CITY	50% STATE 50% CITY
42400500	PORTLAND CEMENT CONCRETE SIDEWALK, SPECIAL	SQ FT	969							969
42400800	DETECTABLE WARNINGS	SQ FT	150	75					75	
44000100	PAVEMENT REMOVAL	SQ YD	4629	4629						
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	995	995						
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	2221	2221						
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	580	580						
44000300	CURB REMOVAL	FOOT	979	979						
44000400	GUTTER REMOVAL	FOOT	456	456						
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1163	1163						
44000600	SIDEWALK REMOVAL	SQ FT	8367	8088				279		
44004250	PAVED SHOULDER REMOVAL	SQ YD	231	231						
44201765	CLASS D PATCHES, TYPE II 10 INCH	SQ YD	57	57						
44201769	CLASS D PATCHES, TYPE III 10 INCH	SQ YD	55	55						
44201803	CLASS D PATCHES, TYPE II 13 INCH	SQ YD	26	26						
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	273	273						
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1					
50102400	CONCRETE REMOVAL	CU YD	61.2			61.2				
50104600	CONCRETE RETAINING WALL REMOVAL	FOOT	716	716						
50104720	REMOVAL OF EXISTING CONCRETE DECK	EACH	1			1				
50105210	REMOVE EXISTING CULVERTS	FOOT	61	61						
50200100	STRUCTURE EXCAVATION	CU YD	309			309				
50300100	FLOOR DRAINS	EACH	10			10				
50300225	CONCRETE STRUCTURES	CU YD	70.2			70.2				
50300255	CONCRETE SUPERSTRUCTURE	CU YD	356.3			356.3				
50300260	BRIDGE DECK GROOVING	SQ YD	930			930				
50300280	CONCRETE ENCASEMENT	CU YD	3.2			3.2				
50300300	PROTECTIVE COAT	SQ YD	1210			1210				
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	88			88				
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1			1				
50500505	STUD SHEAR CONNECTORS	EACH	3984			3984				
50500715	JACK AND REMOVE EXISTING BEARINGS	EACH	10			10				
50501110	STRUCTURAL STEEL REMOVAL	POUND	3460			3460				
50600600	CLEANING AND PAINTING STEEL BRIDGE NO. 1	L SUM	1			1				
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	102,570			102,570				
50606401	CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES NO. 1	L SUM	1			1				
50800515	BAR SPLICERS	EACH	1799			1799				
50900605	HANDRAIL REMOVAL	FOOT	788.5	788.5						
50901720	BICYCLE RAILING	FOOT	457	168		289				
50901750	PARAPET RAILING	FOOT	289			289				
51100300	SLOPE WALL 6 INCH	SQ YD	142			142				
51201600	FURNISHING STEEL PILES HP 12X53	FOOT	325			325				
51202305	DRIVING PILES	FOOT	325			325				

*SPECIALTY ITEMS

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. HORIZ.

DATE

DRAWN BY

CHECKED BY

12/18/2006 10:54:11 AM
c:\projects\80170\details.dgn