

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
623	*	LASALLE	126	5
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
* (34)R,DM&X-1RS&BR				

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE TYPE:							
				I000-2A	X171-5B	X071-2A	Y007	SFTY-1A	SFTY-1B	SFTY-1B	
				ROADWAY	SN 050-0095	SN 050-0094	STORM SEWER UPSIZE	SIDEWALK REMOVAL	DETECTABLE WARNINGS	SIDEWALK	
				80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	100% CITY	100% CITY	100% CITY	50% STATE 50% CITY	
51203600	TEST PILE STEEL HP 12X53	EACH	1				1				
51205200	TEMPORARY SHEET PILING	SO FT	3274	2743			531				
51500100	NAME PLATES	EACH	1				1				
52000110	PREFORMED JOINT STRIP SEAL	FOOT	38				38				
52000325	NEOPRENE EXPANSION JOINT 2 1/2"	FOOT	38				38				
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	6				6				
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	6				6				
52100520	ANCHOR BOLTS, 1"	EACH	60				60				
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	1	1							
54213699	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 54"	EACH	1	1							
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	254	254							
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	13	13							
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	47	47							
550A0110	STORM SEWERS, CLASS A, TYPE 1 21"	FOOT	52	52							
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	9	9							
550A0190	STORM SEWERS, CLASS A, TYPE 1 48"	FOOT	254	190.5			63.5				
550A0200	STORM SEWERS, CLASS A, TYPE 1 54"	FOOT	360	241			119				
550A0320	STORM SEWERS, CLASS A, TYPE 2 8"	FOOT	19	19							
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	39	39							
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	17	17							
550A0430	STORM SEWERS, CLASS A, TYPE 2 30"	FOOT	44	44							
550A0480	STORM SEWERS, CLASS A, TYPE 2 48"	FOOT	196	147			49				
550A0490	STORM SEWERS, CLASS A, TYPE 2 54"	FOOT	340	228			112				
550A2630	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 54"	FOOT	24	16			8				
55100300	STORM SEWER REMOVAL 8"	FOOT	194	194							
55100500	STORM SEWER REMOVAL 12"	FOOT	613	613							
55100900	STORM SEWER REMOVAL 18"	FOOT	48	48							
* 56106300	ADJUSTING WATER MAIN 6"	FOOT	10	10							
56109210	WATER VALVES TO BE ADJUSTED	EACH	5	5							
* 56300300	ADJUSTING WATER SERVICE LINES	FOOT	165	165							
* 56400300	FIRE HYDRANTS TO BE ADJUSTED	EACH	1	1							
58700300	CONCRETE SEALER	SO FT	24				24				
59000200	EPOXY CRACK INJECTION	FOOT	28				28				
59100100	GEOCOMPOSITE WALL DRAIN	SO YD	66				66				
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	80				80				
60221200	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 3 FRAME AND GRATE	EACH	1	1							
60222240	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	1	1							
60223700	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1	1							

\*SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

## SUMMARY OF QUANTITIES

SCALE: VERT. \_\_\_\_\_  
 DATE \_\_\_\_\_ HORIZ. \_\_\_\_\_

DRAWN BY \_\_\_\_\_  
 CHECKED BY \_\_\_\_\_