CONTRACT NO. 66617

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
623	*	LASALLE	126	6
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* (34)R,DM&(X-1)RS&BR

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	SN 050-0095	SN 050-0094	STORM SEWER UPSIZE	SIDEWALK REMOVAL	DETECTABLE WARNINGS	SIDEWALK
	CONSTRUCTION CODE TYPE:			I000-2A	X171-5B	X071-2A	Y007	SFTY-1A	SFTY-1B	SFTY-1B
				80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	100% CITY	100% CITY	100% CITY	50% STATE 50% CITY
60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	11	11						
60223810	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 3 FRAME AND GRATE	EACH	1	1						
60224445	MANHOLES, TYPE A, 7'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1	1						
60224446	MANHOLES, TYPE A, 7'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2						
60224447	MANHOLES, TYPE A, 7'-DIAMETER, TYPE 3 FRAME AND GRATE	EACH	1	1						
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	7	7						
60240220	INLETS, TYPE B, TYPE 3 FRAME AND GRATE	EACH	4	4						
60240328	INLETS, TYPE B, TYPE 24 FRAME AND GRATE	EACH	2	2						
60255500	MANHOLES TO BE ADJUSTED	EACH	15	15						
60500040	REMOVING MANHOLES	EACH	1	1						
60500050	REMOVING CATCH BASINS	EACH	12	12						
60500060	REMOVING INLETS	EACH	2	2						
60600605	CONCRETE CURB, TYPE B	FOOT	20	20						
60601005	CONCRETE CURB, TYPE B (SPECIAL)	FOOT	42	42						
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	12	12						
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	3042	3042						
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	250	250						
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4						
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	2	2						
* 63100169	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)	EACH	2	2						
63200310	GUARDRAIL REMOVAL	FOOT	756	756						
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8	8						
67100100	MOBILIZATION	L SUM	1	0.8		0.2				
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1						
70101205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321 (SPECIAL)	EACH	1	1						
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1						
70102550	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	1	1						
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1						
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1						
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	75	75						
* 70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1						
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	479	479						
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	31.2	31.2						
70300220	TEMPORARY PAVEMENT MARKING LINE 4"	FOOT	4702	4702						
70300260	TEMPORARY PAVEMENT MARKING LINE 12"	FOOT	106	106						
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	972	972						
70300570	PAVEMENT MARKING TAPE, TYPE III 24"	FOOT	79	79						
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2,275	2,275						

*SPECIALTY ITEMS

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. HORIZ.

DATE

DRAWN BY

CHECKED BY

12/18/2006 10:51:23 AM
c:\projects\p0170\der015.dgn