CONTRACT NO. 66617

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
623	*	LASALLE	126	12
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* (34)R,DM&(X-1)RS&BR

TREE REMOVAL / TREE PRUNING

LOCATION	6 - 15 UNITS DIAMETER 6	7	8	9	10	11	12	13	14	15	OVER 15 DIAMETER 16	17	18	19	20	21	22	23	24	25	27	30	32	36	TREE PRUNING OVER 10" DIA EACH
1026+21.4, 57.6' RT									1																
1026+65.8, 51.2' LT							1																		
1026+66.4, 88.3' LT																						1			
1026+87.8, 50.9' RT																								1	
1027+09.6, 26.5' LT							1																		
1027+13.3, 22' LT									1																
1027+15.2, 21.4' LT					1																				
1027+19.3, 22.9' LT											1														
1027+25.1, 22.9' LT					1																				
1027+32.4, 24.8' LT																			1						
1027+35.5, 41' LT													1												
1027+38.6, 30.3' LT					1																				
1029+53.3, 49.8' LT																						1			
1029+88, 49' RT																									1
1030+90.8, 33.5' LT			1																						
1031+06.7, 33.6' LT			1																						
1031+17.4, 38.3' LT			1																						
1031+28.2, 38.6' LT			1																						
1032+29, 34.8' LT	1																								
1032+56.5, 37.2 LT	1																								
1033+66.6, 30.1 LT											1														
TODD STREET (NORTH)																									
NO. OF TREES	8	4	4	2	1	1	1		2	1	1							1	1						
BUCK STREET (SOUTH)																									
NO. OF TREES		1	2	1	1	1	2		2	1					1							1	1		
AT SN 050-0094																									
NORTHWEST QUADRANT																									
NO. OF TREES	15	6	10	3	5	4	6	4	4	4	2	1	4	1	2	2	3		3		1	1	2		
NORTHEAST QUADRANT																									
NO. OF TREES	13	7	6	7	4	3	8	1	2	2	1	2	4	1	1	1		2		2		1			
SOUTHWEST QUADRANT																									
NO. OF TREES	18	6	5	6	3	4	7	4	3	2	1	3	2	1	3	1	2	1	1	3	2			1	
SOUTHEAST QUADRANT																									
NO. OF TREES	8	7	5	3	2	2	6		3	1		2		2		2		1	1			2			
SUBTOTALS	384	217	288	198	190	165	384	117	252	165	112	136	198	95	140	126	110	115	168	125	81	210	96	72	
TOTALS	2360										1784														1

REMOVAL ITEMS

LOCATION	SIDE	PAVEMENT REMOVAL SQ YD	STEP REMOVAL EACH	CONCRETE RETAIN WALL REMOVAL FOOT	FENCE REMOVAL FOOT	HANDRAIL REMOVAL FOOT
1023+69.5 TO 1026+33.5	RT			264		
1023+69.5 TO 1026+39.5	LT			270		
1026+58.5 (METAL)	LT		1			
1023+70 TO 1026+56.2	LT					286.2
1023+70 TO 1026+47	RT					277
1026+90.3 TO 1027+96.8	RT			106.5		
1026+92.5 TO 1027+69	RT					76.5
1027+72.6 (CONCRETE)	RT		1			
1027+76 TO 1028+17	RT					41
1027+05.7 TO 1027+81.2	LT			75.5		
1027+05.5 TO 102+88	LT					82.5
1027+91 (CONCRETE)	LT		1			
1027+95 TO 1028+20.3	LT					25.3
1022+95 TO 1026+60		1093.3				
1026+93 TO 1029+89.5		816.3				
1022+92 TO 1025+88	RT	568.3				
1022+92 TO 1026+02	LT	606				
1030+51 (WOOD)	RT				6	
1033+61 (CHAIN LINK)	LT				12	
1034+84.72 TO 1035+16		82.6				
1038+06 TO 1038+36.72		80.1				
TODD STREET						
223+70 TO 225+87		555.9				
224+92 (ORNAMENTAL)					16	
SERVICE DRIVE						
3026+57 TO 3030+00		700.7				
TEMPORARY PAVEMENT		126				
TOTALS		4629	3	716	34	788.5

WIDENING

LOCATION	PCC BSE CSE WIDEN 9" SQ YD	SUBBASE GRAN MATERIAL "B" 12' EACH
UNION STREET		
NW QUADRANT	14	42.5
SW QUADRANT	18	57.4
SE QUADRANT	16.5	32.2
NE QUADRANT (UNDER C&G)		6.8
CENTRAL STREET		
NW QUADRANT	9.6	21.6
SW QUADRANT	10.7	24
SE QUADRANT	10.3	23.6
NE QUADRANT	9.1	23.2
1031+41 TO 1034+84.72 RT	62.1	233.7
1030+43.8 TO 1031+29 LT	9.1	43
BLACKSTONE STREET		
NW QUADRANT	4.1	15.1
NE QUADRANT	2.9	14.9
1031+98 TO 1034+84.72 LT	31.6	147.7
TOTALS	198	686

PAVING

LOCATION	BIT MATLS PRIME COAT GALLON	AGG PRIME COAT TON	LEV BIND (HM) N70 TON	LEV BIND (MM) N70 TON	HMA BIND CSE IL-19.0 N70 TON	HMA SURF CSE "D" N70 TON	HMA BIND CSE IL-19.0 N50 TON	HMA SURF CSE "C" N50 TON	AGG BASE TYPE B TON	SUB GRAN MATL "B" 12" SQ YD	SUB GRAN MATL "A" 4" SQ YD	TEMP RAMP SQ YD
1019+50 TO 1022+15	84.6	2.1	0.53	59.3		88.9						32.8
1022+15 TO 1022+95 (INCLUDES UNION ST)	53.9	1.3	0.34	22.4		56.6						35.8
1022+95 TO 1023+23.4	40.4				72.5	9.1				128.1		
1023+23.4 TO 1025+65.6	383.5				687.2	85.9				1242.2		
1025+65.6 TO 1028+06	320.6				574.4	71.8				976.4		
1028+06 TO 1029+89.5	198.8				356.2	44.5				676.2		
1029+89.5 TO 1034+84.72	114.4	2.9	0.72	80.1		120.2						
1038+36.72 TO 1038+97	13.4	0.3	0.08			14						13.3
AT BUCK STREET	50.2				89.9	11.2				169.8		
AT TODD STREET	45.3				81.3	10.2				153.5		
AT CENTRAL STREET LT	6.3	0.2	0.04			8.8						7.2
AT CENTRAL STREET RT	4.1	0.1	0.03			5.7						6.4
AT BLACKSTONE STREET	8.4	0.2	0.05			11.7						9.2
TODD STREET												
223+90 TO 225+35	157.1						170.1	35.2			530.1	
225+35 TO 225+87	54.1						58.5	12.1			172.8	13.3
SERVICE DRIVE	368.7							165	450			
TOTALS	1904	7	2	162	1862	539	229	212	450	3346	703	118

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. HORIZ.

DATE

DRAWN BY

CHECKED BY

12/18/2006 10:51:06 AM
c:\projects\ep0170\details.dgn