

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
623	*	LASALLE	126	15
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
* (34)R,DM&IX-1RS&BR				

STORM SEWER SCHEDULE

LOCATION	TRENCH BACKFILL	STORM SEWERS CLASS A, TYPE 1								STORM SEWERS CLASS A, TYPE 2						STORM SEWERS RUBBER GASKET CLASS A, TYPE 2	STORM SEWERS (WATERMAIN REQUIREMENTS)		PRECAST REINFORCED CONCRETE FLARED END SECTIONS	
		12"	15"	18"	21"	24"	48"	54"	8"	12"	18"	30"	48"	54"	54"	12"	54"	18"	54"	
		CU YD	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	EACH	EACH	
1022+64.2 TO 1022+46.6 LT	14.1										17									
1022+64.2 LT TO 1022+34.7 RT	44										44									
1022+34.7 TO 1022+54.7 RT	31.5												20							
1022+54.7 TO 1022+98.7 RT	65.3												40							
*1022+56.6 41' LT									8											
**1022+54.7 28.6' RT									11											
1022+98.7 LT TO 1022+97.7 RT	11.2	55																		
1022+98.7 TO 1024+40 RT	202.3																			
1024+40 LT TO 1024+40 RT	5.3	40																		
1024+40 RT	1.3	5																		
1024+40 TO 1025+50 RT	95.3																			
1025+50 LT TO 1025+50 RT	5.3	40																		
1025+50 RT	1.7	5																		
1025+50 TO 1026+23.9 RT	73.6																			
1026+23.9 RT TO 222+99.6 LT		12																		
1026+20 LT TO 223+99 LT				18																
223+99 TO 224+09 LT	1.4		8																	
223+99 TO 224+09 RT	1.1	8																		
1026+20 TO 1026+75.9 LT	14.5				52															
1026+23.9 RT TO 1026+88.4 LT	66.5																			
1026+75.9 TO 1026+88.4						9														
223+99 RT TO 1026+75.9 LT		16																		
1026+88.4 TO 1027+00 LT				29																
1027+00 LT																				
1026+88.4 TO 1027+80 LT																			1	
1027+80 LT	2.7	12																		
1027+80 LT TO 1027+80 RT	3.8	29																		
1027+80 TO 1030+00 LT																				
1029+94.6 RT TO 1029+97.8 LT	9.9																			
1029+97.8 TO 1030+00 LT	3.4										30									
1030+00 TO 1030+30 LT	30.5										9									
1030+26.5 TO 1030+30 LT																				
1030+26.5 LT TO 1030+40 RT	10																			
1030+30 TO 1031+00 LT																				
1031+00 TO 1031+80 LT	48.4																			
1031+79.4 RT TO 1031+79.4 LT	6.9	32																		
1031+79.4 TO 1031+80 LT	1.4		5																	
1031+80 TO 1033+30 LT																				
1033+30 TO 1034+86.1 LT																				
1034+86.1 TO 1035+01.2 LT	20.5																			
1035+01.2 LT TO 1035+01.2 RT	39.6																			
1034+85 TO 1035+01.2 RT																				
1034+85, 30' RT TO 1034+85, 53.2' RT																				
1034+85, 53.2' RT TO 1034+85, 76.5' RT																				
1034+85, 76.5' RT TO 1034+85, 99.3' RT																				
1034+85, 99.3' RT																				
TOTALS	812	254	13	47	52	9	254	360	19	39	17	44	196	340	24	41	138	1	1	

\* ATTACH TO EXISTING COMBINATION SEWER AFTER INLET REMOVAL  
 \*\* AT CONFLICT MANHOLE

12/18/2006 10:44:45 AM  
 c:\projects\ep01\01\06\0116.dgn

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SCHEDULE OF QUANTITIES**  
 SCALE: VERT.      DRAWN BY  
 DATE      HORIZ.      CHECKED BY