

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
698	*	BUREAU	22	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
* (102)RS-4 & (TX-1,17)RS-2				

SUMMARY OF QUANTITIES				80% FED./20% ST.
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE
				ROADWAY I000
20400800	FURNISHED EXCAVATION	CU YD	6	6
25000200	SEEDING, CLASS 2	ACRE	0.1	0.1
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	6	6
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	6	6
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	6	6
25100630	EROSION CONTROL BLANKET	SQ YD	320	320
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	6181.2	6181.2
40600300	AGGREGATE (PRIME COAT)	TON	154	154
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	22	22
40600895	CONSTRUCTING TEST STRIP	EACH	1	1
40600535	LEVELING BINDER (HAND METHOD), N70	TON	36	36
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	2993	2993
40600990	TEMPORARY RAMP	SQ YD	160	160
40603340	HOT-MIX ASPHALT, SURFACE COURSE, MIX "D", N70	TON	6020	6020
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	698	698
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	71253	71253
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	6021	6021
48101200	AGGREGATE SHOULDERS, TYPE B	TON	578	578
* 56109210	WATER VALVES TO BE ADJUSTED	EACH	4	4
60255500	MANHOLES TO BE ADJUSTED	EACH	12	12
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3
67100100	MOBILIZATION	L SUM	1	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	9060	9060
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1237	1237
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	50195	50195
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	4026	4026
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	4467	4467
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1777	1777
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	279	279
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3187	3187

SUMMARY OF QUANTITIES				80% FED./20% ST.
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE
				ROADWAY I000
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1112	1112
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	48872	48872
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	3886	3886
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	4467	4467
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1777	1777
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	279	279
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	976	976
78200300	PRISMATIC CURB REFLECTOR	EACH	64	64
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	454	454
* 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	225	225
* 88600100	DETECTOR LOOP, TYPE I	FOOT	917	917
* 87900200	DRILL EXISTING HANDHOLE	EACH	2	2
* 89502210	MODIFY EXISTING CONTROLLER CABINET	EACH	1	1
* X8860100	LOOP DETECTOR TESTING	EACH	2	2

\* SPECIALTY ITEMS

12/19/2006 12:09:18 PM c:\projects\ep01706\detail1.s.dgn