

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	(32,47-4)RA-2	GRUNDY	18	3
FED. ROAD DIST. NO.		ILLINOIS	STATE AID PROJECT	

# SUMMARY OF QUANTITIES

CONSTRUCTION CODE TYPE: Y022

RURAL  
100% STATE  
TOTAL  
QUANTITY

CODE NO.	ITEM	UNIT	RURAL 100% STATE TOTAL QUANTITY
20200100	EARTH EXCAVATION	CU YD	16
20400800	FURNISHED EXCAVATION	CU YD	10
20800150	TRENCH BACKFILL	CU YD	53
25000100	SEEDING, CLASS 1	ACRE	0.07
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	6
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	6
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	6
25100630	EROSION CONTROL BLANKET	SQ YD	330
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	113
42001200	PAVEMENT FABRIC	SQ YD	104
42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6"	SQ FT	702

DATE: 10/12/2006  
C:/projects/rest area/three rivers/details.dgn

\* SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SUMMARY OF QUANTITIES**  
F.A.I. ROUTE 80  
SECTION (32,47-4)RA-2  
GRUNDY COUNTY