

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
404	*	TAZEWELL	7	2

\* D4 BRIDGE REPAIR 2007

## COMMITMENTS

NO COMMITMENTS HAVE BEEN MADE FOR THIS PROJECT.

## GENERAL NOTES

UNLESS DIRECTED OTHERWISE BY THE SHOTCRETE MANUFACTURER, 5 DAYS OF CURING TIME WILL BE REQUIRED. TRAFFIC WILL BE KEPT OFF THE REPAIR AREA DURING THIS TIME. SEE THE REPAIR PLANS FOR MORE INFORMATION.

PLAN DIMENSIONS AND DETAILS RELATIVE TO EXISTING STRUCTURE HAVE BEEN TAKEN FROM EXISTING PLANS AND ARE SUBJECT TO NOMINAL CONSTRUCTION VARIATIONS. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY SUCH DIMENSIONS AND DETAILS IN THE FIELD AND MAKE NECESSARY APPROVED ADJUSTMENTS PRIOR TO WORK OR THE ORDERING OF MATERIALS. SUCH VARIATIONS SHALL NOT BE CAUSE FOR ADDITIONAL COMPENSATION FOR A CHANGE IN THE SCOPE OF THE WORK. HOWEVER, THE CONTRACTOR WILL BE PAID FOR THE QUANTITY ACTUALLY FURNISHED AT THE UNIT PRICE BID FOR THE PROJECT.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

### COMMITMENTS AND GENERAL NOTES

SCALE: VERT.  
HORIZ.  
DATE 01-03-2006

DRAWN BY CEJ  
CHECKED BY