

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
702	(113B)	WOODFORD	38	5
STA. 13+30		TO STA. 17+00		
FED. ROAD DIST. NO. 4 ILLINOIS FED. AID PROJECT				

**GUARDRAIL SCHEDULE**

LOCATION	TRAFFIC BARRIER TERMINAL TYPE 1 SPECIAL (TANGENT) (EACH)	STEEL PLATE BEAM GUARDRAIL TYPE A (FOOT)	TRAFFIC BARRIER TERMINAL TYPE 6A (EACH)
STAGE I			
STA. 14+09.7 TO STA. 14+59.7 LT.	1		
STA. 14+59.7 TO STA. 15+04 LT.			1
STA. 15+86 TO STA. 16+30.3 LT.			1
STA. 16+30.3 TO STA. 16+80.3 LT.	1		
STAGE II			
STA. 13+34.7 TO STA. 13+84.7 RT.	1		
STA. 13+84.7 TO STA. 14+59.7 RT.		75	
STA. 14+59.7 TO STA. 15+04 RT.			1
STA. 15+86 TO STA. 16+30.3 RT.			1
STA. 16+30.3 TO STA. 16+80.3 RT.	1		
TOTAL	4	75	4

**BITUMINOUS SCHEDULE**

LOCATION	TEMPORARY RAMP (SQ. YD.)	LEVELING BINDER (MACHINE METHOD), N50 (TON)	HOT MIX ASPHALT SURFACE COURSE, MIX "D", N50 (TON)	BITUMINOUS MATERIALS (PRIME COAT) (TON)
STA. 14+80 TO STA. 15+24			15.6	0.07
STA. 15+04 TO STA. 15+24		4.5		
STA. 15+66 TO STA. 15+86		4.5		
STA. 15+66 TO STA. 16+18			18.4	0.08
STA. 15+19 TO STA. 15+24	22			
STA. 15+66 TO STA. 15+71	22			
TOTAL	44	9	34	0.15

**PAVEMENT MARKING SCHEDULE**

LOCATION	LENGTH (FT.)	PAVEMENT MK. REMOVAL		SHORT TERM PVMT. MARKING LINE - 4"		PAINT PVMT. MK. LINE - 4"	
		WHITE (SQ. FT.)	YELLOW SKIP DASH & NO PASSING (SQ. FT.)	WHITE (FT.)	YELLOW (FT.)	WHITE (SQ. FT.)	YELLOW SKIP DASH & NO PASSING (SQ. FT.)
STA. 12+70 TO STA. 15+24 RT. (EDGE) ST. I	254	85					
STA. 15+66 TO STA. 18+50 RT. (EDGE) ST. I	284	95					
STA. 12+32.5 TO STA. 15+24 (C) ST. I	291.5		52				
STA. 15+66 TO STA. 18+57.5 (C) ST. I	291.5		101				
STA. 12+70 TO STA. 15+24 LT. (EDGE) ST. II	254	85					
STA. 15+66 TO STA. 18+25 LT. (EDGE) ST. II	284	95					
STA. 12+32.5 TO STA. 18+57.5 (C)	625			125			641
STA. 12+70 TO STA. 18+50 LT. (EDGE)	580					580	
STA. 12+70 TO STA. 18+25 RT. (EDGE)	555					555	
STA. 12+32.5 RT. (STOP BAR)	12						
STA. 18+57.5 LT. (STOP BAR)	12						
TOTAL		513		125		1776	

NOTE: SHORT-TERM PAVEMENT MARKING QUANTITIES ARE FOR TWO APPLICATIONS.  
 \* 10% OF TOTAL LENGTH FOR SHORT-TERM PAVEMENT MARKING

**SCHEDULE GUARDRAIL & TERMINAL MARKERS**

LOCATION	GUARDRAIL MARKERS TYPE A (EACH)	TERMINAL MARKER DIRECT APPLIED (EACH)
STA. 13+34.7 RT.		1
STA. 14+09.7 LT.		1
STA. 16+80.3 LT.		1
STA. 16+80.3 RT.		1
STA. 13+90 RT.	1	
STA. 14+70 RT.	1	
STA. 15+50 RT.	1	
STA. 16+30 RT.	1	
STA. 14+60 LT.	1	
STA. 15+15 LT.	1	
STA. 15+70 LT.	1	
STA. 16+25 LT.	1	
TOTAL	8	4

**SCHEDULE GUARDRAIL AGGREGATE EROSION CONTROL**

LOCATION	QUANTITY (TON)
STA. 13+30 TO STA. 15+23 RT.	42
STA. 13+87.5 TO STA. 15+23 LT.	25
STA. 15+67.3 TO STA. 17+00 RT.	24
STA. 15+67.3 TO STA. 17+00 LT.	24
TOTAL	115

**SCHEDULE RAISED REFLECTIVE PAVEMENT MARKER**

LOCATION	RAISED REFL PAVT MRK REM (EACH)
STA. 14+85 (C)	1
STA. 15+65 (C)	1
TOTAL	2

**SCHEDULE PRECAST CONCRETE BRIDGE SLAB**

LOCATION	QUANTITY (SQ. YD.)
STA. 15+04 TO STA. 15+23.92 LT. & RT.	143.5
STA. 15+66.08 TO STA. 15+86 LT. & RT.	143.5
TOTAL	287

**SCHEDULE PAVEMENT REMOVAL**

LOCATION	QUANTITY (SQ. YD.)
STA. 15+04 TO STA. 15+24	70
STA. 15+66 TO STA. 15+86	70
TOTAL	140

**SCHEDULE PERMANENT SEEDING**

LOCATION	SEEDING CLASS 2 (ACRE)	NITROGEN FERT. NUT. (POUND)	PHOSPHORUS FERT. NUT. (POUND)	POTASSIUM FERT. NUT. (POUND)	EROSION CONTROL BLANKET (SQ. YD.)	TEMPORARY EROSION CONTROL SEEDING (POUND)
STA. 13+30 TO STA. 17+00	0.20	18	18	18	968	20
TOTAL	0.20	18	18	18	968	20

**SCHEDULE HOT MIX ASPHALT SURFACE REMOVAL - BUTT JOINT**

LOCATION	QUANTITY (SQ. YD.)
STA. 14+80 TO STA. 14+99	80
STA. 15+91 TO STA. 16+18	114
TOTAL	194

**EARTHWORK SCHEDULE**

LOCATION	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
	CUBIC YARD	CUBIC YARD	CUBIC YARD	CUBIC YARD
STA. 13+30 TO STA. 15+04	0	0	83	-83
STA. 15+86 TO STA. 17+00	0	0	71	-71
TOTAL	0	0	154	-154

**SCHEDULE PERIMETER EROSION BARRIER**

LOCATION	QUANTITY (FEET)
STA. 13+50 TO STA. 15+25 RT.	200
STA. 14+00 TO STA. 15+25 LT.	150
STA. 15+67 TO STA. 16+50 RT.	100
STA. 15+67 TO STA. 17+00 LT.	150
TOTAL	600

**SCHEDULE SUB-BASE GRANULAR MATERIAL TYPE A**

LOCATION	QUANTITY (SQ. YD.)
STA. 15+04 TO STA. 15+24	70
STA. 15+66 TO STA. 15+86	70
TOTAL	140

**SCHEDULE PORTLAND CEMENT CONCRETE BASE COURSE 9"**

LOCATION	QUANTITY (SQ. YD.)
STA. 15+04 TO STA. 15+24	70
STA. 15+66 TO STA. 15+86	70
TOTAL	140

QUANTITY SCHEDULES  
 IL ROUTE 117 OVER WALNUT CREEK  
 F.A.P. RTE. 702 - SECTION (113B)  
 WOODFORD COUNTY  
 STA. 15+45.00  
 S.N. 102-0018

FILE NAME: 05 REV. 12/7/06