

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
693	129 B-2	MCLEAN	34	8

FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT

**CONTRACT NO. 70519**

**70400100 TEMPORARY CONCRETE BARRIER**

LOCATION	TYPE	FOOT
STAGE 1		
STA 66+85.0 TO STA 67+44.5	8:1 TAPER	60
STA 67+44.5 TO STA 68+44.5	TANGENT	100
STA 68+44.5 TO STA 69+04.0	8:1 TAPER	60
STAGE 2		
STA 66+97.1 TO STA 67+07.1	8:1 TAPER	10
TOTAL		230

**70400200 RELOCATE TEMPORARY CONCRETE BARRIER**

LOCATION	TYPE	FOOT
STAGE 2		
STA 67+07.1 TO STA 67+46.5	8:1 TAPER	40
STA 67+46.5 TO STA 68+65.8	TANGENT	120
STA 68+65.8 TO STA 69+25.6	8:1 TAPER	60
TOTAL		220

**Z0030240 IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE),**

TEST LEVEL 2	LOCATION	EACH
STAGE 1		
	STA 66+84.1	1
	STA 69+03.7	1
TOTAL		2

**Z0030340 IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE),**

TEST LEVEL 2	LOCATION	EACH
STAGE 2		
	STA 66+97.1	1
	STA 69+25.6	1
TOTAL		2

**40603090 HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90**

LOCATION	TON
STAGE 1	
WEST ABUTMENT	1
EAST ABUTMENT	1
STAGE 2	
WEST ABUTMENT	2
EAST ABUTMENT	2
TOTAL	6

**44000500 COMBINATION CURB AND GUTTER REMOVAL**

LOCATION	FOOT
STAGE 1	
RT STA 66+68 TO STA 67+44	77
RT STA 68+33.83 TO STA 69+33	100
TOTAL	177

**60605400 COMBINATION CONCRETE CURB AND GUTTER TYPE B-6.24 (SPECIAL)**

LOCATION	FOOT
STAGE 1	
RT STA 66+63 TO STA 67+44	77
RT STA 68+33.83 TO STA 69+33	100
TOTAL	177

**44000600 SIDEWALK REMOVAL**

LOCATION	SO FT
STAGE 1	
RT STA 66+63 TO STA 67+44.44	398
RT STA 68+33.83 TO STA 68+62	110
TOTAL	508

**42400100 PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH**

LOCATION	SO FT
STAGE 1	
RT STA 66+63 TO STA 67+44.44	412
RT STA 68+33.83 TO STA 68+62	121
TOTAL	533

**44000198 HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH**

LOCATION	SO YD
FINAL PHASE	
STA 66+62 TO STA 67+51.03	634
STA 68+37.24 TO STA 69+33	681
TOTAL	1,315

**40600990 TEMPORARY RAMP**

LOCATION	SO YD
FINAL PHASE	
STA 66+62 TO STA 66+67	36
STA 67+46.03 TO STA 67+51.03	36
STA 68+37.24 TO STA 68+42.24	36
STA 69+28 TO STA 69+33	36
TOTAL	144

**40600100 BITUMINOUS MATERIALS (PRIME COAT)**

LOCATION	GALLON
STAGE 1-2	
STA 67+49.95 TO STA 67+51.03	1
STA 68+37.25 TO STA 68+38.33	1
FINAL PHASE	
STA 66+62 TO STA 67+51.03	64
STA 68+37.25 TO STA 69+33	69
TOTAL	135

**40600300 AGGREGATE (PRIME COAT)**

LOCATION	TON
FINAL PHASE	
STA 66+62.00 TO STA 67+51.03	1.5
STA 68+37.25 TO STA 68+62.11	1.5
TOTAL	3

**40603345 HOT-MIX ASPHALT SURFACE COURSE, MIX'D", N90**

LOCATION	TON
FINAL PHASE	
STA 66+62.00 TO STA 67+51.03	54
STA 68+37.24 TO STA 69+33.00	58
TOTAL	112

**X0323710 REMOVE CONDUIT ATTACHED TO STRUCTURE**

LOCATION	FOOT
STAGE 1	
RT STA 67+44.0 TO STA 68+32.9	90
STAGE 2	
LT STA 67+54.6 TO STA 68+44.0	90
TOTAL	180

**XX002094 REMOVE AND REINSTALL FIBER OPTIC CABLE IN CONDUIT**

LOCATION	L SUM
STAGE 1	
RT STA 65+80.0 TO STA 73+29.0	1
TOTAL	1

APPROXIMATE LENGTH OF FIBER OPTIC CABLE= 775 FOOT

**X0322256 TEMPORARY INFORMATION SIGNING**

STAGE 1	SIGN NO.	SIZE	SO FT
	TIS-1	48x30	10.00
	TIS-2	36x12	3.00
	TIS-3	42x24	7.00
	TIS-4	36x12	3.00
	TIS-5	36x12	3.00
	TIS-6	36x12	3.00
	TIS-7	36x12	3.00
	TIS-8	42x24	7.00
	TIS-9	36x12	3.00
	TIS-10	42x18	5.25
	TIS-11	36x12	3.00

STAGE 2	SIGN NO.	SIZE	SO FT
	TIS-1	48x30	**
	TIS-2	36x12	**
	TIS-3	42x24	.
	TIS-4	36x12	.
	TIS-6	36x12	.
	TIS-7	36x12	.
	TIS-8	42x24	**
	TIS-9	36x12	**
	TIS-12	36x12	3.00
	TIS-13	42x18	5.25
	TIS-14	36x12	3.00
	TIS-15	36x12	3.00
	TIS-16	48x30	10.00
TOTAL			75

\*RELOCATE SIGN FROM STAGE 1 LOCATION  
\*\*SIGN ERECTED IN STAGE 1

**SCHEDULE OF QUANTITIES**

FAP ROUTE 693 (IL 9)  
SECTION 129 B-2  
MCLEAN COUNTY

CUMMINS ENGINEERING CORPORATION

JOB #: 2114.5  
FILE: 2114SUM.DGN  
DATE: 12/07/06