

SUMMARY OF QUANTITIES

LOCATION OF WORK: FAP 322 (US 51)

CODE NO	ITEM	UNIT	CONSTRUCTION TYPE CODE:				
			DEWITT COUNTY 100% STATE SFTY-2A TOTAL QUANTITY	DEWITT COUNTY 100% STATE SFTY-2A SN 020-0050 QUANTITY	DEWITT COUNTY 100% STATE SFTY-2A SN 020-0053 QUANTITY	DEWITT COUNTY 100% STATE SFTY-2A SN 020-0055 QUANTITY	DEWITT COUNTY 100% STATE SFTY-2A SN 020-0005 QUANTITY
50102400	CONCRETE REMOVAL	CU YD	12.0	4.5	5.2	2.3	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	12.0	4.5	5.2	2.3	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	990.0	400.0	380.0	210.0	
50800515	BAR SPLICERS	EACH	15.0	6.0	6.0	3.0	
67100100	MOBILIZATION	L SUM	1.0	0.25	0.25	0.25	0.25
70100320	TRAFFIC CONTROL & PROTECTION STANDARD 701422	L SUM	1.0	0.25	0.25	0.25	0.25
X0320887	POLYMER CONCRETE	CU FT	27.0	7.3	5.2	7.6	6.9
X0321744	SILICONE JOINT SEALER 2"	FOOT	284.0	96.6		96.6	90.8
X0322932	SILICONE JOINT SEALER 1 1/2"	FOOT	43.0		43.0		
X0322933	SILICONE JOINT SEALER 2 1/2"	FOOT	45.0		45.0		
X7015005	CHANGEABLE MESSAGE SIGN	CAL. DA	7.0	1.75	1.75	1.75	1.75
Z0001700	APPROACH SLAB REPAIR (FULL DEPTH)	SQ YD	6.0	6.0			

PLOT DATE: 12/21/2006
 FILE NAME: c:\projects\70593\70593.dwg
 PLOT SCALE: 1/8" = 1'-0"
 USER NAME: jrogers