

SUMMARY OF QUANTITIES

FAU ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8071	*	SANGAMON	559	6
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
(84-9-4)A,HBK,BY,BY-1		* 02-00382-02-PV		

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	ROADWAY		STRUCTURE					
				MACARTHUR EXTENSION CITY SECTION 02-00382-02-PV STA. 798+08.49 TO STA. 876+31.00	MACARTHUR EXTENSION & I-72 INTERCHANGE	MACARTHUR EXTENSION OVER N.S. RAILROAD (S.N. 084-0512)	INTERURBAN TRAIL OVER N.S. RAILROAD (S.N. 084-7008)	MACARTHUR EXTENSION OVER INTERURBAN TRAIL (S.N. 084-7009)	MACARTHUR EXTENSION OVER I-72 (S.N. 084-0513)	I-72 INTERCHANGE RAMP B & C OVER U.P. RAILROAD (S.N. 084-0514 EB, S.N. 084-0516)	I-72 EB & WB OVER U.P. RAILROAD (S.N. 084-0074 EB, S.N. 084-0075 WB)
				50% STATE / 50% CITY	FUNDING - 1M 90% FED / 10% STATE	FUNDING - 1M 90% FED / 10% STATE	FUNDING - 1M 90% FED / 10% STATE	FUNDING - 1M 90% FED / 10% STATE	FUNDING - 1M 90% FED / 10% STATE	FUNDING - 1M 90% FED / 10% STATE	FUNDING - 1M 90% FED / 10% STATE
28200200	FILTER FABRIC	SQ YD	2128	C000		X181-5B	X932-5B	X928-2A	X781-2A	X171-5B	X171-5B
31100100	SUB-BASE GRANULAR MATERIAL, TYPE A	TON	789.9								
35100500	AGGREGATE BASE COURSE, TYPE A 6"	SQ YD	165								
35100700	AGGREGATE BASE COURSE, TYPE A 8"	SQ YD	702	702							
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	3.0	1.0		0.8					1.2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1274								1274
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	79								
40600605	LEVELING BINDER (MACHINE METHOD) N50	TON	79								
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	79								
40603345	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	132								
40603345	HOT-MIX ASPHALT SURFACE COURSE, MIXTURE D, N90	TON	482								350
40701961	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 14"	SQ YD	145								
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	544								
42001300	PROTECTIVE COAT	SQ YD	615	71		544					
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	108								
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	3970	3970							
44000100	PAVEMENT REMOVAL	SQ YD	15330	1804		13526					
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	18	18							
44000700	APPROACH SLAB REMOVAL	SQ YD	557			557					
44000920	BITUMINOUS CONCRETE SHOULDER REMOVAL	SQ YD	6329			6329					
44004000	PAVED DITCH REMOVAL	FOOT	110			110					
44004400	PAVEMENT REMOVAL (SPECIAL)	SQ YD	2169			2169					
48101620	AGGREGATE SHOULDERS, TYPE B 10"	SQ YD	1524			1524					
48203049	HOT-MIX ASPHALT SHOULDERS, 13"	SQ YD	6064			6064					
50102400	CONCRETE REMOVAL	CU YD	117.6								117.6
50104400	CONCRETE HEADWALL REMOVAL	EACH	16			16					
50104650	SLOPE WALL REMOVAL	SQ YD	2100								2100
50104720	REMOVAL OF EXISTING CONCRETE DECK	EACH	2								2
50105220	PIPE CULVERT REMOVAL	FOOT	358			358					
50157300	PROTECTIVE SHIELD	SQ YD	1007								1007

* PAY ITEM REQUIRES A SPECIAL PROVISION

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF QUANTITIES -2
 FA1-72, MACARTHUR BLVD
 SEC NO. 02-00382-02-PV
 SEC NO. (84-9-4)A,HBK,BY,BY-1
 SANGAMON COUNTY, ILLINOIS

SCALE: VERT. _____
 HORIZ. _____
 DATE 12/14/2006

DRAWN BY CLG
 CHECKED BY JAD

Rev. 2-9-07



© Copyright Hanson Professional Services Inc. 2006

12/14/2006
 CLG
 12/28/06
 CLG
 12/28/06
 JAD
 12/28/06