CONTRACT #72541

FAU ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8071	*	SANGAMON	559	5
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

(84-9-4)A,HBK,BY,BY-1 * 02-00382-02-PV

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY (URBAN)	ROADWAY: MACARTHUR EXTENSION CITY SECTION 02-00382-02-PV STA. 798+08.49 TO STA. 876+31.00 50% STATE / 50% CITY	ROADWAY: MACARTHUR EXTENSION & I-72 INTERCHANGE FUNDING - IM 90% FED / 10% STATE	STRUCTURE: MACARTHUR EXTENSION OVER N.S. RAILROAD (S.N. 084-0512) FUNDING - IM 90% FED / 10% STATE	STRUCTURE: INTERURBAN TRAIL OVER N.S. RAILROAD (S.N. 084-7008) FUNDING - IM 90% FED / 10% STATE	STRUCTURE: MACARTHUR EXTENSION OVER INTERURBAN TRAIL (S.N. 084-7009) FUNDING - IM 90% FED / 10% STATE	STRUCTURE: MACARTHUR EXTENSION OVER I-72 (S.N. 084-0513) FUNDING - IM 90% FED / 10% STATE	STRUCTURE: I-72 INTERCHANGE RAMP B & C OVER U.P RAILROAD (S.N. 084-0514 EB, S.N. 084-0516) FUNDING - IM 90% FED / 10% STATE	STRUCTURE: I-72 EB & WB OVER U.P. RAILROAD (S.N. 084-0074 EB, S.N. 084-0075 WB) FUNDING - IM 90% FED / 10% STATE
				C000	C000	X181-5B	X932-5B	X928-2A	X781-2A	X171-5B	X171-5B
20100500	TREE REMOVAL, ACRES	ACRE	54.75	5.00	49.75						
20200100	EARTH EXCAVATION	CU YD	279,855	18,475	261,380						
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	14500		14500						
20201400	SUB-BASE GRANULAR MATERIAL, TYPE A	TON	800		800						
20400100	BORROW EXCAVATION	CU YD	510,790	218,320	292,470						
* 20400805	FURNISHED EXCAVATION, SPECIAL	CU YD	677,375	129,260	548,115						
* 20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	2110			778		298	662	240	132
20800150	TRENCH BACKFILL	CU YD	3118	2129	989						
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	33320	5498	27,822						
25000200	SEEDING, CLASS 2	ACRE	61.25	18.75	42.50						
25000300	SEEDING, CLASS 3	ACRE	29.75	6.25	23.50						
25000350	SEEDING, CLASS 7	ACRE	182.00	51.50	130.50						
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	8296	2355	5941						
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	8296	2355	5941						
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	8296	2355	5941						
25000700	AGRICULTURAL GROUND LIMESTONE	TON	186.5	53.5	133.0						
25000750	MOWING	ACRE	61.25	18.75	42.50						
25100115	MULCH, METHOD 2	ACRE	91	25.00	66.00						
* 25101005	HEAVY DUTY EXCELSIOR BLANKET	SQ YD	7102	1528	5574						
25200200	SUPPLEMENTAL WATERING	UNIT	80		80						
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	5700	1125	4575						
28000300	TEMPORARY DITCH CHECKS	EACH	190	74	116						
28000400	PERIMETER EROSION BARRIER	FOOT	10750	3265	7485						
28000500	INLET AND PIPE PROTECTION	EACH	77	48	29						
28100125	STONE RIPRAP, CLASS B3	SQ YD	4364	264	4100						
28100129	STONE RIPRAP, CLASS B5	SQ YD	599		599						
28100835	STONE DUMPED RIPRAP, CLASS B5	TON	1409		1409						

* PAY ITEM REQUIRES A SPECIAL PROVISION

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES -1
FAI-72, MACARTHUR BLVD
SEC NO. 02-00382-02-PV
SEC NO. (84-9-4)A,HBK,BY,BY-1
SANGAMON COUNTY, ILLINOIS

SCALE: VERT. HORIZ. DRAWN BY CLG
DATE 12/14/2006 CHECKED BY JAD

HANSON

© Copyright Hanson Professional Services Inc. 2006

12/14/2006
h:\96jobs\96e2002\civil\sheet\sc-60ssqu.dgn

PLAN OUT	CLG	04/28/06
DRAWN	CLG	04/28/06
REVIEWED	JAD/JRW	04/28/06