

SUMMARY OF QUANTITIES

FAU ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8071	*	SANGAMON	559	6
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
(84-9-4)A,HBK,BY,BY-1 * 02-00382-02-PV				

CODE NO.	ITEM	UNIT	URBAN	ROADWAY				STRUCTURE					
			TOTAL QUANTITY	MACARTHUR EXTENSION CITY SECTION 02-00382-02-PV STA. 798+08.49 TO STA. 876+31.00 50% STATE / 50% CITY C000	MACARTHUR EXTENSION & I-72 INTERCHANGE FUNDING - 1M 90% FED / 10% STATE C000	MACARTHUR EXTENSION OVER N.S. RAILROAD (S.N. 084-0512) FUNDING - 1M 90% FED / 10% STATE X181-5B	INTERURBAN TRAIL OVER N.S. RAILROAD (S.N. 084-7008) FUNDING - 1M 90% FED / 10% STATE X932-5B	MACARTHUR EXTENSION OVER INTERURBAN TRAIL (S.N. 084-7009) FUNDING - 1M 90% FED / 10% STATE X928-2A	MACARTHUR EXTENSION OVER I-72 (S.N. 084-0513) FUNDING - 1M 90% FED / 10% STATE X781-2A	I-72 INTERCHANGE RAMP B & C OVER U.P. RAILROAD (S.N. 084-0514 EB, S.N. 084-0516) FUNDING - 1M 90% FED / 10% STATE X171-5B	I-72 EB & WB OVER U.P. RAILROAD (S.N. 084-0074 EB, S.N. 084-0075 WB) FUNDING - 1M 90% FED / 10% STATE X171-5B		
28200200	FILTER FABRIC	SQ YD	2128			2128							
31100100	SUB-BASE GRANULAR MATERIAL, TYPE A	TON	789.9			789.9							
35100500	AGGREGATE BASE COURSE, TYPE A 6"	SQ YD	165			165							
35100700	AGGREGATE BASE COURSE, TYPE A 8"	SQ YD	702	702									
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	3.0	1.0		0.8							1.2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1274										1274
40603130	HOT-MIX ASPHALT BINDER COURSE, IL-25.D, N50	TON	79	79.0									
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	79	79									
40603320	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N90	TON	132			132							
40603345	HOT-MIX ASPHALT SURFACE COURSE, MIXTURE D, N90	TON	350										350
40701961	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 14"	SQ YD	145			145							
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	544			544							
42001300	PROTECTIVE COAT	SQ YD	615	71		544							
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	108			108							
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	3970	3970									
44000100	PAVEMENT REMOVAL	SQ YD	15330	1804		13526							
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	18	18									
* 44000700	APPROACH SLAB REMOVAL	SQ YD	557			557							
* 44000920	BITUMINOUS CONCRETE SHOULDER REMOVAL	SQ YD	6329			6329							
44004000	PAVED DITCH REMOVAL	FOOT	110			110							
* 44004400	PAVEMENT REMOVAL (SPECIAL)	SQ YD	2169			2169							
* 48101620	AGGREGATE SHOULDERS, TYPE B 10"	SQ YD	1524			1524							
48203049	HOT-MIX ASPHALT SHOULDERS, 13"	SQ YD	6064			6064							
50102400	CONCRETE REMOVAL	CU YD	117.6										117.6
* 50104400	CONCRETE HEADWALL REMOVAL	EACH	16			16							
50104650	SLOPE WALL REMOVAL	SQ YD	2100										2100
50104720	REMOVAL OF EXISTING CONCRETE DECK	EACH	2										2
* 50105220	PIPE CULVERT REMOVAL	FOOT	358			358							
50157300	PROTECTIVE SHIELD	SQ YD	1007										1007

* PAY ITEM REQUIRES A SPECIAL PROVISION

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES -2
FAI-72, MACARTHUR BLVD
SEC NO. 02-00382-02-PV
SEC NO. (84-9-4)A,HBK,BY,BY-1
SANGAMON COUNTY, ILLINOIS

SCALE: VERT. _____
HORIZ. _____
DATE 12/14/2006

DRAWN BY CLG
CHECKED BY JAD



12/14/2006
1657 Jan 06 08:20:22 chm\user\c-50\scg\pfn

LAYOUT	CLG	12/28/06
DRAWN	CLG	12/28/06
REVIEWED	JAD/JAM	12/28/06