CONTRACT NO. 72541

FAU ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8071	*	SANGAMON	559	44
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

(84-9-4)A,HBK,BY,BY-1 * 02-00382-02-PV

GUARDRAIL AND TERMINAL SCHEDULE

LOCATION			STEEL PLATE BEAM GUARD RAIL, TYPE A	TRAFFIC BARRIER TERMINAL, TYPE 6	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)	TEMPORARY STEEL PLATE BEAM GUARD RAIL, TYPE A	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 1	MONODIRECTIONAL PRISMATIC BARRIER REFLECTOR	TERMINAL MARKER - DIRECT APPLIED	BARRICADES, TYPE III	IMPACT ATTENUATORS, (NON-REDIRECTIVE), TEST LEVEL 3	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3
			FOOT	EACH	EACH	EACH	FOOT	EACH	EACH	EACH	EACH	EACH	EACH	EACH
BEGIN STATION	**END STATION / OFFSET**	**OFFSET**												
MACARTHUR BOULEVARD														
769+93.00		LT/RT									25			
841+34.00	40'	RT												
		SUBTOTAL									**25**			
INTERSTATE 72														
I-72	595+34.00	CL										1		
I-72	597+32.00	CL										1		
597+57.10	607+18.21	RT												
600+64.50	607+66.00	LT												
602+55.10	603+05.10	RT				1								
602+55.10	609+53.70	RT							9					
602+55.10		LT								1				
602+83.90	603+33.90	RT			1									
602+83.90	609+30.64	RT							9					
602+83.90		RT								1				
603+05.10	606+80.10	RT	375.0											
603+33.90	606+58.90	RT	325.0											
605+70.00	607+19.00	RT												
606+58.90	606+89.54	RT		1										
606+80.10	607+10.74	RT		1										
607+47.77	614+53.32	LT							9					
607+70.78	614+29.98	LT							9					
609+35.00	618+06.00	RT												
609+89.00	611+40.00	LT												
609+97.68	610+28.32	LT		1										
610+06.00	619+65.60	LT												
610+24.34	610+54.98	LT		1										
610+28.32	614+03.32	LT	375.0											
610+54.98	613+39.32	LT	284.0											
613+39.32	619+00.00						561							
614+03.32	614+53.32	LT				1								
614+53.32		RT								1				
619+00.00								1						
686+67.50	688+29.94	LT							3					
686+65.75	687+90.75	RT							2	1				
EASTBOUND - STANDARD 701402									7				1	1
WESTBOUND - STANDARD 701402									7				1	1
		SUBTOTAL	**1359.0**	**4**	**1**	**2**	**561**	**1**	**55**	**4**		**2**	**2**	**2**
		TOTAL	**1359.0**	**4**	**1**	**2**	**561**	**1**	**55**	**4**	**25**	**2**	**2**	**2**

© Copyright Hanson Professional Services Inc. 2003

HANSON

12/16/2006
$FILE$

LAYOUT	CLG	05/ /05
DRAWN	CLG	05/ /05
REVIEWED	JAD/MM	05/ /05

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES -8
FAI-72, MACARTHUR BLVD
SEC NO. 02-00382-02-PV
SEC NO. (84-9-4)A,HBK,BY,BY-1
SANGAMON COUNTY, ILLINOIS

SCALE: VERT. HORIZ.
DATE 05/20/2005
DRAWN BY CLG
CHECKED BY MH