CONTRACT #72541

FAU ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8071	*	SANGAMON	559	51
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

(84-9-4)A,HBK,BY,BY-1 * 02-00382-02-PV

DRAINAGE STRUCTURE SCHEDULE – 4

NO.	ROADWAY	STATION	OFFSET FEET		FRAME ELEV	INLETS: TYPE A, T1 F&L (OPEN)	TYPE A, T3 F&G	TYPE A, T37G	TYPE B, T3 F&G	TYPE B, T37G	TYPE B, STD 609006	TYPE B, STD 609006 SPCL	TYPE C, STD 609006	TYPE C, STD 609006 SPCL	TYPE D, STD 609006	TYPE D, STD 609006 SPCL	TYPE E, STD 610001	TYPE F, STD 610001	TYPE F, STD 610001 SPCIL	MANHOLES: TYPE A, 4' DIA T1 CL	TYPE A, 4' DIA T8G	TYPE A, 4' DIA T3 F&G	TYPE A, 4' DIA	TYPE A, 5' DIA	TYPE A, 6' DIA	SPECIAL TYPE 1	SPECIAL TYPE 2	SPECIAL TYPE 3	SPECIAL TYPE 4	SPECIAL TYPE 5	REINF. CONC. PIPE TEE: 36" PIPE 12" RISER	42" PIPE 12" RISER	48" PIPE 12" RISER	54" PIPE 12" RISER	60" PIPE 12" RISER	66" PIPE 12" RISER	FRAME & LID TY 1 CL	F&G TYPE 3	G&C TYPE 2B	GRATE TYPE 37	12" PRC FLARED END SECTION	18" PRC FLARED END SECTION	24" PRC FLARED END SECTION	36" PRC FLARED END SECTION	72" PRC FLARED END SECTION	GRATING FOR END SECTION 24"	MH TO BE RECONSTRUCTED	HEAVY DUTY EXCELSIOR BLANKET	COMMENTS
133	N/A																																																
134	N/A																																																
135	N/A																																																
136	N/A																																																
137	N/A																																																
138	N/A																																																
139	N/A																																																
140	N/A																																																
141	N/A																																																
142	N/A																																																
143	MAC BLVD	837+20.00	82.00	L	604.89					1																																							
144	MAC BLVD	837+20.00	58.92	L	609.01				1																																								
145	MAC BLVD	837+20.00	7.30	L	609.96				1																																								
146	MAC BLVD	837+20.00	7.30	R	609.96				1																																								
147	MAC BLVD	837+20.00	46.92	R	609.25				1																																								
148	MAC BLVD	837+20.00	70.00	R	604.89																						1											1											
149	MAC BLVD	840+80.00	58.20	L	609.10		1																																										
150	MAC BLVD	840+80.00	x	L	x		1																																										
151	MAC BLVD	840+80.00	x	R	x		1																																										
152	MAC BLVD	840+80.00	46.20	R	609.34		1																																										
153	MAC BLVD	840+80.00	66.75	R	"T"																														1														CONNECT TO EXISTING STORM SEWER
154	MAC BLVD	840+10.00	85.00	R	607.83				1																																								
155	N/A																																																
156	MAC BLVD	842+00.00	58.20	L	608.74		1																																										
157	MAC BLVD	842+00.00	x	L	x		1																																										
158	MAC BLVD	842+00.00	x	R	x		1																																										
159	MAC BLVD	842+00.00	46.20	R	608.98		1																																										
160	N/A																																																
161	MAC BLVD	844+75.00	58.20	L	607.91		1																																										
162	MAC BLVD	844+75.00	7.30	L	608.84		1																																										
163	MAC BLVD	844+75.00	7.30	R	608.84		1																																										
164	MAC BLVD	844+75.00	46.20	R	608.15		1																																										
165	MAC BLVD	844+75.00	64.75	R	"T"																													1															
166	MAC BLVD	846+30.00	58.20	L	607.45		1																																										
167	MAC BLVD	846+30.00	7.30	L	608.38		1																																										
168	MAC BLVD	846+30.00	7.30	R	608.38		1																																										
169	MAC BLVD	846+30.00	46.20	R	607.69		1																																										
170	MAC BLVD	846+30.00	64.75	R	"T"																													1															
171	MAC BLVD	847+85.00	90.60	L	604.12					1																																							
172	MAC BLVD	847+85.00	58.20	L	606.98				1																																								
173	MAC BLVD	847+85.00	7.30	L	607.91				1																																								
174	MAC BLVD	847+85.00	7.30	R	607.91				1																																								
175	MAC BLVD	847+85.00	46.20	R	607.22				1																																								
176	MAC BLVD	847+85.00	64.50	R	604.12																							1										1											

NOTE:
SHADED ITEMS INDICATE DRAINAGE STRUCTURES NOT CONSTRUCTED IN GRADING & STRUCTURES CONTRACT. SHOWN FOR INFORMATION ONLY.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
DRAINAGE STRUCTURE SCHEDULE -4
FAI-72, MACARTHUR BLVD
SEC NO. 02-00382-02-PV
SEC NO. (84-9-4)A,HBK,BY,BY-1
SANGAMON COUNTY, ILLINOIS

SCALE: VERT. HORIZ. DRAWN BY CLG
DATE 12/18/2006 CHECKED BY JMM

LAYOUT	CLG	04/28/06
DRAWN	CLG	04/28/06
REVIEWED	JCD/JMM	04/28/06

12/18/2006
$FILE$

HANSON

© Copyright Hanson Professional Services Inc. 2006