CONTRACT #72541

FAU ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8071	*	SANGAMON	559	59
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

(84-9-4)A,HBK,BY,BY-1 # 02-00382-02-PV

DRAINAGE STRUCTURE SCHEDULE – 12

NO.	ROADWAY	STATION	OFFSET FEET		FRAME ELEV	INLETS: TYPE A, T1 F&L (OPEN)	TYPE A, T3 F&G	TYPE A, T37G	TYPE B, T3 F&G	TYPE B, T37G	TYPE B, STD 609006	TYPE B, STD 609006 SPCL	TYPE C, STD 609006	TYPE C, STD 609006 SPCL	TYPE D, STD 609006	TYPE D, STD 609006 SPCL	TYPE E, STD 610001	TYPE F, STD 610001	TYPE F, STD 610001 SPCIL	MANHOLES: TYPE A, 4' DIA T1 CL	TYPE A, 4' DIA T8G	TYPE A, 4' DIA T3 F&G	TYPE A, 4' DIA	TYPE A, 5' DIA	TYPE A, 6' DIA	SPECIAL TYPE 1	SPECIAL TYPE 2	SPECIAL TYPE 3	SPECIAL TYPE 4	SPECIAL TYPE 5	REINF. CONC. PIPE TEE: 36" PIPE 12" RISER	42" PIPE 12" RISER	48" PIPE 12" RISER	54" PIPE 12" RISER	60" PIPE 12" RISER	66" PIPE 12" RISER	FRAME & LID TY 1 CL	F&G TYPE 3	G&C TYPE 2B	GRATE TYPE 37	12" PRC FLARED END SECTION	18" PRC FLARED END SECTION	24" PRC FLARED END SECTION	36" PRC FLARED END SECTION	72" PRC FLARED END SECTION	GRATING FOR END SECTION 24"	MH TO BE RECONSTRUCTED	HEAVY DUTY EXCELSIOR BLANKET	COMMENTS
486	MAC BLVD	844+00.00	46.20	R	608.38				1																																							
487	MAC BLVD	844+00.00	63.70	R	605.17																								1								1										
488	MAC BLVD	853+50.00	58.20	L	605.29		1																																								
489	MAC BLVD	853+50.00	7.30	L	606.22		1																																								
490	MAC BLVD	853+50.00	7.30	R	606.22		1																																								
491	MAC BLVD	853+50.00	46.20	R	605.53		1																																								
492	MAC BLVD	853+50.00	63.75	R	"T"																												1														
493	LINCOLNSHIRE	181+10.00	x	L	x		1																																								
494	LINCOLNSHIRE	181+15.00	52.00	L	602.19				1																																						
495	LINCOLNSHIRE	181+10.00	x	R	x		1																																								
496	LINCOLNSHIRE	181+15.00	60.00	R	601.99				1																																						
497	LINCOLNSHIRE	181+15.00	70.00	R	600.75																	1															1										
498	LINCOLNSHIRE	181+15.00	70.00	L	600.75																	1															1										
499	LINCOLNSHIRE	183+45.00	x	L	x		1																																								
500	LINCOLNSHIRE	183+50.00	x	L	x				1																																						
501	LINCOLNSHIRE	183+45.00	x	R	x		1																																								
502	LINCOLNSHIRE	183+50.00	x	R	x				1																																						
503	LINCOLNSHIRE	183+45.00	60.00	L	602.65																	1															1										
504	LINCOLNSHIRE	183+67.00	60.00	R	602.65																	1															1										
505	LINCOLNSHIRE	183+79.00	114.00	L	599.40																																		1							18	
506	LINCOLNSHIRE	184+25.00	160.00	R	599.40																																		1							18	
							2	5	42	15			2	1	2					1	4	1	7	6	6	4	4	3	2	3	2	2	4	6	9		7	2		27	72	2	3	6	1	1	1	1592	

NOTE:
SHADED ITEMS INDICATE DRAINAGE STRUCTURES NOT CONSTRUCTED IN GRADING & STRUCTURES CONTRACT. SHOWN FOR INFORMATION ONLY.

© Copyright Hanson Professional Services Inc. 2006

HANSON

12/18/2006
#7L.5

LAYOUT	CLG	10/23/06
DRAWN	CLG	09/28/06
REVIEWED	JMD/JWM	09/28/06

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
DRAINAGE STRUCTURE SCHEDULE -12
FAI-72, MACARTHUR BLVD
SEC NO. 02-00382-02-PV
SEC NO. (84-9-4)A,HBK,BY,BY-1
SANGAMON COUNTY, ILLINOIS

SCALE: VERT. HORIZ.
DATE 12/18/2006
DRAWN BY CLG
CHECKED BY JWM