

FAU ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8071	*	SANGAMON	559	62
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
(84-9-4)A,HBK,BY,BY-1 * 02-00382-02-PV				

STORM SEWER SCHEDULE - 3

FROM #	INVERT ELEV	TO #	INVERT ELEV	STORM SEWER, CLASS A												TRENCHLESS PIPE INSTALLATION 72"	STORM SEWER JACKED IN PLACE SPECIAL	12" PIPE DRAINS SPECIAL	TRENCH BACKFILL	COMMENTS	
				TYPE 1				TYPE 2				TYPE 3		TY 5	TYPE 6						
				12"	18"	24"	36"	42"	48"	54"	66"	54"	60"	72"	66"						18"
170	592.21	165	591.93											152							
170	592.21	176	592.51											152							
171	601.12	172	600.92		30																
172	600.92	173	600.62		48													31			
173	600.62	174	600.42															9			
174	600.42	175	600.12															27			
175	600.12	176	599.92																		
176	592.51	181	592.79											152							
177	603.88	178	603.58	25																	
178	603.58	179	603.38	13																	
179	603.38	180	602.88	25																	
180	602.88	181	594.54	15															END SEWER @ TOP OF SLOPE		
181	592.79	186	593.08											152							
182	600.05	183	599.75		49													20			
183	599.75	184	599.55		1													1			
184	599.55	185	599.25		43													31			
185	599.25	186	599.05		15																
186	593.08	492	593.55											253							
187	600.25	182	600.05		30																
193	602.49	194	602.19	25																	
194	602.19	195	601.99	13																	
195	601.99	196	601.49	25																	
196	601.49	197	595.41	13															END SEWER @ TOP OF SLOPE		
197	593.66	202	593.95											152							
198	602.02	199	601.72	25																	
199	601.72	200	601.52	13																	
200	601.52	201	601.02	25																	
201	601.02	202	595.70	12															END SEWER @ TOP OF SLOPE		
202	593.95	208	594.24											152							
203	598.54	204	598.34		16																
204	598.34	205	598.04		42													17			
205	598.04	206	597.84		12													9			
206	597.84	207	597.54		36													26			
207	597.54	208	595.99		13																
208	594.24	213	594.41											91							
209	601.27	210	600.97	25																	
210	600.97	211	600.77	13																	
211	600.77	212	600.27	25																	
212	600.27	213	595.91	13															END SEWER @ TOP OF SLOPE		
213	594.41	218	594.58											85							
214	601.18	216	601.08	8																	
215	601.18	217	600.08	8																	
216	600.08	363	600.58	25																	
217	600.08	218	596.08	14															END SEWER @ TOP OF SLOPE		
218	594.58	221	594.71											64							
219	601.22	365	600.92	25																	

NOTE:
 SHADED ITEMS INDICATE DRAINAGE STRUCTURES NOT
 CONSTRUCTED IN GRADING & STRUCTURES CONTRACT.
 SHOWN FOR INFORMATION ONLY.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 STORM SEWER SCHEDULE -3
 FAI-72, MACARTHUR BLVD
 SEC NO. 02-00382-02-PV
 SEC NO. (84-9-4)A,HBK,BY,BY-1
 SANGAMON COUNTY, ILLINOIS

SCALE: VERT. DRAWN BY CLG
 HORIZ. CHECKED BY JWM
 DATE 12/18/2006



© Copyright Hanson Professional Services Inc. 2006
 12/18/2006
 \$FILES
 LAYOUT CLG 04/28/06
 DRAWN CLG 04/28/06
 REVIEWED JWB/JWM 04/28/06