CONTRACT #72541

| FAU ROUTE | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|---|---|---|---|
| 8071 | * | SANGAMON | 559 | 64 |
| STA. | | TO STA. | | |
| FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT | | |

(84-9-4)A,HBK,BY,BY-1 * 02-00382-02-PV

# STORM SEWER SCHEDULE – 5

| FROM (#) | INVERT ELEV | TO (#) | INVERT ELEV | STORM SEWER, CLASS A TYPE 1 12" | TYPE 1 18" | TYPE 1 24" | TYPE 1 36" | TYPE 2 42" | TYPE 2 48" | TYPE 2 54" | TYPE 2 66" | TYPE 3 54" | TYPE 3 60" | TYPE 3 72" | TY 5 66" | TYPE 6 18" | TYPE 6 72" | TRENCHLESS PIPE INSTALLATION 72" | STORM SEWER JACKED IN PLACE SPECIAL | 12" PIPE DRAINS SPECIAL | TRENCH BACKFILL | COMMENTS |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 270 | 622.16 | 271 | 600.33 | | | | | | | | | | | | | | | | | 79 | | END SEWER @ 270 |
| 272 | 599.51 | 273 | 597.85 | | | | | | | | | | | | | | | | | 51 | | END SEWER @ 272 |
| 274 | 621.19 | 275 | 610.00 | | | | | | | | | | | | | | | | | 25 | | END SEWER @ TOP OF SLOPE |
| 276 | 626.09 | 277 | 610.84 | | | | | | | | | | | | | | | | | 39 | | END SEWER @ TOP OF SLOPE |
| 278 | 625.00 | 279 | 610.03 | | | | | | | | | | | | | | | | | 32 | | END SEWER @ TOP OF SLOPE |
| 280 | 625.73 | 281 | 616.00 | | | | | | | | | | | | | | | | | 23 | | END SEWER @ TOP OF SLOPE |
| 282 | 638.34 | 283 | 618.95 | | | | | | | | | | | | | | | | | 41 | | END SEWER @ TOP OF SLOPE |
| 284 | 616.13 | 285 | 600.76 | | | | | | | | | | | | | | | | | 32 | | END SEWER @ TOP OF SLOPE |
| 286 | 638.40 | 287 | 618.95 | | | | | | | | | | | | | | | | | 39 | | END SEWER @ TOP OF SLOPE |
| 288 | 619.98 | 289 | 614.00 | | | | | | | | | | | | | | | | | 14 | | END SEWER @ TOP OF SLOPE |
| 291 | 594.90 | 6 | 590.50 | | | 152 | | | | | | | | | | | | | | | 71 | |
| 292 | 588.00 | 52 | 582.64 | | | | | | | | | | | | | | 535 | 348 | | | 99 | |
| 293 | 599.87 | 253 | 598.30 | | | | 222 | | | | | | | | | | | | | | 152 | |
| 294 | 598.75 | 295 | 599.00 | | | | 125 | | | | | | | | | | | | | | | |
| 299 | 596.83 | 229 | 596.58 | | 25 | | | | | | | | | | | | | | | | | |
| 304 | 598.88 | 256 | 598.73 | 13 | | | | | | | | | | | | | | | | | | |
| 307 | 628.44 | 308 | 613.00 | | | | | | | | | | | | | | | | | 32 | | END SEWER @ TOP OF SLOPE |
| 309 | 630.80 | 310 | 612.10 | | | | | | | | | | | | | | | | | 40 | | END SEWER @ TOP OF SLOPE |
| 311 | 627.48 | 312 | 617.40 | | | | | | | | | | | | | | | | | 27 | | |
| 313 | 629.67 | 314 | 617.66 | | | | | | | | | | | | | | | | | 25 | | END SEWER @ TOP OF SLOPE |
| 315 | 597.00 | 235 | 596.50 | 14 | | | | | | | | | | | | | | | | | | |
| 316 | 597.25 | 244 | 597.00 | 6 | | | | | | | | | | | | | | | | | | |
| 317 | 598.10 | 297 | 598.17 | | | | 94 | | | | | | | | | | | | | | 14 | |
| 317 | 598.38 | 323 | 598.28 | | | | | 15 | | | | | | | | | | | | | | |
| 317 | 598.38 | 296 | 599.23 | | | | 60 | | | | | | | | | | | | | | | |
| 318 | 599.54 | 321 | 598.43 | | | | 118 | | | | | | | | | | | | | | | |
| 319 | 599.70 | 322 | 599.38 | | | | 86 | | | | | | | | | | | | | | | |
| 325 | 618.99 | 326 | 610.00 | | | | | | | | | | | | | | | | | 22 | | END SEWER @ TOP OF SLOPE |
| 327 | 619.93 | 328 | 608.22 | | | | | | | | | | | | | | | | | 25 | | END SEWER @ TOP OF SLOPE |
| 329 | 618.26 | 330 | 606.78 | | | | | | | | | | | | | | | | | 25 | | END SEWER @ TOP OF SLOPE |
| 331 | 620.37 | 332 | 606.56 | | | | | | | | | | | | | | | | | 31 | | END SEWER @ TOP OF SLOPE |
| 333 | 621.25 | 334 | 608.05 | | | | | | | | | | | | | | | | | 29 | | END SEWER @ TOP OF SLOPE |
| 335 | 625.17 | 336 | 610.63 | | | | | | | | | | | | | | | | | 33 | | END SEWER @ TOP OF SLOPE |
| 337 | 625.50 | 338 | 610.63 | | | | | | | | | | | | | | | | | 32 | | END SEWER @ TOP OF SLOPE |
| 339 | 630.14 | 340 | 612.86 | | | | | | | | | | | | | | | | | 37 | | END SEWER @ TOP OF SLOPE |
| 341 | 629.21 | 342 | 613.94 | | | | | | | | | | | | | | | | | 33 | | END SEWER @ TOP OF SLOPE |
| 343 | 627.53 | 344 | 615.03 | | | | | | | | | | | | | | | | | 27 | | END SEWER @ TOP OF SLOPE |
| 345 | 621.97 | 346 | 600.42 | | | | | | | | | | | | | | | | | 46 | | END SEWER @ TOP OF SLOPE |
| 347 | 626.48 | 348 | 600.10 | | | | | | | | | | | | | | | | | 46 | | END SEWER @ TOP OF SLOPE |
| 349 | 627.85 | 350 | 615.64 | | | | | | | | | | | | | | | | | 27 | | END SEWER @ TOP OF SLOPE |
| 351 | 629.23 | 352 | 615.87 | | | | | | | | | | | | | | | | | 32 | | END SEWER @ TOP OF SLOPE |
| 353 | 630.90 | 354 | 599.34 | | | | | | | | | | | | | | | | | 104 | | END SEWER @ TOP OF SLOPE |
| 355 | 631.65 | 356 | 616.67 | | | | | | | | | | | | | | | | | 33 | | END SEWER @ TOP OF SLOPE |
| 357 | 630.38 | 358 | 616.50 | | | | | | | | | | | | | | | | | 29 | | END SEWER @ TOP OF SLOPE |
| 359 | 619.76 | 360 | 614.00 | | | | | | | | | | | | | | | | | 13 | | END SEWER @ TOP OF SLOPE |
| 361 | 596.44 | 362 | 595.78 | | | 216 | | | | | | | | | | | | | | | | |

NOTE:
SHADED ITEMS INDICATE DRAINAGE STRUCTURES NOT CONSTRUCTED IN GRADING & STRUCTURES CONTRACT. SHOWN FOR INFORMATION ONLY.

© Copyright Hanson Professional Services Inc. 2006

HANSON

12/18/2006
$FILE$

| | | |
|---|---|---|
| LAYOUT | CLG | 04/28/06 |
| DRAWN | CLG | 04/28/06 |
| REVIEWED | JAD/JWM | 04/28/06 |

| REVISIONS NAME | DATE |
|---|---|
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION
STORM SEWER SCHEDULE -5
FAI-72, MACARTHUR BLVD
SEC NO. 02-00382-02-PV
SEC NO. (84-9-4)A,HBK,BY,BY-1
SANGAMON COUNTY, ILLINOIS

SCALE: VERT. HORIZ.
DATE 12/18/2006
DRAWN BY CLG
CHECKED BY JWM