

**SUMMARY OF QUANTITIES**

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	SN 069-7500		
				F	NHF	
				80% FED. 20% STATE	80% FED. 20% STATE	
				Y007	I000	SFTY-3N
20200100	EARTH EXCAVATION	CU YD	595	595		
20400800	FURNISHED EXCAVATION	CU YD	455	455		
25000200	SEEDING, CLASS 2	ACRE	0.50	0.50		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	35	35		
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	35	35		
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	35	35		
25000700	AGRICULTURAL GROUND LIMESTONE	TON	0.8	0.8		
25100115	MULCH, METHOD 2	ACRE	0.50	0.50		
25100630	EROSION CONTROL BLANKET	SO YD	90	90		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	200	200		
28000400	PERIMETER EROSION BARRIER	FOOT	407	407		
28000500	INLET AND PIPE PROTECTION	EACH	3	3		
28001000	AGGREGATE (EROSION CONTROL)	TON	3	3		
28100807	STONE DUMPED RIPRAP, CLASS A4	TON	202	202		
28200200	FILTER FABRIC	SO YD	449	449		
35101400	AGGREGATE BASE COURSE, TYPE B	TON	91		91	
35800100	PREPARATION OF BASE	SO YD	596		596	
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	48		48	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	22.5		22.5	
40600300	AGGREGATE (PRIME COAT)	TON	117.8		117.8	
40600895	CONSTRUCTING TEST STRIP	EACH	1		1	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	956		956	
40600990	TEMPORARY RAMP	SO YD	50		50	
40800050	INCIDENTAL HOT MIX ASPHALT SURFACING	TON	46		46	
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SO YD	27847		27847	
44000100	PAVEMENT REMOVAL	SO YD	236	236		
44200168	PAVEMENT PATCHING, TYPE II, 14 INCH	SO YD	315		315	
44200172	PAVEMENT PATCHING, TYPE III, 14 INCH	SO YD	36		36	
44200174	PAVEMENT PATCHING, TYPE IV, 14 INCH	SO YD	382		382	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	371		371	
48203100	HOT-MIX ASPHALT SHOULDERS	TON	76	76		
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1		
50105220	PIPE CULVERT REMOVAL	FOOT	282	118	164	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	14940	14940		
51205200	TEMPORARY SHEET PILING	SO FT	2017	2017		
54001000	BOX CULVERT END SECTIONS	EACH	2	2		
54003000	CONCRETE BOX CULVERTS	CU YD	67.6	67.6		
54201483	PIPE CULVERTS, TYPE 2, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 18"	FOOT	180		180	

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310	115(RS-3,B-2)	MORGAN	42	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		STATE CONTRACT NO. 72663

CONSTRUCTION TYPE CODES  
Y007 - MINOR STRUCTURES (STORM SEWERS, CULVERTS, SHOWSHED, PUMP STATIONS, RETAINING WALLS, ETC.)  
I000 - BITUMINOUS CONCRETE  
SFTY-3N - IMPACT ATTENUATORS (CRASH CUSHION/IMPACT ATTENUATOR)

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION  <b>SUMMARY OF QUANTITIES</b> F.A.P. ROUTE 310 (US 67) SCOTT COUNTY  SCALE: VERT. NONE HORIZ. NONE DATE 03/01/2004	DRAWN BY AJP CHECKED BY JOJ
NAME	DATE		

Rev.