

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310	115(RS-3,B-2)	MORGAN	42	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
STATE CONTRACT NO. 72663				

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	SN 069-7500		
				F	NHE	
				80% FED. 20% STATE	80% FED. 20% STATE	
				Y007	I000	SFTY-3N
54201501	PIPE CULVERTS, TYPE 2, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 36"	FOOT	135		135	
54202335	PIPE CULVERTS, TYPE 3, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 30"	FOOT	164		164	
60802030	AUTOMATIC FLAP GATE 30"	EACH	1	1		
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	60.7	60.7		
* 63000025	STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES	FOOT	26.8	26.8		
* 63000130	STEEL PLATE BEAM GUARD RAIL, TYPE A (SPECIAL)	FOOT	50.0	50.0		
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2	2		
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	4	4		
63200310	GUARDRAIL REMOVAL	FOOT	292	292		
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	9	9		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	5	1	
67100100	MOBILIZATION	L SUM	1	1		
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1		
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1		
70101205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321 (SPECIAL)	EACH	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	5	5		
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	949		949	
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	3533		3533	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	1459		1459	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	600	600		
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	550	550		
* 78001120	PAINT PAVEMENT MARKING - LINE 5"	FOOT	23478		23478	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	133		133	
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	6	6		
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	133	133		
X0321100	GEOTEXTILE RETAINING WALL	SO FT	29	29		
X0324118	GRANULAR CULVERT BACKFILL	CU YD	368	368		
35600716	HOT-MIX ASPHALT BASE COURSE WIDENING, 10"	SO YD	159	159		
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	2423		2423	
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	321		321	
40600625	LEVELING BINDER (MACHINE METHOD) N50	TON	1212		1212	
X7200201	WIDTH RESTRICTION SIGNING	L SUM	1	1		
50800515	BAR SPLICERS	EACH	56	56		
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2			2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2			2
* Z0054517	ROCK FILL - FOUNDATION	TON	130	130		

CONSTRUCTION TYPE CODES
Y007 - MINOR STRUCTURES (STORM SEWERS, CULVERTS, SHOWSHED, PUMP STATIONS, RETAINING WALLS, ETC.)
I000 - BITUMINOUS CONCRETE
SFTY-3N - IMPACT ATTENUATORS (CRASH CUSHION/IMPACT ATTENUATOR)

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
F.A.P. ROUTE 310 (US 67)
SCOTT COUNTY
SCALE: VERT. NONE
HORIZ. NONE
DATE 03/01/2004
DRAWN BY AJP
CHECKED BY JDJ

* SPECIALTY ITEMS