•	F.A.P SECTION		(COUNTY		TOTAL SHEETS	SHEET NO.
	75 •			CHRISTIAN		96	2
	STA. TO STA.						
	FED. ROAD DIST. NO.		ILLINOIS	FED.	AID	PROJEC1	

• D 6 RESURFACING 2007

GENERAL NOTES

- ALL OF THE DISTURBED AREAS WITHIN THE RIGHT OF WAY NOT COVERED BY SURFACING MATERIAL SHALL BE SEEDED.
- 2. CONTRACTOR SHALL PROVIDE ADEQUATE DRAINAGE AND EROSION PROTECTION FOR THE DURATION OF THIS PROJECT.
- SEEDING WILL NOT BE PERMITTED AT ANY TIME WHEN THE GROUND IS FROZEN, WET OR IN AN UNTILLABLE CONDITION. LOCATIONS TO BE SEEDED SHALL BE DETERMINED BY THE ENGINEER.
- 4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING UTILITY PROPERTY FROM CONSTRUCTION OPERATIONS AS OUTLINED IN ARTICLE 107.31 OF THE STANDARD SPECIFICATIONS. THE JULIE NUMBER IS 800-892-0123. A MINIMUM OF FORTY-EIGHT HOURS ADVANCE NOTICE IS REQUIRED. ANY DAMAGE TO THE UNDERGROUND FACILITIES, CAUSED BY THE CONTRACTOR SHALL BE REPAIRED TO THE SATISFACTION OF THE DEPARTMENT AT THE CONTRACTOR'S EXPENSE, INCLUDING TEMPORARY REPAIRS WHICH MAY BE REQUIRED TO KEEP THE FACILITY OPERATIONAL WHILE MATERIAL IS BEING OBTAINED TO MAKE PERMANENT REPAIRS.
- 5. THE LOCATIONS OF THOSE BURIED AND ABOVEGROUND UTILITIES SHOWN ARE APPROXIMATE, ARE SHOWN FOR CONTRACTOR INFORMATIONAL USE ONLY, AND ARE NOT TO BE REFERENCED FOR CONSTRUCTIONS PURPOSES. THE IMPLIED PRESENCE OR ABSENCE OF UTILITIES IS NOT TO BE CONSTRUED BY THE OWNER, ENGINEER, CONTRACTOR, OR SUBCONTRACTORS TO BE AN ACCURATE AND COMPLETE REPRESENTATION OF UTILITIES THAT MAY OR MAY NOT EXIST ON THE CONSTRUCTION SITE. BURIED AND ABOVEGROUND UTILITY LOCATION, IDENTIFICATION, AND MARKING ARE THE SOLE RESPONSIBILITY OF THE CONTRACTOR, REROUTING, DISCONNECTION, PROTECTION, ETC. OF ANY UTILITIES MUST BE COORDINATED BETWEEN THE CONTRACTOR, UTILITY COMPANY, AND OWNER. SITE SAFETY, INCLUDING THE AVOIDANCE OF HAZARDS ASSOCIATED WITH BURIED AND ABOVEGROUND UTILITIES, REMAINS THE SOLE RESPONSIBILITY OF THE CONTRACTOR.
- 6. THE THICKNESS OF HOT-MIX ASPHALT MIXTURES SHOWN ON THE PLANS IS THE NOMINAL THICKNESS. DEVIATIONS FROM THE NOMINAL THICKNESS WILL BE PERMITTED WHEN SUCH DEVIATIONS OCCUR DUE TO IRREGULARITIES IN THE EXISTING SURFACE OR BASE ON WHICH THE BITUMINOUS MIXTURE IS PLACED.
- AGGREGATE (PRIME COAT): FA 20 MAY BE USED IN ADDITION TO THE GRADATIONS LISTED IN THE 2ND PARAGRAPH OF ARTICLE 1003.03(c).
- FOR STABILIZATION, ALL TYPE III BARRICADES SHALL REQUIRE A MINIMUM OF FOUR SANDBAGS PER BARRICADE.
- 9. WHERE SECTION OR SUBSECTION MONUMENTS ARE ENCOUNTERED, THE ENGINEER SHALL BE NOTIFIED BEFORE SUCH MONUMENTS ARE REMOVED. THE CONTRACTOR SHALL PROTECT AND CAREFULLY PRESERVE ALL MONUMENTS UNTIL AN AUTHORIZED SURVEYOR OR AGENT HAS WITNESSED OR OTHERWISE REFERENCED THEIR LOCATION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR HAVING AN AUTHORIZED SURVEYOR RE-ESTABLISH ANY SECTION OR SUBSECTION MONUMENTS DESTROYED BY HIS OPERATIONS.

10. THE FOLLOWING RATES OF APPLICATION HAVE BEEN USED IN CALCULATING

GRANULAR MATERIALS
BITUMINOUS MATERIAL (PRIME COAT)
HOT-MIX ASPHALT SURF CSE
HOT-MIX ASPHALT LEVELING BINDER
AGGREGATE (PRIME COAT)

AGGREGATE (PRIME COAT)

O.002

TON/SQ YD/IN
O.002

TON/SQ YD/IN

- 11. ANY REFERENCE TO A STANDARD IN THESE PLANS SHALL BE INTERPRETED TO MEAN THE EDITION AS INDICATED BY THE SUBNUMBER LISTED ON THE INDEX OF SHEETS OR THE COPY OF THE STANDARD INCLUDED IN THESE PLANS.
- 12. UNLESS NOTED OTHERWISE, STATIONS AND OFFSETS REFER TO CENTERLINE OF PROJECT.
- 13. EVERY TREE SHALL BE SAVED IF POSSIBLE. THE ENGINEER IN THE FIELD WILL VERIFY AND MARK ALL TREES REQUIRED TO BE REMOVED. SHOULD THE ENGINEER'S DECISION INCREASE OR DECREASE THE OUANTITIES OF WORK TO BE PERFORMED FROM THE PLANS, THE CONTRACTOR SHALL ACCEPT PAYMENT AS STATED IN ARTICLE 104.02 OF THE STANDARD SPECIFICATIONS. TREES OUTSIDE THE LIMITS OF CONSTRUCTION SHALL NOT BE DISTURBED UNLESS DESIGNATED BY THE ENGINEER.
- 14. IN ADDITION TO FIELD SURVEYS AND AERIAL SURVEYS, PLAN DIMENSIONS AND DETAILS RELATIVE TO THE EXISTING FACILITIES HAVE BEEN TAKEN FROM EXISTING PLANS AND ARE SUBJECT TO CONSTRUCTION VARIATIONS. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY SUCH DIMENSIONS AND DETAILS IN THE FIELD. SUCH VARIATIONS SHALL NOT BE A CAUSE FOR ADDITIONAL COMPENSATION DUE TO A CHANGE IN THE SCOPE OF THE WORK. HOWEVER, THE CONTRACTOR WILL BE PAID FOR THE QUANTITY ACTUALLY FURNISHED AT THE UNIT PRICE BID FOR THE WORK.
- 15. EARTH EXCAVATION NECESSARY TO CONSTRUCT HOT-MIX ASPHALT SHOULDERS 8" SHALL BE PAID FOR AS EARTH EXCAVATION WIDENING AS SPECIFIED IN SECTION 202 OF THE STANDARD SPECIFICATIONS.
- 16. THE EXACT LOCATIONS AND SIZES OF PAVEMENT PATCHES SHALL BE DETERMINED BY THE ENGINEER IN THE FIELD.
- 17. BEFORE ORDERING STORM SEWER, THE CONTRACTOR SHALL CONSULT THE ENGINEER FOR EXACT LENGTHS.
- 18. ALL ELEVATIONS REFER TO U.S.G.S. MEAN SEA LEVEL DATUM.

COMMITMENTS:

1 884

DISTRICT SIX						
EXAMINED Jovenner 29 20 06						
OPERATIONS ENGINEER						
EXAMINED Nov 28 20 00						
PROGRAM IMPLEMENTATION ENGINEER						
EXAMINED DECEMBER 2006						
PROGRAM DEVELOPMENT ENGINEER						

Mix No.	No. 1	No. 2	No. 3	No. 4
Mixture Use(s)	Hot-Mix Asphalt Surface	Level Binder	Incidental HMA Surface	Hot-Mix Asphalt Shoulders
AC/PG:	SBS PG 70-22	PG 64-22	PG 64-22	PG 58-22
RAP X:	0%	15%	15%	15%
Design Air Volds:	4.0% @ N Design=70	4.0% @ N Design=70	4.0% @ N Design≈50	2.0% @ N Design=3
Mixture Composition: (Gradation Mixture)	IL 9.5 or 12.5	IL 9.5	IL 9.5 or 12.5	BAM
Friction Aggregate:	Mix "D"	N/A	Mi× "C"	N/A

REVISIONS
NAME DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

GENERAL NOTES

FAP 75 (IL 29)

SECTION D 6 RESURFACING 2007

CHRISTIAN COUNTY

SCALE: VERT. DRAWN BY

SCALE: VERT. HORIZ. DATE

CHECKED BY

LOT DATE = 12/14/2006 LLE NAYE = ci-ymro,pecs/v1654683\shtgemote.d; LTS SCALE = 43.3735 / IM, SER NAME = myers,p