

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
75	*	CHRISTIAN	97	27
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

*D 6 RESURFACING 2007

EARTH EXCAVATION WIDENING

LOCATION	LT SHLD WIDTH	RT SHLD WIDTH	DEPTH (INCH)	VOLUME (CU YD)		
I-29 MAINLINE						
STA 28+80.00	TO	STA 31+19.00	3	3	8	35.41
STA 32+05.00	TO	STA 39+52.00	0	3	8	55.33
STA 32+05.00	TO	STA 39+86.00	3	0	8	57.85
STA 40+28.00	TO	STA 41+98.04 BK	0	3	8	12.60
STA 40+50.00	TO	STA 41+98.04 BK	3	0	8	10.97
STA 42+39.60 AH	TO	STA 58+66.00 BK	3	3	8	240.95
STA 58+70.03 AH	TO	STA 58+79.00	3	3	8	1.33
STA 60+81.00	TO	STA 79+60.00	0	3	8	139.19
STA 60+81.00	TO	STA 80+05.00	3	0	8	142.52
STA 80+48.00	TO	STA 100+89.78	0	3	8	151.24
STA 80+45.00	TO	STA 100+89.78	3	0	8	151.47
STA 137+17.09	TO	STA 204+26.00	0	3	8	496.96
STA 137+17.09	TO	STA 139+21.00	3	0	8	15.10
STA 139+75.00	TO	STA 158+52.00	3	0	8	139.04
STA 159+26.00	TO	STA 163+81.00	3	0	8	33.70
STA 164+50.00	TO	STA 204+16.00	3	0	8	293.78
STA 205+27.00	TO	STA 206+47.00	0	3	8	8.89
STA 205+09.00	TO	STA 206+47.00	3	0	8	10.22
TOTAL						1,996.55

HOT-MIX ASPHALT SURFACE REMOVAL (VARIABLE DEPTH)

LOCATION	PAVEMENT WIDTH (FOOT)	LT SHLD WIDTH	RT SHLD WIDTH	AREA (SQ YD)
I-29 MAINLINE				
STA 29+15.00	TO	STA 41+98.04 BK	24	3,421.44
STA 42+39.60 AH	TO	STA 58+66.00 BK	24	4,337.07
STA 58+70.03 AH	TO	STA 58+79.00	24	23.92
STA 58+79.00	TO	STA 60+81.00	BRIDGE OMISSION	
STA 60+81.00	TO	STA 100+89.78	24	10,690.08
STA 100+89.78	TO	STA 102+35.45	24	517.94
STA 102+35.45	TO	STA 107+29.75	26 TO 36	2,141.97
STA 107+29.75	TO	STA 110+72.28	36	1,674.59
STA 110+72.28	TO	STA 113+67.47	36 TO 26	1,279.16
STA 113+67.47	TO	STA 119+82.61	24	2,187.16
STA 119+82.61	TO	STA 124+54.86	26 TO 36	2,046.42
STA 124+54.86	TO	STA 129+69.26	36	2,514.84
STA 129+69.26	TO	STA 137+17.09	36 TO 26	3,240.60
STA 137+17.09	TO	STA 206+12.00	24	18,386.43
TOTAL				52,461.62

HOT-MIX ASPHALT SURFACE REMOVAL 2"

LOCATION	LENGTH (FOOT)	PAVEMENT WIDTH (FOOT)	AREA (SQ YD)			
I-29 MAINLINE						
STA 520+72.00	TO	STA 524+01.34	329.34	52	1,902.85	
STA 524+01.34	TO	STA 526+85.47	284.13	VAR	2,692.71	
STA 526+85.47	TO	STA 552+05.00	2,519.53	40	11,197.91	
STA 552+05.00	TO	STA 554+07.00	202.00	40 TO 48	987.56	
STA 554+07.00	TO	STA 564+80.00	1,073.00	48	5,722.67	
STA 564+80.00	TO	STA 570+17.12	537.12	48 TO 50	2,924.32	
STA 570+17.12	TO	STA 572+17.12	200.00	50 TO 60	1,222.22	
STA 572+17.12	TO	STA 577+05.51	488.39	60 TO 62	3,310.20	
STA 577+05.51	TO	STA 583+11.84	606.33	VAR	5,596.03	
STA 583+11.84	TO	STA 583+24.00	12.16	48	64.85	
STA 47+07.92	TO	STA 49+22.00	214.08	48 TO 33	963.36	
STA 49+22.00	TO	STA 54+22.00	500.00	33	1,833.33	
STA 54+22.00	TO	STA 55+37.00	115.00	33 TO 30	402.50	
STA 55+37.00	TO	STA 56+92.00	155.00	30 TO 21	439.17	
STA 56+92.00	TO	STA 59+46.00	254.00	24	677.33	
STA 59+46.00	TO	STA 60+66.00	120.00	24 TO 33	380.00	
STA 60+66.00	TO	STA 63+74.00	308.00	33	1,129.33	
STA 63+74.00	TO	STA 64+66.00	92.00	33 TO 30	322.00	
STA 64+66.00	TO	STA 65+99.00	133.00	30 TO 24	399.00	
STA 65+99.00	TO	STA 79+89.00	1,390.00	24	3,706.67	
STA 79+89.00	TO	STA 84+78.00	489.00	27	1,467.00	
STA 84+78.00	TO	STA 87+81.23	303.23	VAR	1,026.15	
STA 7+18.82	TO	STA 13+43.26	624.44	VAR	2,394.36	
STA 13+43.26	TO	STA 15+31.02	187.76	VAR	1,592.09	
STA 15+31.02	TO	STA 17+42.49	211.47	42	859.79	
STA 17+42.49	TO	STA 26+00.00	857.51	VAR	5,473.81	
STA 26+00.00	TO	STA 27+47.00	147.00	30 TO 28	473.67	
SIDE STREETS/ROADS & ENTRANCES (FROM SCHEDULE ON SHEET 97)						3,268.57
TOTAL						62,429.45

LEVEL BINDER (MACHINE METHOD), N70

LOCATION	PAVEMENT WIDTH (FOOT)	PAVEMENT AREA (SQ YD)	TONS		
I-29 MAINLINE					
STA 28+80.00	TO	STA 41+98.04 BK	24	3,514.77	147.62
STA 42+39.60 AH	TO	STA 58+66.00 BK	24	4,337.07	182.16
STA 58+70.03 AH	TO	STA 58+79.00	24	23.92	1.00
STA 60+81.00	TO	STA 100+89.78	24	10,690.08	448.98
STA 100+89.78	TO	STA 102+35.45	24	388.45	16.31
STA 102+35.45	TO	STA 107+29.75	26 TO 36	1,702.59	71.51
STA 107+29.75	TO	STA 110+72.28	36	1,370.12	57.55
STA 110+72.28	TO	STA 113+67.47	36 TO 26	1,016.77	42.70
STA 113+67.47	TO	STA 119+82.61	24	1,640.37	68.90
STA 119+82.61	TO	STA 124+54.86	26 TO 36	1,626.64	68.32
STA 124+54.86	TO	STA 129+69.26	36	2,057.60	86.42
STA 129+69.26	TO	STA 137+17.09	36 TO 26	2,575.86	108.19
STA 137+17.09	TO	STA 206+47.00	24	18,479.76	776.15
TOTAL				2,075.81	

PLOT DATE = 12/15/2006
 FILE NAME = c:\p\projects\654683\schedules.dgn
 PLOT SCALE = 1/8"=1'-0"
 USER NAME = laughlin-1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF QUANTITIES
 FAP 75 (IL 29)
 SECTION D 6 RESURFACING 2007
 CHRISTIAN COUNTY
 SCALE: VERT. DRAWN BY
 DATE HORIZ. CHECKED BY