

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
75	*	CHRISTIAN	97	28

STA.	TO STA.
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT

*D 6 RESURFACING 2007

TEMPORARY RAMP

LOCATION			LENGTH (FOOT)	PAVEMENT WIDTH (FOOT)	AREA (SQ YD)
I-29 MAINLINE					
STA 520+72.00	TO	STA 520+78.67	6.67	49.0	36.31
STA 27+42.00	TO	STA 27+47.00	6.67	26.0	19.27
STA 28+80.00	TO	STA 28+85.00	5.00	26.0	14.44
STA 206+40.33	TO	STA 206+47.00	6.67	24.0	17.79
SIDE STREETS					
Cheney	LT		6.67	26.0	19.27
Cheney	RT		6.67	36.5	27.05
Knute Rockne Road	LT		6.67	46.5	34.46
Sportsman Drive	LT		6.67	26.0	19.27
Hawley Street	RT		6.67	35.0	25.94
Haner Street	RT		6.67	28.5	21.12
Lincoln Street	LT		6.67	26.5	19.64
Maxwell Street	RT		6.67	29.5	21.86
Taft Street	RT		6.67	32.5	24.09
Bidwell Street	LT		6.67	40.0	29.64
West Bryant Street	RT		6.67	25.0	18.53
Wilson Street	RT		6.67	21.0	15.56
John Street	RT		6.67	18.5	13.71
W Park			6.67	52.0	38.54
S Webster			6.67	37.0	27.42
Washington	LT		6.67	27.0	20.01
Washington	RT		6.67	36.0	26.68
Main Street	LT		6.67	27.0	20.01
Main Street	RT		6.67	27.0	20.01
Walnut Street	LT		6.67	37.0	27.42
Walnut Street	RT		6.67	37.0	27.42
Cherokee Street	LT		6.67	31.0	22.97
Cherokee Street	RT		6.67	31.0	22.97
Cheyenne Street	RT		6.67	24.0	17.79
Shawnee Street	LT		6.67	28.0	20.75
Shawnee Street	RT		6.67	24.0	17.79
Chestnut Street	RT		6.67	24.0	17.79
Long Street	LT		6.67	24.0	17.79
Long Street	RT		6.67	20.0	14.82
Paw Paw Street	RT		6.67	23.0	17.05
McAdam	LT		6.67	30.0	22.23
Main Cross	LT		6.67	40.0	29.64
Main Cross	RT		6.67	30.0	22.23
Pershing	LT		5.00	66.0	36.67
Pershing	RT		5.00	65.0	36.11
Kennedy	LT		5.00	25.0	13.89
Lake	RT		5.00	26.0	14.44
Lake	LT		5.00	26.0	14.44
1550 East	LT		5.00	50.0	27.78
Velma Road	LT		5.00	72.0	40.00
Velma Road	RT		5.00	80.0	44.44
			TOTAL		1,057.05

AGGREGATE SHOULDERS, TYPE B

LOCATION			LT SHLD WIDTH	RT SHLD WIDTH	AVERAGE DEPTH (INCH)	TONS
I-29 MAINLINE						
STA 8+90.00	TO	STA 10+00.00	0	3	2.5	5.22
STA 10+68.00	TO	STA 11+47.00	0	3	2.5	3.75
STA 11+61.00	TO	STA 13+43.00	3	0	2.5	8.64
STA 14+75.00	TO	STA 19+04.00	0	3	2.5	20.36
STA 15+30.00	TO	STA 17+83.00	3	0	2.5	12.01
STA 20+23.00	TO	STA 27+47.00	3	3	2.5	68.71
STA 28+80.00	TO	STA 31+19.00	3	3	2.5	22.68
STA 32+05.00	TO	STA 39+52.00	0	3	2.5	35.45
STA 32+05.00	TO	STA 39+86.00	3	0	2.5	37.06
STA 40+28.00	TO	STA 41+98.04 BK	0	3	2.5	8.07
STA 40+50.00	TO	STA 41+98.04 BK	3	0	2.5	7.03
STA 42+39.60 AH	TO	STA 58+66.00 BK	3	3	2.5	154.36
STA 58+70.03 AH	TO	STA 58+79.00	3	3	2.5	0.85
STA 60+81.00	TO	STA 79+60.00	0	3	2.5	89.17
STA 60+81.00	TO	STA 80+05.00	3	0	2.5	91.30
STA 80+48.00	TO	STA 127+33.00	0	3	2.5	222.32
STA 80+45.00	TO	STA 109+09.00	3	0	2.5	135.91
STA 110+51.00	TO	STA 127+33.00	3	0	2.5	79.82
STA 128+92.00	TO	STA 136+21.00	3	0	2.5	34.59
STA 128+92.00	TO	STA 204+26.00	0	3	2.5	357.52
STA 137+00.00	TO	STA 139+21.00	3	0	2.5	10.49
STA 139+75.00	TO	STA 158+52.00	3	0	2.5	89.07
STA 159+26.00	TO	STA 163+81.00	3	0	2.5	21.59
STA 164+50.00	TO	STA 204+16.00	3	0	2.5	188.20
STA 205+27.00	TO	STA 206+47.00	0	3	2.5	5.69
STA 205+09.00	TO	STA 206+47.00	3	0	2.5	6.55
					TOTAL	1,716.41

PLOT DATE = 12/15/2006
 FILE NAME = c:\p\projects\4654683\schedule.dgn
 PLOT SCALE = 1/8"=1'-0" / IN.
 USER NAME = laughlin-1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF QUANTITIES
 FAP 75 (IL 29)
 SECTION D 6 RESURFACING 2007
 CHRISTIAN COUNTY
 SCALE: VERT. DRAWN BY
 HORIZ. CHECKED BY
 DATE