

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
75	*	CHRISTIAN	97	35
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

*D 6 RESURFACING 2007

PREFORMED PLASTIC PAVEMENT MARKING, TYPE B, LETTERS AND SYMBOLS

LOCATION	LANE	DIRECTION	SYMBOL TYPE	SO FT
IL-29 MAINLINE				
STA 523+05	RTL	EB	ONLY	20.8
STA 523+41	LTL	EB	LEFT TURN	15.6
STA 523+41	RTL	EB	RIGHT TURN	15.6
STA 524+25	RTL	EB	ONLY	20.8
STA 524+60	LTL	EB	LEFT TURN	15.6
STA 524+60	RTL	EB	RIGHT TURN	15.6
STA 526+06	LTL	WB	LEFT TURN	15.6
STA 527+31	LTL	WB	LEFT TURN	15.6
STA 529+44	LTL	EB	LEFT TURN	15.6
STA 530+61	LTL	EB	LEFT TURN	15.6
STA 532+00	2LLT	WB	LEFT TURN	15.6
STA 533+98	2LLT	EB	LEFT TURN	31.2
STA 535+98	2LLT	EB	LEFT TURN	31.2
STA 537+98	2LLT	EB	LEFT TURN	31.2
STA 539+98	2LLT	EB	LEFT TURN	31.2
STA 541+98	2LLT	EB	LEFT TURN	31.2
STA 543+98	2LLT	EB	LEFT TURN	31.2
STA 545+98	2LLT	EB	LEFT TURN	31.2
STA 547+98	2LLT	EB	LEFT TURN	31.2
STA 549+98	2LLT	EB	LEFT TURN	31.2
STA 551+98	2LLT	EB	LEFT TURN	31.2
STA 554+28	LTL	EB	LEFT TURN	15.6
STA 555+79	LTL	EB	LEFT TURN	15.6
STA 557+26	RTL	WB	RIGHT TURN	15.6
STA 557+99	RTL	WB	RIGHT TURN	15.6
STA 558+94	RTL	WB	RIGHT TURN	15.6
STA 559+89	RTL	WB	RIGHT TURN	15.6
STA 561+36	RTL	WB	RIGHT TURN	15.6
STA 572+34	LTL	EB	LEFT TURN	15.6
STA 573+32	LTL	EB	LEFT TURN	15.6
STA 574+20	LTL	WB	LEFT TURN	15.6
STA 575+62	CL	EB	STRAIGHT	11.5
STA 575+62	RL	EB	RIGHT TURN	15.6
STA 575+62	LTL	EB	LEFT TURN	15.6
STA 576+71	CL	EB	LEFT LANE	15.6
STA 576+71	LTL	EB	LEFT TURN	15.6
STA 576+71	RL	EB	RIGHT LANE	15.6
STA 577+76	RTL	S	RIGHT TURN	15.6
CONTINUED	CONTINUED	CONTINUED	CONTINUED	CONTINUED

PREFORMED PLASTIC PAVEMENT MARKING, TYPE B, LETTERS AND SYMBOLS

LOCATION	LANE	DIRECTION	SYMBOL TYPE	SO FT
IL-29 MAINLINE				
STA 577+76	CL	S	STRAIGHT	11.5
STA 577+76	LL	S	LEFT TURN	15.6
STA 579+47	CL	WB	STRIGHT	11.5
STA 579+47	LL	WB	LEFT TURN	15.6
STA 580+26	CL	WB	STRAIGHT	11.5
STA 580+26	RTL	WB	RIGHT TURN	15.6
STA 580+26	LL	WB	LEFT TURN	15.6
STA 581+57	LTL	EB	LEFT TURN	15.6
STA 48+27	LTL	EB	LEFT TURN	15.6
STA 49+18	LTL	EB	LEFT TURN	15.6
STA 50+23	LTL	WB	LEFT TURN	15.6
STA 50+82	LTL	WB	LEFT TURN	15.6
STA 51+92	LTL	EB	LEFT TURN	15.6
STA 52+81	LTL	EB	LEFT TURN	15.6
STA 53+75	LTL	WB	LEFT TURN	15.6
STA 54+17	LTL	WB	LEFT TURN	15.6
STA 61+64	LTL	EB	LEFT TURN	15.6
STA 62+21	LTL	EB	LEFT TURN	15.6
STA 63+21	LTL	WB	LEFT TURN	15.6
STA 63+70	LTL	WB	LEFT TURN	15.6
STA 11+75	LTL	EB	LEFT TURN	15.6
STA 13+59	LTL	EB	LEFT TURN	15.6
STA 14+99	LTL	EB	LEFT TURN	15.6
STA 16+58	LTL	EB	LEFT TURN	15.6
STA 18+11	LTL	EB	LEFT TURN	15.6
STA 20+09	LTL	WB	LEFT TURN	15.6
STA 21+04	LTL	WB	LEFT TURN	15.6
STA 107+32	LTL	EB	LEFT TURN	15.6
STA 108+52	LTL	EB	LEFT TURN	15.6
STA 109+52	LTL	EB	LEFT TURN	15.6
STA 126+36	LTL	EB	LEFT TURN	15.6
STA 127+31	LTL	EB	LEFT TURN	15.6
STA 128+80	LTL	WB	LEFT TURN	15.6
STA 129+66	LTL	WB	LEFT TURN	15.6
PARK				
STA 9+13	RTL	EB	RIGHT TURN	15.6
STA 9+13	LTL	EB	LEFT TURN	15.6
STA 9+13	CL	EB	STRAIGHT	11.5
WEBSTER				
STA 114+54	RL	N	COMBINATION	26
STA 114+72	LL	N	LEFT TURN	15.6
MAIN CROSS-NORTH	RTL	SB	RIGHT TURN	15.6
MAIN CROSS-SOUTH	RTL	NB	RIGHT TURN	15.6
TOTAL				1,388.70

PLOT DATE = 12/15/2006
 FILE NAME = c:\p\projects\654683\schedule.dgn
 PLOT SCALE = 1/8"=1'-0"
 USER NAME = laughlin-1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF QUANTITIES
 FAP 75 (IL 29)
 SECTION D 6 RESURFACING 2007
 CHRISTIAN COUNTY
 SCALE: VERT. DRAWN BY
 HORIZ. CHECKED BY
 DATE