

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
75	*	CHRISTIAN	97	37
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 24"

LOCATION	DIRECTION	DESCRIPTION	LENGTH (FOOT)
IL-29 MAINLINE			
STA 524+88.00	EB	STOP BAR	11.5
STA 525+10.00	EB	STOP BAR	12.0
STA 525+32.44	EB	STOP BAR	14.0
STA 525+74.00	WB	STOP BAR	14.3
STA 525+90.01	WB	STOP BAR	12.0
STA 556+07.00	EB	STOP BAR	24.2
STA 556+93.00	WB	STOP BAR	29.4
STA 578+14.00	S	STOP BAR	23.8
STA 578+10.33	SW	STOP BAR	18.8
STA 579+12.00	WB	STOP BAR	23.8
STA 579+32.32	NW	STOP BAR	18.2
STA 52+97.00	EB	STOP BAR	23.0
STA 53+60.00	WB	STOP BAR	23.0
STA 62+36.00	EB	STOP BAR	23.0
STA 63+00.00	WB	STOP BAR	23.0
CHENEY ST.			
STA 524+76.79	TO STA 524+95.19	S	STOP BAR 20.0
STA 525+03.70	TO STA 525+16.31	S	STOP BAR 13.8
STA 525+63.71	TO STA 525+79.37	N	STOP BAR 18.6
STA 526+15.33	TO STA 526+32.28	NE	STOP BAR 22.0
PARK			
STA 9+50.30	E	STOP BAR	12.0
STA 9+66.28	E	STOP BAR	12.0
STA 9+45.55	TO STA 9+62.41	SE	STOP BAR 19.9
NORTH WEBSTER			
STA 115+05.32	N	STOP BAR	12.0
STA 115+11.17	N	STOP BAR	12.0
STA 114+93.58	TO STA 115+05.29	NE	STOP BAR 17.8
N. MAIN ST.	S	STOP BAR	20.0
S. MAIN ST.	N	STOP BAR	17.0
KENNEDY		STOP BAR	24.5
N. LAKE		STOP BAR	18.3
S. LAKE		STOP BAR	13.2
TOTAL			570.1

HOT-MIX ASPHALT SURFACE REMOVAL (DECK)

LOCATION	BRIDGE WIDTH (FOOT)	AREA (SQ YD)
I-29 MAINLINE		
STA 27+47.00 TO STA 28+80.00	44	650.22
STA 58+79.00 TO STA 60+81.00	30	673.33
TOTAL		1,323.55

HMA SHOULDERS 8"

LOCATION	LT SHLD WIDTH	RT SHLD WIDTH	AREA (SQ YD)
I-29 MAINLINE			
STA 28+80.00 TO STA 31+19.00	3	3	159.33
STA 32+05.00 TO STA 39+52.00	0	3	249.00
STA 32+05.00 TO STA 39+86.00	3	0	260.33
STA 40+28.00 TO STA 41+98.04 BK	0	3	56.68
STA 40+50.00 TO STA 41+98.04 BK	3	0	49.35
STA 42+39.60 AH TO STA 58+66.00 BK	3	3	1,084.27
STA 58+70.03 AH TO STA 58+79.00	3	3	5.98
STA 60+81.00 TO STA 79+60.00	0	3	626.33
STA 60+81.00 TO STA 80+05.00	3	0	641.33
STA 80+48.00 TO STA 100+89.78	0	3	680.59
STA 80+45.00 TO STA 100+89.78	3	0	681.59
STA 137+17.09 TO STA 204+26.00	0	3	2,236.30
STA 137+17.09 TO STA 139+21.00	3	0	67.97
STA 139+75.00 TO STA 158+52.00	3	0	625.67
STA 159+26.00 TO STA 163+81.00	3	0	151.67
STA 164+50.00 TO STA 204+16.00	3	0	1,322.00
STA 205+27.00 TO STA 206+47.00	0	3	40.00
STA 205+09.00 TO STA 206+47.00	3	0	46.00
TOTAL			8,984.39

VALVE VAULTS TO BE ADJUSTED

LOCATION	EACH
IL 29 MAINLINE	
STA 526+40.00 RT	1
STA 543+51.00 RT	1
STA 543+55.00 RT	1
STA 543+90.00 RT	1
STA 543+95.00 RT	1
STA 546+91.00 RT	1
STA 551+22.00 RT	1
STA 551+30.00 RT	1
STA 564+55.00 RT	1
STA 564+55.00 RT	1
STA 564+59.00 RT	1
STA 577+85.00 RT	1
STA 115+02.00 LT	1
STA 582+62.00 RT	1
STA 49+49.00 RT	1
STA 50+52.00 RT	1
STA 53+11.00 RT	1
STA 53+56.00 RT	1
STA 62+48.00 RT	1
STA 69+61.00 RT	1
STA 79+60.00 RT	1
STA 79+87.00 RT	1
TOTAL 22	

MANHOLES TO BE ADJUSTED

LOCATION	EACH
IL 29 MAINLINE	
STA 539+77.00 LT	1
STA 571+18.00 LT	1
STA 573+14.00 LT	1
STA 573+95.00 LT	1
STA 574+07.00 CL	1
STA 577+53.00 CL	1
STA 115+00.00	1
STA 53+08.00 LT	1
STA 53+16.00 LT	1
STA 53+45.00 RT	1
STA 69+32.00 RT	1
STA 11+91.00 MEDIAN	1
STA 127+87.00 RT	1
TOTAL 13	

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF QUANTITIES
 FAP 75 (IL 29)
 SECTION D 6 RESURFACING 2007
 CHRISTIAN COUNTY
 SCALE: VERT. / HORIZ.
 DATE: / / DRAWN BY: / CHECKED BY: /