

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
75	*	CHRISTIAN	97	38
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

*D 6 RESURFACING 2007

THERMOPLASTIC PAVEMENT MARKING - LINE 12" (WHITE)

LOCATION	DESCRIPTION	COLOR	LENGTH (FOOT)
IL-29 MAINLINE			
CHENEY - SW ISLAND	CHEVRONS	WHITE	22.67
CHENEY - SE ISLAND	CHEVRONS	WHITE	49.25
CHENEY - NW ISLAND	CHEVRONS	WHITE	19.48
CHEYNEY			
STA 520+72.00 TO STA 524+90.00	DIAGONALS	YELLOW	217.90
STA 525+90.00 TO STA 527+90.00	DIAGONALS	YELLOW	39.29
BIDWELL - NE ISLAND	CHEVRONS	WHITE	21.70
PARK/WEBSTER - NW ISLAND	CHEVRONS	WHITE	48.44
PARK/WEBSTER - SW ISLAND	CHEVRONS	WHITE	45.34
PARK/WEBSTER - SE ISLAND	CHEVRONS	WHITE	36.52
PARK/WEBSTER - NE ISLAND	CHEVRONS	WHITE	16.86
WALNUT			
STA 54+25.00 TO STA 56+47.00	DIAGONALS	YELLOW	54.90
CHEROKEE			
STA 59+46.00 TO STA 61+64.00	DIAGONALS	YELLOW	72.40
STA 63+75.00 TO STA 65+90.00	DIAGONALS	YELLOW	50.60
MAIN CROSS - SE ISLAND	CHEVRONS	WHITE	23.67
MAIN CROSS - NW ISLAND	CHEVRONS	WHITE	32.25
KENNEDY			
STA 102+00.00 TO STA 107+30.00	DIAGONALS	YELLOW	161.42
STA 110+20.00 TO STA 113+67.00	DIAGONALS	YELLOW	123.15
LAKE ROAD			
STA 120+20.00 TO STA 126+15.00	DIAGONALS	YELLOW	219.03
STA 130+10.00 TO STA 134+90.00	DIAGONALS	YELLOW	141.90
TOTAL			1,396.77

PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 5"

LOCATION	COLOR	DESCRIPTION	NUMBER OF LINES	LENGTH (FOOT)
IL-29 MAINLINE				
STA 556+93.00 TO STA 561+50.00	WHITE	SKIP-DASHES	1	120.0
STA 561+50.00 TO STA 575+57.00	WHITE	SKIP-DASHES	2	720.0
STA 575+57.00 TO STA 576+40.00	WHITE	SKIP-DASHES	1	30.0
STA 579+10.00 TO STA 581+75.00	WHITE	SKIP-DASHES	1	70.0
TOTAL				940.0

THERMOPLASTIC PAVEMENT MARKING - LINE 6"

LOCATION	COLOR	DESCRIPTION	LENGTH (FOOT)
STA 107+30.00 TO STA 109+77.00	WHITE	LANE LINE	247.00
STA 126+32.00 TO STA 127+47.00	WHITE	LANE LINE	115.00
STA 128+54.23 TO STA 129+69.00	WHITE	LANE LINE	114.77
TOTAL			476.77

MEDIAN SCHEDULE

LOCATION	CONCRETE MEDIAN SURFACE REMOVAL SQ FT	CONCRETE MEDIAN SURFACE, 4 INCH SQ FT
IL-29 MAINLINE		
STA 8+00.00 TO STA 13+98.00	325	325
STA 14+82.00 TO STA 18+17.00	150	150
STA 19+95.00 TO STA 24+89.00	150	150
TOTAL		625

REMOVE AND RE-ERECT RAIL ELEMENT OF EXISTING GUARD RAIL

LOCATION	LENGTH (FOOT)	
I-29 MAINLINE		
RT STA 25+72.00 TO STA 27+55.00	187.50	
LT STA 26+02.00 TO STA 27+37.00	137.50	
LT STA 28+73.00 TO STA 30+58.00	187.50	
RT STA 28+91.00 TO STA 30+58.00	162.50	
RT STA 32+55.00 TO STA 34+05.00	150.00	
RT STA 56+89.00 TO STA 58+78.00	187.50	
LT STA 57+04.00 TO STA 58+78.00	175.00	
LT STA 60+79.00 TO STA 78+96.00	1,812.50	
RT STA 60+79.00 TO STA 77+93.00	1,712.50	
RT STA 115+74.00 TO STA 122+75.00	700.00	
LT STA 116+44.00 TO STA 121+52.00	512.50	
LT STA 128+91.00 TO STA 130+65.00	175.00	
TOTAL		6,100.00

THERMOPLASTIC PAVEMENT MARKING - LINE 8" WHITE

LOCATION	DESCRIPTION	LENGTH
CHENEY - SW ISLAND	MEDIAN	131.00
CHENEY - SE ISLAND	MEDIAN	175.80
CHENEY - NW ISLAND	MEDIAN	99.30
BIDWELL - NE ISLAND	MEDIAN	32.30
PARK/WEBSTER - NW ISLAND	MEDIAN	159.27
PARK/WEBSTER - SW ISLAND	MEDIAN	168.00
PARK/WEBSTER - SE ISLAND	MEDIAN	181.47
PARK/WEBSTER - NE ISLAND	MEDIAN	210.89
McADAM - NW ISLAND	MEDIAN	42.98
MAIN CROSS - SE ISLAND	MEDIAN	133.89
MAIN CROSS - NW ISLAND	MEDIAN	171.68
TOTAL		1,506.58

CONCRETE CURB REPAIR

LOCATION	LENGTH (FOOT)	
IL-29 MAINLINE		
STA 8+00.00 TO STA 13+98.00	475	
STA 14+82.00 TO STA 18+17.00	175	
STA 19+95.00 TO STA 24+89.00	125	
TOTAL		775

PLOT DATE = 12/15/2006
 FILE NAME = c:\p\projects\654683\schedules.dgn
 PLOT SCALE = 1/8"=1'-0"
 USER NAME = laughlin-1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

FAP 75 (IL 29)
SECTION D 6 RESURFACING 2007
CHRISTIAN COUNTY

SCALE: VERT. _____
HORIZ. _____

DATE _____ DRAWN BY _____
CHECKED BY _____