

| | | | | |
|---------------------|----------|------------------|--------------|-----------|
| F.A. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 662 | . | MACOUPIN | 66 | 4 |
| STA. | | TO STA. | | |
| FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT | | |

• (V,T) B-2

| SUMMARY OF QUANTITIES | | UNITS | TOTAL QUANTITY | CONSTR. CODE | CONSTR. CODE | CONSTR. CODE |
|-----------------------|--|-------------|-------------------------------|--------------------------------------|---------------------------------------|---|
| | | | <i>80% FED. 20% STATE</i> | | | |
| PAY CODE NUMBER | PAY ITEM DESCRIPTION | | | RURAL ROADWAY 1000 80% FED 20% STATE | IL 4 BRIDGE X081-2A 80% FED 20% STATE | IMPACT ATTEN. SFTY-3N 80% FED 20% STATE |
| 40600990 | TEMPORARY RAMP | SO YD | 27 | 27 | - | - |
| 40600625 | LEVELING BINDER (MACHINE METHOD), N50 | TON | 118 | 118 | - | - |
| 40603335 | HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50 | TON | 195 | 195 | - | - |
| 40800050 | INCIDENTAL HOT-MIX ASPHALT SURFACING | TON | 15 | | 15 | |
| 42001165 | BRIDGE APPROACH PAVEMENT | SO YD | 216.7 | 216.7 | - | - |
| 44000100 | PAVEMENT REMOVAL | SO YD | 260 | 260 | - | - |
| 48101200 | AGGREGATE SHOULDERS, TYPE B | TON | 74 | 74 | - | - |
| 48203100 | HOT-MIX ASPHALT SHOULDERS | TON | 97 | | 97 | |
| <i>50100100</i> | <i>REMOVAL OF EXISTING STRUCTURES</i> | <i>EACH</i> | <i>1</i> | <i>-</i> | <i>1</i> | |
| 50200100 | STRUCTURE EXCAVATION | CU YD | <i>260</i> | - | <i>260</i> | - |
| 50300225 | CONCRETE STRUCTURES | CU YD | 52.3 | - | 52.3 | - |
| 50300255 | CONCRETE SUPERSTRUCTURES | CU YD | 144.5 | - | 144.5 | - |
| 50300260 | BRIDGE DECK GROOVING | SO YD | 335 | - | 335 | - |
| 50300300 | PROTECTIVE COAT | SO YD | 431 | - | 431 | - |
| 50401105 | FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE I-BEAMS, 54 IN. | FOOT | 524.5 | | 524.5 | - |
| 50800205 | REINFORCEMENT BARS, EPOXY COATED | POUND | <i>32,120</i> | - | <i>32,120</i> | |
| 50800515 | BAR SPLICERS | EACH | <i>355</i> | | <i>355</i> | |
| 51201105 | FURNISHING METAL PILE SHELLS 14" | FOOT | <i>931</i> | | <i>931</i> | |

| REVISIONS | |
|-----------|------|
| NAME | DATE |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF QUANTITIES
 SCALE: VERT. DATE
 HORIZ. DATE
 DRAWN BY
 CHECKED BY

Rev.

PLOT DATE: 11/19/2006
 FILE NAME: c:\projects\652688\sketches\as.dgn
 PLOT SCALE: 1/8"=1'-0" / IN.
 USER NAME: f.dougherty