

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
717	101B-1	LOGAN	49	8
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

ENGINEER'S FIELD OFFICE, TYPE A	
LOCATION	CAL MO
JOBSITE	9
TOTAL 9	

RELOCATE TEMPORARY CONCRETE BARRIER			
LOCATION			FOOT
STA 251+75	TO	STA 257+75	600
TOTAL			600

MOBILIZATION	
LOCATION	L SUM
JOBSITE	1
TOTAL 1	

PAINT PAVEMENT MARKING - LINE 5"					
		EDGE LINES	SKIP-DASH	COMBINED	
		WHITE	YELLOW		
LOCATION		FOOT	FOOT	FOOT	
STA 250+86.19	TO	STA 258+49.59	1527	191	1,718
TOTAL				1,718	

TRAFFIC CONTROL AND PROTECTION	
STANDARD 701306	1 L SUM
STANDARD 701326	1 L SUM
STANDARD 701321 SPECIAL	1 EACH

RAISED REFLECTIVE PAVEMENT MARKER			
LOCATION			EACH
STA 250+86.16	TO	STA 258+49.59	11
TOTAL			11

IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	
LOCATION	EACH
STA 251+75	1
STA 256+88	1
TOTAL 2	

TRAFFIC CONTROL SURVEILLANCE	
LOCATION	CAL DA
JOBSITE	5
TOTAL 5	

GUARDRAIL MARKERS, TYPE A			
LOCATION			EACH
LT STA 252+78	TO	STA 257+36	6
LT STA 252+16	TO	STA 256+74	6
TOT			12

IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	
LOCATION	EACH
STA 251+75	1
STA 256+88	1
TOTAL 2	

TEMPORARY BRIDGE TRAFFIC SIGNALS	
LOCATION	EACH
JOBSITE (for staging, 2 signals)	1
TOTAL 1	

TERMINAL MARKER - DIRECT APPLIED			
LOCATION			EACH
LT STA 252+28.01			1
LT STA 257+86.31			1
RT STA 251+65.51			1
RT STA 256+86.31			1
TOTAL			4

BRIDGE DECK GROOVING			
LOCATION		WIDTH	SO YD
STA 253+16.16	TO	STA 253+46.16	30.83' 102.77
STA 256+05.66	TO	STA 256+35.66	30.83' 102.77
TOTAL			206

SHORT-TERM PAVEMENT MARKING			
LOCATION			FOOT
STA 250+86.19	TO	STA 253+16.16	3 APPLICATIONS 69
STA 256+35.66	TO	STA 258+49.59	3 APPLICATIONS 64
TOTAL			133

PAVEMENT MARKING REMOVAL			
LOCATION			SO FT
LT STA 250+86.19	TO	STA 258+49.59	318
RT STA 250+86.19	TO	STA 253+16.16	96
RT STA 256+35.66	TO	STA 258+49.59	89
TOTAL			503

WORK ZONE PAVEMENT MARKING REMOVAL			
LOCATION			SO FT
STA 250+86.19	TO	STA 253+16.16	7.6
STA 256+35.66	TO	STA 258+49.59	7.1
TOTAL			15

RAISED REFLECTIVE PAVEMENT MARKER REMOVAL			
LOCATION			EACH
STA 250+86.16	TO	STA 258+49.59	11
TOTAL			11

TEMPORARY CONCRETE BARRIER			
LOCATION			FOOT
STA 251+75	TO	STA 257+75	600
TOTAL			600

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF QUANTITIES
 FAP 717 (IL 10)
 SECTION 101B-1
 LOGAN COUNTY

SCALE: VERT. _____
 HORIZ. _____
 DATE _____ DRAWN BY _____
 CHECKED BY _____