

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SHEET 3 OF 8  
CONTRACT 72A48

GUARDRAIL SCHEDULE

STA TO	STA	SIDE	TRAF. BARR. TERM. TY 1 SPC. (TANGENT) EACH	TRAF. BARR. TERM. TY 6A EACH	STEEL PLATE BEAM GUARDRAIL FEET	REMOVE AND REPLACE STEEL BRIDGERAIL FEET	GUARDRAIL REMOVAL FEET	TERMINAL MARKERS DIRECT APPLIED EACH	GUARDRAIL MARKERS TY A EACH
SN 034-0025									
771+07.31	771+57.31	RT	1				42.5	1	
771+57.31	772+94.81	RT			137.5		137.5		2
772+94.81	773+26.81	RT		1			32		
773+26.81	773+57.19	RT				30.38			1
773+57.19	773+89.19	RT		1			32		
773+89.19	774+26.69	RT			37.5		37.5		1
774+26.69	774+76.69	RT	1				47.5	1	
771+73.31	772+23.31	LT	1				50.5	1	
772+23.31	772+60.81	LT			37.5		37.5		1
772+60.81	772+92.81	LT		1			32		
772+92.81	773+23.19	LT				30.38			1
773+23.19	773+55.19	LT		1			32		
773+55.19	773+92.69	LT			37.5		37.5		1
773+92.69	774+42.69	LT	1				41.5	1	
SN 034-0026									
801+92.84	802+42.84	RT	1				43	1	
802+42.84	830+67.84	RT			2825		2825		35
830+67.84	830+99.84	RT		1			32		
830+99.84	833+00.64	RT				200.8			3
833+00.64	833+32.64	RT		1			32		
833+32.64	837+07.64	RT			375		375		5
837+07.64	837+57.64	RT	1				49	1	
829+30.34	829+80.34	LT	1				46.5	1	
829+80.34	830+67.84	LT			87.5		87.5		1
830+67.84	830+99.84	LT		1			32		
830+99.84	833+00.64	LT				200.8			3
833+00.64	833+32.64	LT		1			32		
833+32.64	834+70.14	LT			137.5		137.5		2
834+70.14	835+20.14	LT	1				40.5	1	
TOTALS			8	8	3675	463	4292	8	56

DATE	
BY	
NO. OF PLAT	
NOTEBOOK NO.	

SN 034-0025, 26  
GUARDRAIL SCHEDULE