

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	*	SANGAMON	26	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

* - D-6 CABLE MEDIAN BAR #2

LOCATION OF WORK				URBAN I-55 90% FED./10% STATE	
SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE	
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	SFTY-2A	
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	292	292	
25001000	SEEDING, CLASS 2 (SPECIAL)	ACRE	4	4	
25100630	EROSION CONTROL BLANKET	SQ YD	19,476	19,476	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	800	800	
48203013	HOT-MIX ASPHALT SHOULDERS, 4"	SQ YD	18,656	18,656	
48203037	HOT-MIX ASPHALT SHOULDERS, 10"	SQ YD	648	648	
63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	475	475	
63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	2	2	
63200310	GUARDRAIL REMOVAL	FOOT	900	900	
67100100	MOBILIZATION	L SUM	1	1	
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	5	5	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	4	4	
78200410	GUARDRAIL MARKERS, TYPE A	EACH	8	8	
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	2	
X0325231	CABLE GUARD MARKER	EACH	699	699	
X0325589	HIGH TENSION CABLE MEDIAN BARRIER	FOOT	27,764	27,764	
X0325590	HIGH TENSION CABLE MEDIAN BARRIER TERMINAL	EACH	8	8	
Z0029999	IMPACT ATTENUATOR REMOVAL	EACH	3	3	
X0325606	HIGH TENSION CABLE MEDIAN BARRIER DEMONSTRATION	EACH	2	2	



PLOT DATE : 12/12/2006
FILE NAME : s:\projects\653006\shl\summary.dgn
PLOT SCALE : 1/8"=1'-0"
USER NAME : laughlin

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
FAI 55 (I-55)
SECTION D-6 CABLE MEDIAN BAR #2
SANGAMON COUNTY
SCALE: VERT. DATE: DRAWN BY: CHECKED BY:

Rev.