CONTRACT NO. 72A56

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	*	SANGAMON	26	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* - D-6 CABLE MEDIAN BAR #2

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

LOCATION OF WORK				URBAN I-55 90% FED./10% STATE
SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	SFTY-2A
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	292	292
25001000	SEEDING, CLASS 2 (SPECIAL)	ACRE	4	4
25100630	EROSION CONTROL BLANKET	SQ YD	19,476	19,476
48203013	HOT-MIX ASPHALT SHOULDERS, 4"	SQ YD	18,656	18,656
48203037	HOT-MIX ASPHALT SHOULDERS, 10"	SQ YD	648	648
63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	475	475
63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	2	2
63200310	GUARDRAIL REMOVAL	FOOT	900	900
67100100	MOBILIZATION	L SUM	1	1
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	5	5
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	4	4
78200410	GUARDRAIL MARKERS, TYPE A	EACH	8	8
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	2
X0325231	CABLE GUARD MARKER	EACH	699	699
X0325589	HIGH TENSION CABLE MEDIAN BARRIER	FOOT	27,764	27,764
X0325590	HIGH TENSION CABLE MEDIAN BARRIER TERMINAL	EACH	8	8
Z0029999	IMPACT ATTENUATOR REMOVAL	EACH	3	3
X0325606	HIGH TENSION CABLE MEDIAN BARRIER DEMONSTRATION	EACH	2	2

Rev.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

FAI 55 (I-55)
SECTION D-6 CABLE MEDIAN BAR #2
SANGAMON COUNTY

SCALE: VERT. HORIZ.
DATE
DRAWN BY
CHECKED BY

PLOT DATE : 12/13/2006
FILE NAME : c:\Projects\d653006\shtsoq.dgn
PLOT SCALE : 105.8824 ' / IN.
USER NAME : laughlinrl