

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	*	SANGAMON	26	9
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* D-6 CABLE MEDIAN BAR #2

GUARDRAIL REMOVAL

LOCATION	LENGTH (FOOT)
RT STA 455+11 TO STA 456+30	125
LT STA 468+20 TO STA 469+45	125
RT STA 622+41 TO STA 624+41	200
RT STA 635+58 TO STA 637+08	150
RT STA 349+71 TO STA 346+71	300
TOTAL	900

* - TBT TY 6 TO BE LEFT IN PLACE

IMPACT ATTENUATOR REMOVAL

LOCATION	EACH
STA 374+00 (SN 084-0088 N SIDE)	1
STA 374+50 (SN 084-0088 S SIDE)	1
STA 556+50 (SN 084-0101 N SIDE)	1
TOTAL	3

STEEL PLATE BEAM GUARDRAIL, TYPE A

LOCATION	LENGTH (FOOT)
RT STA 453+93 TO STA 456+30	237.5
LT STA 468+20 TO STA 470+58	237.5
TOTAL	475.0

TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)

LOCATION	QUANTITY (EACH)
RT STA 453+43 TO STA 453+93	1
LT STA 470+58 TO STA 471+08	1
TOTAL	2

TERMINAL MARKER - DIRECT APPLIED

LOCATION	QUANTITY (EACH)
RT STA 453+43	1
LT STA 471+08	1
TOTAL	2

HIGH TENSION CABLE MEDIAN BARRIER

LOCATION	LENGTH (FOOT)
LT STA 374+52.50 TO STA 446+29.54 BK	7,177
LT STA 446+39.17 AH TO STA 455+97.50	958
LT STA 468+61.50 TO STA 521+45.50	5,284
RT STA 522+88.50 TO STA 582+36.50	5,948
RT STA 618+76.50 TO STA 695+32.26 BK	7,656
RT STA 355+49.48 AH TO STA 348+08.50	741
TOTAL	27,764

HIGH TENSION CABLE MEDIAN BARRIER TERMINAL

LOCATION	EACH
LT STA 374+25.00 TO STA 374+52.50	1
LT STA 455+97.50 TO STA 456+25.00	1
LT STA 468+34.00 TO STA 468+61.50	1
LT STA 521+45.50 TO STA 521+73.00	1
RT STA 522+61.00 TO STA 522+88.50	1
RT STA 582+36.50 TO STA 582+64.00	1
RT STA 618+49.00 TO STA 618+76.50	1
RT STA 348+08.50 TO STA 347+81.00	1
TOTAL	8

HOT-MIX ASPHALT SHOULDERS, 4"

LOCATION	LENGTH (FOOT)	WIDTH (FOOT)	AREA (SQ YD)
LT STA 374+25.00 TO STA 446+29.54 BK	7,205	6.0	4,803.03
LT STA 446+39.17 AH TO STA 456+25.00	986	6.0	657.22
LT STA 468+34.00 TO STA 521+73.00	5,339	6.0	3,559.33
RT STA 522+61.00 TO STA 582+64.00	6,003	6.0	4,002.00
RT STA 618+49.00 TO STA 695+32.26 BK	7,683	6.0	5,122.17
RT STA 355+49.48 AH TO STA 347+81.00	768	6.0	512.32
TOTAL			18,656.07

HOT-MIX ASPHALT SHOULDERS, 10"

LOCATION	LENGTH (FOOT)	WIDTH (FOOT)	AREA (SQ YD)
LT STA 515+58.00 TO STA 518+68.00	310	1.0 TO 6.0	120.56
LT STA 518+68.00 TO STA 521+73.00	305	6.0	203.33
RT STA 522+61.00 TO STA 525+66.00	305	6.0	203.33
RT STA 525+66.00 TO STA 528+76.00	310	1.0 TO 6.0	120.56
TOTAL			647.78

PLOT DATE = 12/13/2006
 FILE NAME = c:\p\projects\4653806\shs\shs.dwg
 PLOT SCALE = 1/8"=1'-0"
 USER NAME = laughlin-1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULES OF QUANTITIES
 FAI 55 (1-55)
 SECTION D-6 CABLE MEDIAN BAR #2
 SANGAMON COUNTY

SCALE: VERT. DRAWN BY
 HORIZ. CHECKED BY
 DATE