CONTRACT NO. 72A80

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
304	*	PIKE	16	4
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* 101(RS-5); 14(RS-6)

RESURFACING SCHEDULE

LOCATION (STA TO STA)	LENGTH FEET	PAVT. WIDTH FEET	BIT. SHLD. WIDTH FEET	BIT. SURF. REMOVAL BUTT JOINT SQ YD	BIT. SURF. REMOVAL V.D. SQ YD	TEMP. RAMPS SQ YD	BIT. MATLS. (P.C.) TON	AGG. (P.C.) TON	BIT. CONC. SURF. CSE. 1 1/2" TON	BIT. SHLDS. 1 1/2" TON	AGG. SHLDS. T-B TON
PART "A"											
484+85.00 TO 485+00.00	15.00	27.0	-	45.00	-	15.00	0.02	0.09	3.8	-	1.1
485+00.00 TO 541+50.00	5650.00	27.0	-	-	16950.00	-	6.44	33.90	1423.8	-	421.9
541+50.00 TO 541+85.00	35.00	24.0	2.8	-	114.72	-	0.04	0.23	7.8	1.8	2.6
541+85.00 TO 549+00.00	715.00	24.0	4.0	-	2542.22	-	0.97	5.08	160.2	53.4	53.4
549+00.00 TO 549+50.00	50.00	24.0	7.0	-	211.11	-	0.08	0.42	11.2	6.5	3.7
549+50.00 TO 554+37.87	487.87	24.0	10.0	-	2385.14	-	0.91	4.77	109.3	91.1	
554+22.87 TO 554+37.87	15.00	24.0	10.0	73.33	-	24.44	0.03	0.15	3.4	2.8	
						-					
557+21.06 TO 557+36.06	15.00	24.0	10.0	73.33	-	24.44	0.03	0.15	3.4	2.8	
557+36.06 TO 558+00.00	63.94	24.0	10.0	-	312.60	-	0.12	0.63	14.3	11.9	
558+00.00 TO 558+50.00	50.00	24.0	7.0	-	211.11	-	0.08	0.42	11.2	6.5	3.7
558+50.00 TO 566+90.20	840.20	24.0	4.0	-	2987.38	-	1.14	5.97	188.2	62.7	62.7
PART "B"											
1173+00.00 TO 1173+15.00	15.00	24.0	-	40.00	-	13.33	0.02	0.08	3.4	-	1.1
1173+15.00 TO 1178+50.00	535.00	24.0	-	-	1426.67	-	0.54	2.85	119.8	-	39.9
1178+50.00 TO 1184+75.00	625.00	23.5	-	-	1631.94	-	0.62	3.26	137.1	-	23.3
1184+75.00 TO 1195+00.00	1025.00	24.0	-	-	2733.33	-	1.04	5.47	229.6	-	76.5
1195+00.00 TO 1196+48.00	148.00	23.5	-	-	386.44	-	0.15	0.77	32.5	-	5.5
1196+48.00 TO 1201+10.00	462.00	23.0	-	-	1180.67	-	0.45	2.36	99.2	-	-
1201+10.00 TO 1202+35.00	125.00	23.5	-	-	326.39	-	0.12	0.65	27.4	-	4.7
1202+35.00 TO 1233+50.00	3115.00	24.0	-	-	8306.67	-	3.16	16.61	697.8	-	232.6
1233+50.00 TO 1233+94.83	44.83	24.0	2.5	-	132.00	-	0.05	0.26	10.0	1.0	3.3
1233+94.83 TO 1236+00.00	205.17	24.0	4	-	638.31	-	0.24	1.28	46.0	7.7	15.3
1236+00.00 TO 1236+28.16	28.16	24.0	2.5	-	95.43	-	0.04	0.19	6.3	1.7	2.1
TOTALS =				231.67	42572.13	77.22	16.27	85.61	3345.5	250.0	953.7

PAVEMENT MARKING SCHEDULE

LOCATION (STA TO STA)	LENGTH FEET	5" SKIP DASH YELLOW FEET	5" SOLID YELLOW FEET	5" SOLID WHITE FEET	5" TEMP. PVT. MK. FEET	RAISED REFL. PVT. MKS. EACH
WHITE EDGE LINES						
PART "A"						
LT 484+85.00 TO LT 566+90.20 (BK)	8173.90			8173.90	8173.90	
RT 484+85.00 TO RT 566+90.20 (BK)	8173.90			8173.90	8173.90	
PART "B"						
LT 1173+00.00 TO LT 1194+58.90 (BK)	2158.90			2158.90	2158.90	
LT 1194+62.10 (AH) TO LT 1236+28.16 (BK)	4166.06			4166.06	4166.06	
RT 1173+00.00 TO RT 1194+58.90 (BK)	2158.90			2158.90	2158.90	
RT 1194+62.10 (AH) TO RT 1236+28.16 (BK)	4166.06			4166.06	4166.06	
YELLOW SKIP DASH AT CENTERLINE						
PART "A"						
484+85.00 TO 505+90.00	2105.00	526.25			526.25	
508+47.00 TO 566+90.20 (BK)	5843.20	1460.80			1460.8	
PART "B"						
1173+00.00 TO 1188+83	1583.00	395.75			395.75	
1229+85 TO 1236+28.16 (BK)	643.16	160.79			160.79	
YELLOW SOLID NO PASSING ZONES *						
PART "A"						
LT 505+80 TO LT 520+40	1460.00		1460.00		1460.00	
RT 489+00 TO RT 508+50	1950.00		1950.00		1950.00	
RT 562+60 TO RT 566+90.20 (BK)	430.20		430.20		430.20	
PART "B"						
LT 1173+00 TO LT 1173+83	83.00		83.00		83.00	
LT 1188+83 TO LT 1194+58.90 (BK)	575.90		575.90		575.90	
LT 1194+62.10 (AH) TO LT 1236+28.16 (BK)	4166.06		4166.06		4166.06	
RT 1181+33 TO RT 1229+85	4852.00		4852.00		4852.00	
PAVEMENT MARKERS						
PART "A"						
484+85.00 TO 566+90.20 (BK)	8173.90					102
PART "B"						
1173+00.00 TO 1194+58.90 (BK)	2158.90					27
1194+62.10 (AH) TO 1236+28.16 (BK)	4166.06					52
SUB-TOTALS =		2,543.59	13,517.16	28,997.72	45,058.47	181
TOTALS =				45,058.47	45,058.47	181

SHORT TERM PAVEMENT MARKING SCHEDULE

LOCATION (STA TO STA)	LENGTH FEET	SKIP DASH YELLOW (3 APPL.) FEET	EDGE DIAG. WHITE (3 APPL.) FEET	WORK ZONE REMOVAL (FINAL LIFT) SQ FT
YELLOW SKIP DASH AT CENTERLINE				
PART "A"				
484+85.00 TO 566+90.20 (BK)	8173.90	2452.2		340.6
PART "B"				
1173+00.00 TO 1194+58.90 (BK)	2158.90	647.7		90.0
1194+62.10 (AH) TO 1236+28.16 (BK)	4166.06	1249.8		173.6
WHITE DIAGONAL EDGE LINES ON SHLDS.				
PART "A"				
LT 541+50.00 TO LT 566+90.20 (BK)	2540.2		152.4	21.2
RT 541+50.00 TO RT 566+90.20 (BK)	2540.2		152.4	21.2
PART "B"				
LT 1233+50.00 TO LT 1236+28.16 (BK)	278.16		16.7	2.3
RT 1236+00.00 TO RT 1236+28.16 (BK)	28.16		1.7	0.2
SUB-TOTALS =		4,349.66	323.20	649.0
TOTALS =			4,672.86	649.0

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES OF QUANTITIES

FAP RTE. 304 (IL 106/96)
SEC. 101(RS-5); 14(RS-6)
PIKE COUNTY

SCALE: VERT. HORIZ. DRAWN BY TMJ
DATE 11-17-2006 CHECKED BY JCN

PLOT DATE = 12/11/2006
FILE NAME = c:\Projects\d550787\sht sch.dgn
PLOT SCALE = 21.333 ' / IN.
USER NAME = bughlin

SCHEDULES OF QUANTITIES, FAP 304 (IL 106/96)