

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
9079	65BR	MADISON	46	2
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

INDEX OF SHEETS

- 1 COVER SHEET
- 2 INDEX OF SHEETS, HIGHWAY STANDARDS, GENERAL NOTES, & COMMITMENTS
- 3-4 SUMMARY OF QUANTITIES
- 5-6 TYPICAL SECTIONS
- 7-8 SCHEDULES
- 9 TIE POINTS AND BENCHMARKS
- 10 PLAN SHEET
- 11-13 PLAN PROFILE SHEETS
- 14-15 STAGE CONSTRUCTION SHEETS
- 16 PLAT OF HIGHWAYS
- 17 MISCELLANEOUS DETAILS
- 18-29 STRUCTURE PLANS
CROSS SECTIONS
- 30-32 MAINLINE
- 33-35 NORTHWEST ACCESS ROAD
- 36-39 NORTHEAST ACCESS ROAD
- 40-43 SOUTHWEST ACCESS ROAD
- 44-46 SOUTHEAST ACCESS ROAD

HIGHWAY STANDARDS

000001-04	635006-02
001001-01	635011-01
001006	666001
280001-03	701011-01
420401-05	701311-02
515001-02	701321-08
609006-03	701326-02
630001-07	702001-06
630101-07	704001-03
630301-04	780001-01
631031-06	781001-02
631032-03	

GENERAL NOTES

1. THE STANDARDS AND REVISIONS NUMBER SHALL APPLY TO THIS PROJECT.
2. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING MATERIALS.
3. ILLINOIS STATE LAW REQUIRES A 48-HOUR NOTICE BE GIVEN TO ALL UTILITIES WITHIN THE PROJECT AREA BEFORE DIGGING BY CALLING J.U.L.I.E. AND BY NOTIFYING NON-J.U.L.I.E. MEMBERS INDIVIDUALLY. AGENCIES KNOWN TO HAVE FACILITIES WITHIN THE PROJECT AREA ARE AS FOLLOWS:
 - AT&T ILLINOIS (COMMUNICATIONS)
 - CHARTER COMMUNICATIONS, INC. (CABLE TV)
 - VILLAGE OF GLEN CARBON (WATER & SANITARY SEWER)
 - AMERENIP (GAS & ELECTRIC)
 (MEMBERS OF J.U.L.I.E. (800) 892-0123 ARE INDICATED BY *)
 NON-J.U.L.I.E. MEMBERS MUST BE NOTIFIED INDIVIDUALLY.)
4. A QUANTITY OF 250 FEET OF "TEMPORARY PAVEMENT MARKING - LINE 6" WHITE HAS BEEN INCLUDED IN THE PLANS FOR PAINTING THE BOTTOM 6" OF THE TEMPORARY CONCRETE BARRIER.
5. RIGHT OF WAY MARKERS SHALL BE SET SO THE BACK OF THE POST IS TWELVE (12") INCHES INSIDE THE RIGHT OF WAY BOUNDARY. RIGHT OF WAY PROPERTY CORNERS ARE MARKED BY A 5/8" IRON ROD WITH IDOT ALUMINUM CAP AND SHALL NOT BE REMOVED OR DISTURBED WHEN SETTING THE RIGHT OF WAY MARKER.
6. NO TRENCHES OR OPEN PITS WILL BE PERMITTED ADJACENT TO A TRAFFIC LANE DURING NON-WORKING HOURS. ALL WIDENING TRENCHES SHALL BE BACKFILLED DURING THE SAME WORKING DAY IT WAS EXCAVATED.
7. NEW JERSEY (NJ) SHAPE BARRIER WILL BE ALLOWED ON THIS PROJECT. INSTALLATION SHALL BE AS SHOWN ON THE PLANS.
8. THE TRAFFIC CONTROL MEASURES SHALL SUPPLEMENT AND BE IN ACCORDANCE WITH TRAFFIC CONTROL STANDARD 701321.
9. THE BARRIER UNIT AT EACH END OF THE TRAFFIC CONTROL INSTALLATION SHALL BE SECURED TO THE PAVEMENT OR SHOULDER USING ALL SIX ANCHORING PINS FOR F-SHAPE BARRIER OR ALL SIX DOWEL BARS FOR NEW JERSEY SHAPE BARRIER.
10. THE TEMPORARY CONCRETE BARRIER (STATE OWNED) IS LOCATED AT IL ROUTE 111, NORTH OF I-55/70. THE CONTRACTOR SHALL PICK UP THE BARRIER AND RETURN THE BARRIER TO THE SAME LOCATION UPON COMPLETION OF THE PROJECT. ANY DAMAGED BARRIER WILL NOT HAVE TO BE REPLACED. THE CONTRACTOR SHALL DISPOSE OF DAMAGED CONCRETE BARRIER IN AN APPROVED DUMP SITE. THE CONNECTOR PINS SHALL BE FURNISHED BY THE CONTACTOR AND THE COST SHALL BE INCLUDED WITH THE COST OF "TEMPORARY CONCRETE BARRIER (STATE OWNED)".
11. ANY REFERENCE TO "BITUMINOUS CONCRETE" SHALL BE CONSTRUED TO DENOTE "HOT MIX ASPHALT".
12. EXISTING FLAP GATES SHALL BE SALVAGED BY THE CONTRACTOR AND DELIVERED TO THE WOOD RIVER OPERATIONS YARD AT 200 SOUTH BELLWOOD. PLEASE CONTACT STEVE WHEELER AT (618) 259-1440 PRIOR TO DELIVERY.

EROSION AND SEDIMENT CONTROL GENERAL NOTES

ALL EROSION CONTROL PRODUCTS FURNISHED SHALL BE SPECIFICALLY RECOMMENDED BY THE MANUFACTURER FOR THE USE SPECIFIED IN THE EROSION CONTROL PLAN. PRIOR TO APPROVAL AND USE OF THE PRODUCT, THE CONTRACTOR SHALL SUBMIT TO THE ENGINEER A NOTARIZED CERTIFICATION BY THE PRODUCER STATING THE INTENDED USE OF THE PRODUCT AND THAT THE PHYSICAL PROPERTIES REQUIRED FOR THIS APPLICATION ARE MET OR EXCEEDED. THE CONTRACTOR SHALL PROVIDE MANUFACTURER RECOMMENDED INSTALLATION PRECEDURES TO FACILITATE THE ENGINEER IN CONSTRUCTION INSPECTION.

TEMPORARY SEEDING SHALL BE COMPLETED ON A WEEKLY BASIS ON EXPOSED GROUND AND SHALL BE IN ACCORDANCE WITH SECTION 280 OF THE STANDARD SPECIFICATIONS. TEMPORARY EROSION CONTROL SEEDING SHALL BE APPLIED AT A RATE OF 100 LBS/ACRE AND PAID FOR AS "TEMPORARY EROSION CONTROL SEEDING". FOR CALCULATION PURPOSES, TWO APPLICATIONS OF TEMPORARY SEEDING WAS ASSUMED

EARTH STOCKPILES SHALL BE TEMPORARY SEEDED IF THEY ARE TO REMAIN UNUSED FOR MORE THAN FOURTEEN DAYS.

FINAL SEEDING SHALL BE PERFORMED AS SOON AS POSSIBLE WITH CLASS 2 SEEDING.

COMMITMENTS

PLOT DATE = 10/19/2005
 FILE NAME = \\ed16699\plan\pln16699.dgn
 PLOT SCALE = 5/8"=1'-0"
 REFERENCE = SHEET#

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
INDEX OF SHEETS, HIGHWAY STANDARDS, GENERAL NOTES & COMMITMENTS
 FAU ROUTE 9079
 SECTION 65BR
 MADISON COUNTY
 SN 060-0069 (E) 0236 (P)