

F.A.I. RT#	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
10	60-10.11B5	MADISON	151	3
STA.		TO STA.		
FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT				

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	1000-2A 90% FED, 10% STATE ROADWAY	SFTY-2A 90% FED 10% STATE SN 060-0022	SFTY-2A 90% FED 10% STATE SN 060-0059	SFTY-2A 90% FED 10% STATE SN 060-0173	SFTY-2A 90% FED 10% STATE SN 060-0023	SFTY-2A 90% FED 10% STATE SN 060-0024	SFTY-2A 90% FED 10% STATE SN 060-0182	SFTY-2A 90% FED 10% STATE SN 060-0057	SFTY-2A 90% FED 10% STATE SN 060-0058	Y002-1C 100% STATE SIGNING	Y002-1C 90% FED 10% STATE SIGNING
CODE NO	ITEM	UNIT												
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	26		11	7			4	4				
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	156	124					16	16				
* 78200520	BARRIER WALL MARKERS, TYPE B	EACH	10						4	6				
* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	10						4	6				
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	37	37										
78300100	PAVEMENT MARKING REMOVAL	SQ FT	742		307	200			113	122				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1227	1227										
80300100	LOCATING UNDERGROUND CABLE	FOOT	3000	3000										
X0320532	CONCRETE BRIDGE DECK SCARIFICATION (3/8 INCH)	SQ YD	1246				654					592		
X0321468	PLUG EXISTING DECK DRAINS	EACH	94				20	28	32	14				
X0322729	MATERIAL TRANSFER DEVICE	TON	24,399	24,399										
X0322932	SILICONE JOINT SEALER, 1.5"	FOOT	62				62							
X0322944	BRIDGE DECK THIN POLYMER OVERLAY 3/8"	SQ YD	1246				654					592		
X0324952	DETOUR SIGNING	L SUM	1	1										
X4066580	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, N80	TON	12,065	12,065										
X6330103	REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL, TANGENT	EACH	4	4										
X7800400	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 4", SPECIAL	FOOT	7935	7935										
XZ193500	BRIDGE DECK MICROSILICA CONCRETE OVERLAY 2 1/4"	SQ YD	1298					614	684					
Z0006204	BRIDGE DECK HYDRO-SCARIFICATION 1/2"	SQ YD	1298					614	684					
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	32				3	8	9	12				
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	135				13			122				
Z0017100	DOWEL BARS	EACH	1070	1070										
Z0029999	IMPACT ATTENUATOR REMOVAL	EACH	2	2										
■ Z0030260	IMPACT ATTENUATORS (TEMPORARY FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	4	4										
■ Z0030150	IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2										
■ Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2					1	1					
■ Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2					1	1					
Z0075300	TIE BARS	EACH	113	113										
* Z0077800	WOOD POST	EACH	4	4										
⊙ Z0076600	TRAINEES	HOUR	3000	3000										

PLOT DATE = 12/14/2009
 PLOT SCALE = 1/8" = 1'-0"
 REFERENCE = #REF#