

80% FED. / 20% STATE
 X088-2A ACBRF X088-2A ACBRF
 ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

F.A.P. RTE.		SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
592		28BR-2.3	ST. CLAIR	51	3
STA.		TO STA.			
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT			

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	S.N. 082-0087		S.N. 082-0212		
				BRIDGE CANAL NO. 1	RDWY CANAL NO. 1	BRIDGE HARDING DITCH	RDWY HARDING DITCH	RDWY HARDING DITCH
20200100	EARTH EXCAVATION	CU YD	46	46				
20400800	FURNISHED EXCAVATION	CU YD	12838	12838				
20700220	POROUS GRANULAR EMBANKMENT	CU YD	70			70		
25000200	SEEDING, CLASS 2	ACRE	1.25	1.25				
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	113		113			
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	113		113			
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	113		113			
25100105	MULCH, METHOD 1	ACRE	1.25	1.25				
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	625	625				
31101810	SUB-BASE GRANULAR MATERIAL, TYPE B 12"	SQ YD	732		732			
35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	80		80			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.4		0.3		0.1	
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	446	446				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	99		77		22	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	13		13			
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	160			160		
42001300	PROTECTIVE COAT	SQ YD	420			420		
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	694		267		427	
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	18	12		6		
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	229	163	66			
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1				
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1			1		
50102400	CONCRETE REMOVAL	CU YD	12.5			12.5		
50200100	STRUCTURE EXCAVATION	CU YD	72			72		
50200300	COFFERDAM EXCAVATION	CU YD	1133	1133				
50200500	COFFERDAMS	EACH	1	1				
50300225	CONCRETE STRUCTURES	CU YD	16.3			16.3		
50300260	BRIDGE DECK GROOVING	SQ YD	398			398		
50300265	SEAL COAT CONCRETE	CU YD	852.3	852.3				
50301200	CONCRETE WEARING SURFACE	SQ YD	399			399		
50400305	PRECAST PRESTRESSED CONCRETE DECK BEAMS (17" DEPTH)	SQ FT	3770			3770		
50800105	REINFORCEMENT BARS	POUND	50130	50130				
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	7600			7600		
50800515	BAR SPLICERS	EACH	68			68		
50901050	STEEL RAILING, TYPE SM	FOOT	229			229		
51500100	NAME PLATES	EACH	2	1		1		

PLOT DATE = 12/11/2006
 PLOT SCALE = 500000 / IN
 REFERENCE = #REF#