

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
592	288R-2,3	ST. CLAIR	51	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

80% FED. / 20% STATE

X028-2A ACBHF X080-2A ACBHF

SUMMARY OF QUANTITIES

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		S.N. 082-0087		S.N. 082-0212			
				BRIDGE CANAL NO. 1	RDWY CANAL NO. 1	BRIDGE HARDING DITCH	RDWY HARDING DITCH	RDWY HARDING DITCH	
54003000	CONCRETE BOX CULVERTS	CU YD	212.1	212.1			48.2		
58700300	CONCRETE SEALER	SQ FT	48.2				34		
59000200	EPOXY CRACK INJECTION	FOOT	34						
59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	2.1				2.1		
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	1370	979			391		
* 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4				4		
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	6	2			4		
63200310	GUARDRAIL REMOVAL	FOOT	1120	721			399		
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	4		4				
66700095	PERMANENT SURVEY MARKERS	EACH	2		2				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8	1.6	1.6	1.6	1.6	1.6	1.6
67100100	MOBILIZATION	L SUM	1	0.5		0.5			
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	0.5		0.5			
70101830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	L SUM	1	0.5		0.5			
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	8	1.6	1.6	1.6	1.6	1.6	1.6
* 72000100	SIGN PANEL - TYPE 1	SQ FT	9				9		
* 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	16				16		
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1040		400		640		
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	1444	976		468			
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	8	4		4			
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	32	16		16			
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	6	2		4			
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	5	2		3			
* 88600100	DETECTOR LOOP, TYPE I	FOOT	26						26
X0323491	SLOPEWALL CRACK SEALING	FOOT	130			130			
X0323557	BRIDGE JOINT SYSTEM (EXPANSION), 1/4"	FOOT	66			66			
X0325244	PREFORMED JOINT STRIP SEAL	FOOT	66			66			
X0324952	DETOUR SIGNING	L SUM	1	0.5		0.5			
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	193			193			
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	66	66					
Z0065700	SLOPE WALL REPAIR	SQ YD	8			8			
©Z0070600	TRAINEES	HOUR	1000	1000					

PLOT DATE = 08/15/80
 FILE NAME = 800414
 REFERENCE = 488F

© 1980
 *SPECIALTY ITEMS

Rev.