

FAP RTL	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	94-F3000-06-BT	COOK	105	6
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	83709	STPE-DOCI(479)	

EARTHWORK SCHEDULE

FROM STATION	TO STATION	{SUITABLE} EARTH EXCAVATION (CU YD)	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (CU YD)	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR 15% SHRINKAGE (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)	TOPSOIL EXCAVATION AND PLACEMENT (CU YD)	TOPSOIL PLACED (CU YD)	TOPSOIL BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)
CRABTREE TRAIL									
0+00	0+74	31		26	0	26	24	3	21
0+74	1+00	5		4	0	4	4	0	4
1+00	2+00	2		2	1	1	3	3	0
2+00	3+00	3		3	4	-1	7	8	-1
3+00	4+00	1		1	5	-4	8	9	-1
4+00	5+00	1		1	2	-1	8	9	-1
5+00	6+00	2		2	3	-1	6	7	-1
6+00	7+00	1		1	4	-3	6	7	-1
7+00	8+00	3		3	2	1	7	8	-1
8+00	9+00	2		2	7	-5	8	9	-1
9+00	10+00	6		5	6	-1	8	8	0
10+00	11+00	13		11	0	11	7	7	0
11+00	12+00	9		8	1	7	6	7	-1
12+00	13+00	26		22	1	21	14	8	6
13+00	14+00	24		20	18	2	21	10	11
14+00	15+00	3		3	19	-16	20	9	11
15+00	16+00	8		7	2	5	18	7	11
16+00	17+00	7		6	5	1	20	8	12
17+00	18+00	6		5	7	-2	20	9	11
18+00	19+00	15		13	3	10	21	9	12
19+00	20+00	15		13	6	7	21	10	11
20+00	21+00	21		18	6	12	21	10	11
21+00	22+00	61		52	0	52	23	13	10
22+00	23+00	29		25	1	24	23	8	15
23+00	23+49	18	25	15	47	-32	25	12	13
23+49	24+00	0	27	0	66	-66	13	11	2
24+00	25+00	0	16	0	70	-70	14	22	-8
25+00	26+00	0		0	77	-77	28	16	12
26+00	27+00	2		2	29	-27	22	10	12
27+00	28+00	20		17	1	16	20	8	12
28+00	29+00	17		14	1	13	19	7	12
29+00	30+00	24		20	0	20	18	7	11
30+00	31+00	15		13	10	3	20	9	11
31+00	32+00	22		19	10	9	21	10	11
32+00	33+00	48		41	0	41	23	12	12
33+00	34+00	35		30	1	29	22	10	12
34+00	35+00	12		10	3	7	20	8	12
35+00	36+00	10		9	2	7	18	7	11
36+00	37+00	18		15	0	15	18	7	11
37+00	38+00	14		12	2	10	19	7	12
38+00	39+00	7		6	2	4	19	7	12
39+00	40+00	25		21	1	20	20	8	12
40+00	41+00	28		24	0	24	20	8	12
41+00	42+00	7		6	4	2	19	8	11
42+00	43+00	3		3	5	-2	20	8	12
43+00	44+00	19		16	2	14	20	8	12
44+00	45+00	16		14	3	11	20	8	12
45+00	46+00	4		3	5	-2	20	8	12
46+00	47+00	3	21	3	8	-5	19	8	11
47+00	48+00	1	11	1	9	-8	21	9	12
48+00	49+00	9		8	3	5	18	8	10
49+00	50+00	13		11	3	8	19	8	11
50+00	51+00	14		12	2	10	19	8	11
51+00	52+00	24		20	0	20	19	8	11
52+00	53+00	25		21	0	21	19	8	11
53+00	54+00	22		19	0	19	19	7	12
54+00	55+00	21		18	0	18	18	7	11
55+00	56+00	13		11	1	10	18	7	11
56+00	57+00	13		11	1	10	18	7	11
57+00	58+00	10		9	2	7	18	7	11
58+00	59+00	9		8	3	5	19	8	11
59+00	60+00	8		7	77	-70	30	20	10
60+00	61+00	7		6	101	-95	40	31	9
61+00	61+90	12		10	22	-12	27	18	9
SUB-TOTAL		862	100	733	676	57	1143	584	559

FROM STATION	TO STATION	{SUITABLE} EARTH EXCAVATION (CU YD)	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (CU YD)	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR 15% SHRINKAGE (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)	TOPSOIL EXCAVATION AND PLACEMENT (CU YD)	TOPSOIL PLACED (CU YD)	TOPSOIL BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)
PAUL DOUGLAS TRAIL									
100+00	100+13	7		6	0	6	7	1	6
100+13	101+00	75		64	3	61	46	9	37
101+00	102+00	57		48	0	48	23	13	10
102+00	103+00	7		6	6	0	20	8	12
103+00	104+00	5		4	10	-6	21	10	11
104+00	105+00	7		6	7	-1	20	9	11
105+00	106+00	8		7	2	5	19	7	12
106+00	107+00	14		12	1	11	19	7	12
107+00	108+00	15		13	1	12	18	7	11
108+00	109+00	7		6	8	-2	20	8	12
109+00	110+00	3		3	8	-5	18	8	10
110+00	111+00	11		9	1	8	18	7	11
111+00	112+00	19		16	1	15	19	8	11
112+00	113+00	17		14	5	9	21	10	11
113+00	114+00	15		13	5	8	21	10	11
114+00	115+00	18		15	2	13	20	9	11
115+00	116+00	20		17	0	17	19	8	11
116+00	117+00	12		10	12	-2	21	9	12
117+00	118+00	5		4	15	-11	21	10	11
118+00	119+00	17		14	9	5	23	14	9
119+00	120+00	25		21	10	11	26	16	10
120+00	121+00	12		10	165	-155	35	29	6
121+00	121+34	0	16	0	64	-64	15	28	-13
121+34	122+00	0	30	0	125	-125	17	13	4
122+00	123+00	26		22	28	-6	23	9	14
123+00	124+00	26		22	3	19	21	12	10
124+00	125+00	10		9	3	6	19	8	11
125+00	126+00	13		11	2	9	19	7	12
126+00	127+00	2		2	6	-4	19	8	11
127+00	128+00	0		0	10	-10	20	9	11
128+00	129+00	22		19	6	13	21	10	11
129+00	130+00	34		29	0	29	20	9	11
130+00	131+00	20		17	2	15	21	9	12
131+00	132+00	8		7	22	-15	23	12	12
132+00	133+00	8		7	23	-16	23	10	13
133+00	134+00	6	5	5	22	-17	21	9	12
134+00	135+00	6	54	5	6	-1	19	7	12
135+00	136+00	6	16	5	6	-1	19	6	13
136+00	137+00	6		5	3	2	18	6	12
137+00	138+00	0		0	14	-14	22	10	12
138+00	139+00	2		2	15	-13	23	10	13
139+00	140+00	87		74	3	71	27	14	13
140+00	141+00	44		37	7	30	23	13	10
141+00	142+00	14		12	7	5	20	9	11
142+00	143+00	19		16	1	15	19	8	11
143+00	144+00	12		10	1	9	18	7	11
144+00	145+00	22		19	0	19	18	7	11
145+00	146+00	15		13	4	9	19	8	11
146+00	147+00	2		2	6	-4	19	8	11
147+00	148+00	17		14	2	12	19	8	11
148+00	149+00	22		19	0	19	19	8	11
149+00	150+00	10		9	2	7	19	7	12
150+00	151+00	7		6	2	4	18	7	11
151+00	152+00	7		6	2	4	17	7	10
152+00	153+00	4		3	3	0	18	7	11
153+00	154+00	14		12	2	10	19	8	11
154+00	155+00	62		53	0	53	23	13	10
155+00	156+00	62		53	0	53	23	12	12
156+00	157+00	13		11	67	-56	26	16	10

ILLINOIS DEPARTMENT OF TRANSPORTATION
DISTRICT NO. 1 SCHAUMBURG

EARTHWORK
SCHEDULE

SCALE NONE
DATE 3/29/06

DRAWN BY RTA
CHECKED BY SMH